# DAM REHABILITATION AND IMPROVEMENT PROJECT (DRIP) Phase II and Phase III

(Funded by World Bank)

1.

# SANDYNALLAH (KAMARAJ SAGAR) DAM

#### **ENVIRONMENT AND SOCIAL DUE DILIGENCE REPORT**



February 2021

Tamil Nadu Generation and Distribution Corporation Limited (TANGEDCO), Tamil Nadu

### **CONTENTS**

		Page No
CHA	PTER 1: INTRODUCTION	
1.1	PROJECT OVERVIEW	1
1.2	SUB-PROJECT DESCRIPTION – SANDYNALLAH (KAMARAJ SAGAR) DAM	2
1.3	IMPLEMENTATION ARRANGEMENT AND SCHEDULE	8
1.4	PURPOSE OF ESDD	8
1.5	APPROACH AND METHODOLOGY OF ESDD	9
СНА	PTER 2: INSTITUTIONAL FRAMEWORK AND CAPACITY ASSESSMENT	
2.1	POLICY AND LEGAL FRAMEWORK	10
2.2	DESCRIPTION OF INSTITUTIONAL FRAMEWORK	10
CHA	PTER 3: ASSESSMENT OF ENVIRONMENTAL AND SOCIAL CONDITIONS	
3.1	PHYSICAL ENVIRONMENT	12
3.2	PROTECTED AREA	13
3.3	SOCIAL ENVIRONMENT	14
3.4	CULTURAL ENVIRONMENT	14
СНА	PTER 4: ACTIVITY WISE ENVIRONMENT & SOCIAL SCREENING, RISK AND	
	IMPACTS IDENTIFICATION	
4.1	SUB-PROJECT SCREENING	15
4.2	STAKEHOLDERS CONSULTATION	18
4.3	DESCRIPTIVE SUMMARY OF RISK AND IMPACTS BASED ON SCREENING	23
СНА	PTER 5: CONCLUSIONS & RECOMMENDATIONS	
5.1	CONCLUSIONS	25
	5.1.1 Risk Classification	25
	5.1.2 National Legislation and WB ESS Applicability Screening	25
5.2	RECOMMENDATIONS	26
	5.2.1 Mitigation and Management of Risks and Impacts	26
	5.2.2 Institutional Management, Monitoring and Reporting	27

# **List of Tables**

Table 4.1: Summary of Identified Risks/Impacts in Form SF 3	17
Table 5.1: WB ESF Standards applicable to the sub-project	25
Table 5.2: List of Mitigation Plans with responsibility and timelines	26
List of Figures	
Figure 1.1: Selected Photographs of Improvement/Intervention area	6
Figure 1.2: Project Area showing major intervention locations	7
Figure 3.1: Land Use and Land Cover Map of 5 Km radius around Dam site	12
Figure 3.2: Protected Areas around Dam site	13
List of Annexure	
Annexure I: Form SF1	28
Annexure II: Form SF2	30
Annexure III: Stakeholder's consultation: List of Participants	33

#### ABBREVIATIONS AND ACRONYMS

AIDS : Acquired Immunodeficiency Syndrome

CA : Conservation Area

CDSO : Central Dam Safety Organisation

CE : Chief Engineer

COVID : Corona virus Disease

CPMU : Central Project Management Unit

CWC : Central Water Commission

DE : Beyond Dam Area

DHARMA : Dam Health and Rehabilitation Monitoring Application

DI : Within Dam Area

DRIP : Dam Rehabilitation and Improvement Project

DSRP : Dam Safety Review Panel
E&S : Environment & Social
EAP : Emergency Action Plan

ESCP : Environmental and Social Commitment Plan
ESDD : Environmental and Social Due Diligence
ESF : Environmental and Social Framework

ESIA : Environmental and Social Impact Assessment
ESMF : Environment and Social Management Framework

ESMP : Environment and Social Management Plan

ESS : Environmental and Social Standard

ESZ : Eco-sensitive zone

FRL : Full reservoir level

GBV : Gender Based Violence

GIS : Geographic Information System
GRM : Grievance Redressal Mechanism

HEP : Hydroelectric Project

HIV : Human Immunodeficiency Virus

IA : Implementing Agency
IB : Inspection Bungalow

IPF : Investment Project Financing
LMP : Labour Management Procedure

MCM : Million Cubic Meters

MDDL : Minimum Draw down Level

MIS : Management Information System

MW : Mega watt

MWL : Maximum Water Level

OHS : Occupational Health & Safety

OHSP : Occupational Health & Safety Management Plan

PA : Protected Area

PAP : Project Affected Person

PDO : Project Development Objective

PE : Physical Environment

PMC : Project Management Consultancy

PPE : Personal Protective Equipment
PST : Project Screening Template

RET : Rare Endangered and Threatened

RFB : Request for Bids SC : Scheduled Castes

SCADA : Supervisory Control and Data Acquisition

SDSO : State Dam Safety Organisation SEA : Sexual Exploitation and Abuse

SEAH : Sexual Exploitation Abuse and Harassment

SEF : Stakeholder Engagement Framework

SEP : Stakeholder Engagement Plan

SF : Screening Format
SH : Sexual Harassment

SPMU : State Project Management Unit

ST : Scheduled Tribes

TANGEDCO: Tamil Nadu Generation and Distribution Corporation

WB : World Bank
WQ : Water Quality

1

# INTRODUCTION

#### 1.1 PROJECT OVERVIEW

The Dam Rehabilitation and Improvement Project Phase II and Phase III (DRIP Phase II & Phase III) initiated by Ministry of Jal Shakti through Central Water Commission, with an objective to cover more States and more dams (after DRIP Phase I) across India to improve the safety and operational performance of these selected dams. This new Scheme will further strengthen the efforts of Government of India beyond ongoing DRIP Phase I. The project would continue to finance structural improvements along with dam safety institutional strengthening which shall break with the prevailing build-neglect-rebuild approach by giving greater emphasis to establishing innovative financing mechanism for regular O&M and dam rehabilitation, enhancing State capabilities to manage these critical assets through institutional strengthening, and introducing risk-informed dam safety management. The project development objective (PDO) is to increase the safety of selected dams and to strengthen institutional capacity for dam safety in participating States. The project components are as follows:

**Component 1:** Rehabilitation and Improvement of Dams and Associated Appurtenances, focusing on structural and non-structural measures at selected project dams. The proposed interventions will include, but not be limited to, around 35-40 kind of rehabilitation activities as done in ongoing DRIP. In addition, all important non-structural activities will also be taken up. In addition to these interventions, the project will require each rehabilitated dam to have basic instrumentation and could also support the development of additional systems to detect and respond to risks promptly, such as flood forecasting systems, early warning systems, data management and analysis software, and standardized dam safety instrumentation (i.e., Supervisory Control and Data Acquisition [SCADA]).

Component 2: Dam Safety Institutional Strengthening, focusing on regulatory and technical frameworks for dam safety assurance. The activities to be carried out will include, but not be limited to, targeted training nationally and internationally to all partner agencies, development of Management Information Systems (MIS) and other programs to capture and analyze data for long-term planning and guiding of dam operations; support to the further development within CWC of the Dam Health and Rehabilitation Monitoring Application (DHARMA) program, support to the revision of existing guidelines on dam safety and preparation of new guidelines, as needed; rapid risk screening of dams, stakeholders consultation meetings for dissemination of prepared emergency action plans, updation of seismic hazard mapping of country, capacity building of academic and central institutions, public outreach programs, construction supervision & quality assurance activities etc.

**Component 3:** *Incidental Revenue Generation for sustainable operation and maintenance of dams;* in order to ensure long term sustainability of operations & maintenance of

existing dams, it is proposed to encourage the dam owners to explore the incidental revenue generation through innovative ideas i.e. Development of tourism, fisheries, secondary sources of power generation (hydel as well as solar), water recreation activities etc. and divert some part of this generated revenue for O&M of a given dam. Few pilot dams can be selected to experiment this innovation.

**Component 4:** *Project Management;* the overall responsibility for project oversight and coordination will rest with the CDSO of CWC. This Organisation will act as the Central Project Management Unit (CPMU). The CPMU will be assisted by a management and engineering consulting firm. Each state and other agency will establish a Project Management Unit (SPMU) attached to the Chief Engineer's (CE) office in charge of the SDSO or any such similar arrangement in power utilities. This Unit will have direct responsibility for the coordination and management of the project at state level.

The primary beneficiaries of the project are the communities that live in dam breach flood inundation areas and the communities that depend on water, irrigation and electricity services provided by the dams that could be compromised by poor dam performance or failure. The Project will be taken up in 19 states covering 300 dams.

#### 1.2 SUB-PROJECT DESCRIPTION – SANDYNALLAH (KAMARAJ SAGAR) DAM

The Sandynallah (Kamaraj Sagar) Dam was constructed across the Sandynallah stream for diverting the storage to the Pykara New Forebay (Glenmorgan Dam) reservoir for increasing power draft at Pykara (Singara), PUSHEP, Maravakandy and Moyar power stations. The construction of the dam was commenced in 1959 and got completed in 1963. The gross capacity of the reservoir is 27.35 MCM. It is a composite dam with masonry portion in the middle and earthen dam on both flanks. The total length of the dam is 237 m, the maximum height from deepest foundation level is 35.88 m. The catchment area of the dam is 44 sq.km.

This Dam is located at 13 Km away from Ooty in Nilgiri District. The full reservoir level for this Dam is E.L+ 2145.51. 2 Nos. of lift type spillway gate of size 12.192 x 3.502 are provided to discharge 312 cumecs of flood water. It receives water from its own catchment and acts as storage reservoir feeding Pykara basin. The water from Sandynallah reservoir is diverted to Glenmorgan dam.

Salient features of the project area are reported below:

	lient features of the project area are repor	•
1	River	Sandynallah stream
2	Location of the Dam	The Sandynallah (Kamaraj Sagar) Dam
		was constructed across Sandynallah
		stream. This Dam is located at 13 Km
		away from Ooty, Nilgiris District,
		Tamil Nadu.
3	Latitude	11° 26′ 32″ N
4	Longitude	76° 39′ 13″ E
5	Total Catchment Area	44.035 km²
6	Original Inflow Design Peak Flood	312 cumec
7	Maximum observed flood peak (m <sup>3</sup> /s)	744 cumec
8	Revised Inflow Design Peak Flood	744 cumec
9	Type of Dam	Composite Dam
10	Scheme work Commenced	1959
11	Works Completed	1963
12	First full impoundment	1963
13	Gross Storage Capacity at FRL	26.62 MCM
14	Live Storage Capacity	23.11 MCM
15	Reservoir Spread Area (km²) at FRL	N/A
16	Length of Dam	237 m
17	Length of Embankment dam	130.45m
18	Length of Masonry/Concrete dam	107.29 m
19	Elevation of top of Embankment Dam	2147.65 m
20	Elevation of top of Masonry/Concrete Dam	2147.65 m
21	Height of Embankment Dam above Lowest	26 m
	River Bed Level	
22	Height of Masonry/Concrete Dam above	35.88 m
	deepest foundation level	
23	Maximum Water Level	2145.51 m
24	F.R.L.	2145.51 m
25	MDDL	2124.46 m
26	Lowest River Bed Elevation	2120.00 m
27	Top width of Masonry/Concrete Dam	3.00 m
28	Top width of Embankment Dam	6 m
29	Spillway	Ogee, Central spillway
	Length of the Spillway	26.98 m
31	Crest level of Spillway	2142.77 m
32	Discharge Capacity of Spillway	312 cumec
32	Discharge Capacity of Spillway Spillway gate	312 cumec Lift 2 Nos.; 12.192 m x 3.502 m size





View of Dam

#### **Proposed Interventions/ Activities and intended Outcomes**

Dam Safety Review Panel (DSRP) constituted by CWC, Government of India has inspected and made a review of Sandynallah (Kamaraj Sagar) Dam on 13/12/2019 and recommended measures to improve the safety and performance of dam and associated appurtenances in a sustainable manner, and also to strengthen the dam safety institutional set-up.

The objectives of the project are to be achieved through investments for physical and technological improvement activities, managerial upgrading of dam operations, management and maintenance, with accompanying institutional reforms. The project will improve the safety and operational performance of dam and mitigate risks to ensure safety of downstream population and property. The following rehabilitation proposals as described in the PST have been formulated based on DSRP recommendations and these proposals form the basis for preparation of present ESDD report.

#### **Structural Rehabilitation Works**

- 1. Standardisation of Earthen bund
  - In the earthen dam, downstream side chute drains along the slope may be provided in the turfed portion. Horizontal chutes also be improved with plastering.
- 2. Special repairs to masonry portion of dam
  - Reaming the drainage shaft
  - Reaming Foundation Shaft
  - Colour washing, Painting & water washing to the dam structure; chipping & Flush Pointing
  - Gauge plate
- **3.** Repairs to shutters
  - Repairs/replacement of shutters with rubber seals
  - Repair/renewal of hoist operating mechanisms of the gates.
  - Painting gates
- 4. Providing electrification to dams
  - lights on the top of the dam, gallery, approach road
  - Replacement of entire electrical system including providing new motor
- **5.** Special repairs/constructions/improvements to buildings including electrification and fencing
  - Construction of Police Guard Room & DG set Room.

#### **Basic Facilities Enhancement**

- **6.** Special repairs to
  - Concrete approach road to dam
  - Screed Concrete on the top of Dam
  - GI chain link fencing around the Dam complex
- **7.** Standby Generators
  - DG set of 63KVA

**Figures** provide photographs of key infrastructure proposed for rehabilitation works and also major interventions locations.



DSRP inspection at Sandynallah dam on 13.12.2019



Downstream side chute drains to be provided in turfed portion




Downstream right flank new approach steps to be provided



Earthen Dam top to be provided with screed concrete at top for drainage



Earthen Dam approach area to be covered with slope protection



Reaming of choked DG vertical and foundation shafts



Scour vent outlet approach steel ladder and platform to be replaced including the sluice valve



Security type chain link fencing to be provided wherever required



Spillway gate stiffener plates & Rubber seals to be replaced



Operating mechanism to be overhauled with replacement of entire electrical system



New Scour vent gate with hoisting mechanism to be provided

Figure 1.1: Selected Photographs of Improvement/Intervention area



Figure 1.2: Project Area showing major intervention locations

#### 1.3 IMPLEMENTATION ARRANGEMENT AND SCHEDULE

As can be seen from the list of activities proposed under dam rehabilitation project; the activities for Sandynallah (Kamaraj sagar) Dam can be floated as one main package consisting of Civil, Mechanical and Electrical works. Works will be carried out by Contractor(s) as these are labour intensive activities and would be completed over a period of 18 months. IA will hire Contractor(s) based on national open competitive procurement using a Request for Bids (RFB) as specified in the World Bank's – Procurement Regulations for IPF Borrowers, July 2016, (Revised August 2018 Procurement Regulations), and is open to all Bidders as defined in the Procurement Regulations. Following is the overall implementation and procurement schedule:

a) Overall Phasing of Project Implementation:
 Proposed Starting of implementation (MM/DD/YYYY): 01/2021
 Proposed Ending of implementation (MM/DD/YYYY): 06/2022

Implementation Duration (months) (MM): 18 months

b) Timeline phasing of implementation:

SI. No.	Description	From (month/year)	To (month/year)	Status of Procurement Process
1	Main package C M E works	01/2021	06/2022	Procurement process will be initiated after obtaining approval of the PST from World Bank.
2	Other Packages	NIL		
3	Procurement – instrumentation, goods, inspection vehicles	NIL		

#### 1.4 PURPOSE OF ESDD

The overall project (DRIP II) was categorized as Moderate as per the internal Environment and Social Risk Classification of the Bank. The Environment and Social Due Diligence has been conducted to use it as a tool for decision-making on the sub-project with the following specific objectives:

- i. To identify, evaluate and manage the environment and social risks and impacts of the sub-project in a manner consistent with the ESSs;
- ii. To adopt a mitigation hierarchy approach to the project's E&S risks i.e. a) anticipate and avoid risks and impacts; b) minimize or reduce risks and impacts to acceptable levels, if not avoidable; c) once risks and impacts have been minimized or reduced, mitigate; and (d) where significant residual impacts remain, compensate for or offset them, where technically and financially feasible;
- iii. To help identify differentiated impacts on the disadvantaged or vulnerable, if any, and to identify differentiated measures to mitigate such impacts, wherever applicable;
- iv. To assess the relevance and applicability of environmental and social institutions, systems, laws, regulations and procedures in the assessment, development and implementation of projects, whenever appropriate; identify gaps, if any exist, and
- v. To assess borrower's existing capacity, gaps therein, and identify areas for enhanced capacity towards management of E&S risks.

vi. Based on the categorization of Environment and Social risks and impacts of the Dam sub-project, to determine whether ESIA is to be carried out using independent third-party agency or a generic ESMP customized to mitigate E&S risks and impacts will suffice.

#### 1.5 APPROACH AND METHODOLOGY OF ESDD

The following approach has been adopted for ESDD:

- Study sub-project information, proposed interventions, their magnitude and locations and carry out assessment of each proposed intervention to identify the magnitude of E&S risk and impacts;
- ii. Review relevance and applicability of national and state legal requirements and Bank's ESF policy, standards and directives and preliminary assessment of applicability of legal requirement and ESS framework (2-8)
- iii. Conduct site visit to understand baseline environment and social settings, proposed activities under the sub-project, their location and sensitivity, if any.
- iv. present key baseline data essential for impact assessment in immediate vicinity area of proposed interventions from secondary sources, such as land-use, protected areas in vicinity, ascertain presence of indigenous (schedule tribe)/vulnerable people, etc.
- v. Undertake institutional assessment to identify existing capacities & relevant gaps to manage E&S risks and impacts
- vi. Conduct preliminary stakeholder consultations to help identify potential stakeholders; to provide information on the proposed interventions; to identify issues and concerns; and ascertain appropriate mechanisms for continued engagement
- vii. Carry out activity wise environment and social screening and identify risks and impacts. Classify the sub-project based on risk level (low, moderate or substantial and high) and recommend commensurate plans/measures to meet identified risks and impacts.

Chapter

2

# INSTITUTIONAL FRAMEWORK AND CAPACITY ASSESSMENT

#### 2.1 POLICY AND LEGAL FRAMEWORK

India has well defined environmental and social regulatory framework. The regulation applicability depends on nature of work and location of work. Broadly legislation can be divided into four categories viz environmental, forests, wildlife conservation and social. The applicability analysis of regulations pertaining to all the above four categories was carried out. The applicability of World Bank ESF comprising, 10 ESSs (ESS1 to ESS10) to the proposed rehabilitation proposals and Standard specific requirements were analyzed. Further, a comparison of national environmental and social regulations versus World Bank's ESS has been carried out along with the gap analysis. Applicability of Indian regulations, World Bank's ESS along with comparison and gap analysis is discussed in ESMF.

Central Water Commission, Ministry of Jal Shakti, Government of India has prepared "Operational Procedures for Assessing and Managing Environmental Impacts in Existing Dam Projects" and is under publication as a guiding document for the dam owners to systematically address in advance the environmental safeguard requirements and have discussed in detail all applicable legal requirement. Reference has been drawn from this document as well, while carrying out applicability analysis.

Indian environmental regulation require environmental clearance for new dam projects specifically for the purpose of hydropower generation and/or irrigation projects and vary with generation capacity for hydropower projects and cultivable command area served by irrigation projects. Forest related clearances become applicable, if new or any modification in any existing project requires diversion of forest land for non-forestry purposes. Wildlife Clearance process gets triggered if the project is in proximity to protected area or activities are proposed within protected or conservation areas.

Therefore, for the proposed dam rehabilitation activities at Sandynallah (Kamaraj sagar) Dam regulatory clearances will not be applicable as per Indian regulations. Other applicable regulatory requirement is discussed in ESMF.

#### 2.2 DESCRIPTION OF INSTITUTIONAL FRAMEWORK

The sub-project will be implemented by Tamil Nadu Generation and Distribution Corporation, Government of Tamil Nadu. TANGEDCO being responsible for power generation, transmission and distribution; have a well-established customer complaint system for power consumer; where they can register their complaints 24x7 on dedicated line (1912). It also has a 24x7 Chairman's complaint cell with phone number and whatsapp numbers. In addition, it has established a Consumer Grievance Redressal Forum, where consumers can register complaints online/manually, directly or through a representative to be resolved within a period of 60 days; with a provision of filing appeal in next 30 days if the complainant is not satisfied with the redressal.

Tamil Nadu Generation and Distribution Corporation Limited do not have in-house expertise to address E&S issues. As per the suggestions of CPMU/CWC, it is proposed to outsource consultancy services of Environmental and Social experts to assist TANGEDCO in resolving E& S issues.

#### Chapter

3


# ASSESSMENT OF ENVIRONMENTAL AND SOCIAL CONDITIONS

Assessment of physical, ecological and socio-economic conditions at dam site and immediate surrounding has been carried out based on secondary information and site observations; as discussed below.

#### 3.1 PHYSICAL ENVIRONMENT

#### Land Use/ Land Cover

The project surrounding area land use and environmental sensitivity was analysed using GIS techniques. Land use/ Land cover map within 5 km radius of dam is presented at **Figure 3.1**. As can be seen from the map, evergreen/semi-evergreen forest, deciduous forest, and agriculture/fallow land dominates the land use in project surrounding area. In addition, there are small patches of scrub forest and crop land; small and scattered settlement and water body (reservoir). However, the project activities will be confined to dam body only and no structural interventions are proposed beyond existing dam boundaries. Four major villages are identified in dam surrounding (within 5 km) viz. Pykara, Hanumapuram, Brook Dale and Karadumund.



[(Source: Digital data on land use/land cover maps using bhuvan prepared by National Remote Sensing Centre (NRSC) with Institute of Remote Sensing College of Engineering Anna University along with further refinement using Google Earth]

Figure 3.1: Land Use and Land Cover Map of 5 km radius around Dam site

#### **Natural Hazards**

Potential of natural hazards such as earthquake have been assessed. Project falls in earthquake zone II, dam design has taken care of this aspect. (Earthquake Zones, viz. Zone II, III, IV and V. Zone II is the least active and Zone V is the most active.)

Original Design Flood of the project at MWL is 312cumec while the revised design flood as worked out by CWC is 744 cumec which is substantially higher. The matter has been reviewed by experts from CWC and by World Bank; and it is observed that since there is absolutely no possibility of building extra spillway or providing auxiliary spillway on the reservoir rim, if the afflux rises above the MWL and encroaches in the free board for a short period of time, it would be acceptable. TANGEDCO has been conducted Flood Routing Study on 16.03.2015 and hence no additional spillway is required for Sandynallah (Kamaraj sagar) Dam.

#### 3.2 PROTECTED AREA

Protected areas near Sandynallah (Kamaraj sagar) Dam have been reviewed to assess the applicability of ESS 6. Mudumalai Tiger Reserve is about 11.2 Km away (shortest aerial distance). Tiger Reserve has 321.00 square kilometres as Core or Critical Tiger Habitat and 367.586 square kilometres as Buffer area and is part of Nilgiri Biosphere Reserve. In addition, lately an Eco-sensitive Zone (ESZ) has also been notified for the protection of tiger reserve. Buffer Zone (including notified ESZ) is about 4 Km from the dam and nearest boundary of Nilgiri Biosphere Reserve is about 7.9 Km from the dam. No rehabilitation work is proposed beyond the dam boundary, which can directly or indirectly impact the protected area, there ESS 6 will not be triggered.




Figure 3.2: Protected Areas around Dam Site

#### 3.3 SOCIAL ENVIRONMENT

The Sandynallah (Kamaraj sagar) Dam is located across the stream Sandynallah (Kamaraj sagar) Dam in the Nilgiris district in the state of Tamil Nadu. The proximity villages' areas i.e. villages which fall within 5 km distance from the dam, are Pykara, Hanumapuram, Brook Dale and Karadumund. There are no Schedule V<sup>1</sup>areas in state of Tamil Nadu. The district is divided into two revenue Divisions namely Coonoor and Gudalur. The district has six tehsils (talukas) namely Coonoor, Kotagiri, Udhagamandalam, Kundah, Gudalur and Panthalur along with 4 Panchayat Unions (Community Development Blocks); Gudalur, Udhagamandalam, Kotagiri and Coonoor.

The economy of the district is basically dependent on non-agricultural activities & resources. A large number of tea processing industries are the major employment generation for the local people in the district. The brief demographic characteristic of the district is given in the table below:

No. of Households	1,97,653	Household Size	04
Total Population	7,35,394	Population (0-6 age)	6 6,799
Male	3,60,143	Boys (0-6 age)	3 3,648
Female	3,75,251	Girls (0-6 age)	3 3,151
Sex Ratio	1042	Sex Ratio (0-6)	985
Population (SC)	2,35,878 (32.08 %)	Population (ST)	32,813 (4.46%)
Male	1,15,917	Male	16,091
Female	1,19,961	Female	16,722
Literates	5,69,647	Literacy Rate (in %)	85.20
Male	2,99,447	Male	91.72
Female	2,70,200	Female	78.98
No. of Workers	3,49,974	Cultivators	15,645 (4.47%)
Male	2,12,172	Agricultural Labours	79,100 (22.60%)
Female	1,37,802	<b>Household Industrial Workers</b>	3,895 (1.11%)
No. of Main Workers	3,18,924	Other Workers	2,51,334 (71.82%)
No. of Marginal Workers	31,050		
		<b>Source:</b> Census of India, 2	2011 (District Handbook)

Schedule tribe population in the district is very limited (4.46%) and are scattered. There are only very few Scheduled Tribe households in the downstream areas and they are mainstreamed in the area with other households. No physical interventions planned in the downstream areas. Therefore, ESS7 is not applicable. Downstream areas including ST households will be taken into account during the preparation of Emergency Action Plan for Pykara Dam.

#### 3.4 CULTURAL ENVIRONMENT

As per list of National Monuments in Tamil Nadu and list of State Protected monuments in Tamil Nadu; there are no protected monuments in and around dam site i.e. within 10 km radius of dam site.

<sup>1</sup>Scheduled Areas are areas in India with a preponderance of tribal population subject to a special governance mechanism wherein the central government plays a direct role in safeguarding cultural and economic interests of scheduled tribes in the area.

Chapter 4

# ACTIVITY WISE ENVIRONMENT & SOCIAL SCREENING, RISK AND IMPACTS IDENTIFICATION

#### 4.1 SUB-PROJECT SCREENING

The sub-project screening was undertaken following a set methodology. Process of risk /impacts identification was done using two step Screening process. Step I identifies the applicable sub-project activities, preconstruction and construction stage's major auxiliary or interventions related risks and impacts within the impact zone. Step II conducts an analysis of extent of risk viz. low, moderate, substantial and high associated with various sub activities related to each activity that was identified through Step I. All these were then summarized to arrive at overall dam sub-project risk category. Description of each step of screening as per formats, and the outcome of each step is given below.

**Step I Screening (using Form SF-1)**: Sub-Project Component, Construction Support Preparatory Intervention related vs Nature of risk/impact

Scoping exercise was carried out to select the applicability of each activity based on the interventions proposed in the sub-project PST. Applicable interventions were further classified based on the location i.e. within dam area or outside the dam area and for each applicable intervention likely nature of risks and impacts has been listed.

Screening indicated that all project components related activities are limited to within the dam area/premises. Due to nature of these activities, likely impacts will be on physical environment in terms of air pollution, noise pollution and waste generation. None of the proposed structural interventions involve acquisition of private land and/or private assets. These activities in no way cause restriction on access to land or use of resources by local communities and there is no economic displacement envisaged due to the sub-project. Activities interfacing with water bodies — river/reservoir may have risk of spillage of chemicals, construction material, and debris leading to water pollution and impacts on fishes.

Pre-construction and construction stage major auxiliary or preparatory intervention are within dam area as well as beyond dam area. Deployment and haulage of heavy machinery, setting up of workshop, operation of concrete mixture and pumps will be within dam area. Other activities such as labour camp and debris disposal will be beyond dam area. Activities involving machinery and equipment will have OHS risks and impacts on physical environment. Transportation of material, debris/silt disposal and labour camp are likely to generate pollution and impact on physical environment.

Project will involve project managers and supervisors, contracted workers — these would also include migrant workers as all the required labour will not be fully supplied locally for a number of reasons, such as worker unavailability and lack of technical skills and capacity. Construction contractors are expected to stay at/near dam, set up construction equipment and machinery near work location at pre-determined/approved sites. Influx of skilled migrant labour, albeit few in numbers, for construction works is likely. The labour will stay outside the dam premises, hence risk of SEA/SH is likely.

Emergency Action Plan, Early Warning System and Flood Forecasting System, etc. would be required to be prepared. In that case, project will reach out to the disadvantaged and vulnerable persons and groups and involve them mainly during implementation. During preparation of EAP, dam break scenario will be simulated and inundation map prepared to delineate the potential risk area in case of an emergency situation. Similarly, during flood release scenario, area inundated will be delineated by simulation. Population in vulnerable areas under different release scenario will be identified and contacted through public consultation meetings. Communities will be made aware about the warning systems and do's and dont's during such scenarios.

Output of this screenings enclosed as **Annexure I**.

**Step II Screening (using Form SF-2)**: All applicable activities identified as having potential risks/impacts that were identified through Step I screening, are further screened for associated sub-activity and evaluated for the extent of risk. Sub-activity's Risk/Impact intensity is further categorised as Low (L), Moderate (M), Substantial (S) or High (H) based on following criteria:

Low : Localized, temporary and negligible

Moderate: Temporary, or short term and reversible under control

Substantial: Medium term, covering larger impact zone, partially reversible

High : Significant, non- reversible, long term and can only be

contained/compensated

Occupational Health and safety is treated as Moderate by default as its risk effect can be managed by adopting defined guidelines.

Analysis of extent of risk/impact for sub-activities resulted in identification of following activities as having Moderate Risk/impact.

- Special repairs to Approach road to dam and Road on top of dam
- Energy dissipation arrangement

All other activities are categorised as low risk activities. None of the activities for this subproject is having substantial or high risk. The outcome of Screening is enclosed as **Annexure II**. In case of GBV/SEAH, this site was assessed as Low risk.

Based on consideration of all the above, summary of Risk/Impact (as per outcome of SF-2) is summarised for major sub-project activities under **Table 4.1below.** 

Table 4.1: Summary of Identified Risks/Impacts in Form SF 3

Project Activity	Environment Risks									Social Ris	ks	
	Air, water, noise, land use, Soil, Resource use	Pollution downstream and upstream	General Ecology	Protected Area (Wild Life Sanctuaries, National Park and other natural habitat even if not protected)	Other RET species (flora and fauna) outside protected areas	Fish and Aquatic life within dam water body	Land	Tribal	Labour	Cultural heritage	GBV/SEAH	OH and Safety to Labour/ Community
Civil (within Dam Boundary)	M	M	L	None	None	L	L	L	M	L	L	M
Hydro Mechanical/Electrical	L	L	L	None	None	L	L	L	L	L	L	M
Instrumental SCADA, surveillance	L	L	L	None	None	L	L	L	L	L	L	L
Road work	М	L	L	None	None	L	L	L	М	L	L	L
Major debris disposal	L	L	L	None	None	L	L	L	Ĺ	L	L	L
Labour camp	L	L	L	None	None	L	L	L	Ĺ	L	L	L

#### **Criteria for Risk Evaluation:**

Low: Localized, temporary and Negligible

Moderate: temporary, or short term and reversible under control

Substantial: medium term, covering larger impact zone, partially reversible

High: significant, non-reversible, long term and can only be contained/compensated

Occupational Health and safety: it will be treated as Moderate by default as OHS effect can be kept controlled and with negligible effect with adoption of defined

guidelines,

#### 4.2 STAKEHOLDERS CONSULTATION

In light of the COVID 19 pandemic, Government of India has announced a country wide lockdown from March 23 till today that constrained holding of consultation meetings. However, to ensure the participation of stakeholders in ESDD preparation and record their views, stakeholders were contacted over phone and their views recorded. Two sets of questions are prepared, one for each category of stakeholders – direct workers and community. Direct workers included Engineers/staff working at dam (present or working from home) – full time or contracted and community stakeholders included local people from vicinity villages.

Stakeholder consultation was conducted as part of environmental and social impact assessments, with a purpose to:

- a. provide initial information to the communities on the proposed project interventions and particularly the non-structural interventions, if any;
- b. Help identify potential stakeholders who are involved at this stage and will be involved a later stage.
- c. assess their responses in understanding the potential risks and prepare mitigation plan to address their concerns.

Stakeholder consultation was made at dam on 09/06/2020. Inputs were taken from permanent staff of the borrower (TANGEDCO) working at dam, and Agricultural workers on the Downstream side of the Dam at Karumulimund village covered in Hullathi Panchayat.



Following is the outcome of the stakeholder consultation exercise. List of participants is enclosed as **Annexure III**.

# A. Interaction with Dam Engineers/Staff

	Questions	Responses provided / Observations
1.	Please confirm whether all proposed structural rehabilitation activities for this dam are limited to dam compound only or any activities are proposed beyond dam complex like catchment area treatment plan, stabilization of reservoir rim area, slope stabilization, de-silting etc.? Please specify if any possibility of local community interference exists during the implementation of rehabilitation measures; including stakeholder's consultation meetings planned for dissemination of emergency action plans which is a non-structural measure.	The proposed structural Rehabilitation activities are within the dam compound only, Providing the chute drain works on the downstream side both flanks only involved. No desilting work involved in this dam. This dam is located in the Reserve forest area and there is no possibility of community interference during the implementation of Rehabilitation work including stack holders consultant meeting.
2.	Is there any unsettled issues (legacy) related to displacement or resettlement, pending since time of dam construction? If yes, please give a brief detail.	The dam is located in the Reserve forest area; there were no displacement and resettlement issues during construction.
3.	Any unauthorized encroachers or squatters living within the dam premise? If yes, are these not a threat for dam security and dam premise, any official action taken in the past, does the state government have legalized these squatters and these have full right in the property of dam authorities.	No encroachers (or) squatters within the dam premises so far.
4.	What is the proposed institutional arrangement to deal the Environment and Social activities within the scheme i.e. inhouse team of experts/hired agency or individual experts?	Dealing of Environmental and social activity by CWC environmental experts.
5.	Who will be in charge of E&S related activities at dam site and at SPMU level?	Dam site: Executive Engineer/Civil/DRIP/Kundah SPMU: Executive Engineer/Civil/DRIP/Madurai
6.	How do communities contact dam officials? Is there any existing mechanism known to communities to contact dam officials (through telephone/mobile/e-mail/official website?	Through telephone and mobile.
7.	What is existing mechanism to communicate with downstream communities/public on unregulated releases of water during high flood time siren/written communication to district authorities/ telephone/mobile/text	<ol> <li>By siren.</li> <li>Written Communication to the District Collector.</li> <li>Advance intimation to the public/ downstream communities through mobile.</li> </ol>

messages or any other mode of communication?	
8. How do you ensure that downstream community is fully aware of the above existing mechanism?	Already educated the downstream community - by Department officials
9. Are there women employees at the dam site?	P. Sinduja, Assistant Engineer/ Civil/ Pykara T.R.Eswari /Switch Board Attender /Pykara
10 Is there any existing Grievance Redressal Mechanism (GRM) within the department to address any kind of grievance/complaints by general public?	Yes Executive Engineer/Civil/DamSafety-I/Chennai @ HQrs Executive Engineer/Civil/DRIP/Madurai @ Field.
11 Details of any grievances received lately related to this new Scheme?	-Nil-
12 Is dam premise a restricted area or has open access to general public?	Access to Dam area – Fully restricted.
13 Are there tribal's living in the surrounding area of dam complex? Which tribes are these? Please give brief detail.	No Tribal's living in the surrounding dam area.
14 Does the dam have any tourism/water recreation facilities? If yes, how many approximate tourist visits annually, annual revenue generated, whether any portion of this generated revenue is diverted to regular O&M of this dam.	No
15 Do you engage any local labours for routine dam maintenance work? If yes, what is the process of engaging these locals for work at dam, whether through Government approved contractor or hired individually?	Routine Dam maintenance works are being done by department staff only.

# **B.** Interaction with Local Community

Questions	Responses provided / Observations
How many villages are in immediate downstream vicinity?	There is no village on the downstream side of the Dam. Only Five families are living on the downstream side of Dam. which is 2 Km away from the Dam location.
Are they dependent on dam in any way for their livelihood?	No, they are not dependent on the dam. All the basic amenities required are fulfilled by the Solur Panchayat.

3.	Does any of these villages were displaced and rehabilitated during the construction of Sandynallah (Kamaraj Sagar) Dam. Is there any pending compensation issues?	Dam area is fully covered in Reserved forest area.  Displacement and Rehabilitation does not arise.
4.	Is there any R&R affected person known to you who is currently working with the dam authorities? If so, in what capacity (employee/direct worker/contractor)	-NO-
5.	Are you aware of any fishing communities living immediately downstream of dam whose livelihood are directly linked with the fishing activities of this dam?	-NO-
6.	Are you aware of fishing working seasons, revenue earning, any access to general public for fishing, any suggestion etc.	-NO-
7.	Are you aware of local women affected in any way by dam operations?	-NO-
8.	Are you aware of any early flood warning system for this dam, or any other system wherein downstream communities getting regular update during flood season for any uncontrolled release of water?	Yes, The warning siren is already provided.
9.	Are you aware of any dam related incident happened in the past wherein some loss of life encountered? If yes, brief summary may be given	-NO-
10.	If you have to contact the dam authorities; how will you contact, through telephone/mobile/e mail/personally?	By Telephone, Mobile and in Person.
11.	In the past, on any occasion, did you contact dam authorities for any specific reason affecting public in general? If so, how did you contact and how was the response of dam authority?	Such situation did not arise.
12.	Give your views about Sandynallah dam, how this dam is helping Country, State, district or local communities in meeting its objectives, any specific concern can also be given?	The Sandynallah dam storage water being used for Power Generation of Pykara (Singara), Pykara Ultimate Stage Hydro Electric Power House (PUSHEPH), Maravakandy and Moyar.
13.	(a) Are you aware of any document named Emergency Action Plan (EAP) of the dam?	-NO-

(b) If yes, do dam authorities conduct any annual mock drill or consultation meeting on dam site and invite all stakeholders to inform about various protocols in place and consequences in case dam fails?	Consultation meeting to be conducted.
(c) In future, during stakeholder's consultation meeting, would you like to be a part of these consultation and mock drill activities to be conducted by dam authorities?	YES
(d) If yes, how to contact you, please give the corresponding address along with all details to receive the official communication.	<ol> <li>Thiru. M. Sivaji,(former)         S/o. Malliarasu,         Karumullimund,         Kamaraj Bridge         HullathiPanchayath, The Nilgiris.         Ph No: 9159463582.</li> <li>Thiru. N. Oveker Kuttan,         S/o.Naran,         Karumullimund,         Kamaraj Bridge         HullathiPanchayath, The Nilgiris.         Ph No: 9487082727.</li> <li>Tmt. C. Poonjolai,         W/o. (late)Chinnan,         Karumullimund,         Kamaraj Bridge         HullathiPanchayath, The Nilgiris.</li> </ol>
14. Are you a regular follower of official website of dam authorities as a general public, in case you are a contractor, do you follow various tenders notices being invited for various maintenance of this dam?	-NO-
15. Any suggestion to improve overall system by dam authorities in any way, please give in brief?	Proposed Dam Rehabilitation and Improvement works as per DSRP recommendations shall be carried out as a safety measure.

Following is the summary outcome of the stakeholder consultation:

- 1. Sandynallah surplus water let in to Sandynallah Diversion weir which is 6 Km away from the Dam and surplus water passes through Reserved Forest only.
- 2. On downstream side of the Dam near by about 35 Acres of agricultural land are being maintained by the local peoples with their own water source. They are not depend on the surplus water. No further villages on the downstream side of the Dam.

#### 4.3 DESCRIPTIVE SUMMARY OF RISKS AND IMPACTS BASED ON SCREENING

Based on the above screening analysis, potential impacts and risks from the sub-project are summarised below:

#### **Environmental Impacts and Risks**

- Environment risks and impacts, as assessed above, for various project activities under this sub-project are categorised as Low and Moderate due to localised nature of proposed activities i.e. activities remain limited to dam area except for labour camp and muck/debris disposal.
- 2. Execution of civil and hydro-mechanical work within dam body will generate localised impacts on physical environment and resource use; pose risk of exposure of workers requiring personal protective equipment (PPE) use.
- Civil work interfaced with water body especially such as repairs to revetment/rip-rap in u/s face work on upstream face of dam pose risk of water pollution and impact on fish fauna.
- 4. Construction and demolition waste and muck require careful disposal at pre-identified and approved site to minimise the risk of pollution on this count.
- 5. No impact on general ecology is envisaged.

#### Social Risk and impacts

- 1. As the interventions are within the dam premises and on the dam structure, there shall be no adverse impacts on land and assets due to any sub-component or sub-activities
- 2. The dam is not located in the Schedule V area. Though are Scheduled Tribes households in the vicinity, these are mainstreamed into the overall society and do not meet the characteristics outlined in ESS 7. There will be no physical interventions.
- 3. Influx of migrant labour will be low as these works require only few but very skilled labour Also these workers will mostly operate from labour camps within the dam premises/proximity and hence there would be minimal interface with communities and therefore significantly lower SEAH/GBV risks.
- 4. Waste generation from labour colony can pollute drinking water sources of community, risk is low and can be mitigated by providing adequate sanitation facilities.
- 5. No impacts are envisaged on cultural heritage as works shall not be undertaken in their vicinity or result in any impact.
- 6. Labour related risk would include:
  - Safety issues while at work like injuries/accidents/ fatalities leading to even death, while at work; Occupational health and safety risks due to exposure of workers to unsafe conditions while working at heights, working using lifts, handling of equipment and machinery, exposure to air and noise pollution etc. will be addressed through OHS guidelines.
  - > Short terms effects due to exposure to dust and noise levels, while at work
  - ➤ Long term effects on life due to exposure to chemical /hazardous wastes
  - Inadequate accommodation facilities at work force camp, including inadequate sanitation and health facilities
  - Sexual harassment at work

- ➤ Absence or inadequate or inaccessible emergency response system for rescue of labour/workforce in situations of natural calamities.
- ➤ Health risks of labour relating to HIV/AIDS and other sexually transmitted diseases
- Non-payment of wages
- ➤ Discrimination in Employment (e.g. abrupt termination of the employment, working conditions, wages or benefits etc.)
- Unclear terms and conditions of employment
- ➤ Discrimination and denial of equal opportunity in hiring and promotions/incentives/training opportunities
- > Denial for workers' rights to form worker's organizations, etc.
- ➤ Absence of a grievance mechanism for labour to seek redressal of their grievances/issues.

5

# CONCLUSIONS AND RECOMMENDATIONS

#### 5.1 CONCLUSIONS

#### 5.1.1 Risk Classification

As per the ESDD exercise, risk/impacts that have been identified relate to Water Quality, Occupational Health, Physical Environment, labour and SEAH/GBV. The summarised environmental and social risks of identified activities, with level of risk, are presented in previous chapter. These risks are low to moderate and localised, short term and temporary in nature which can be managed with generic/standard ESMP and guidelines. Environment risks of air, water, noise, land use, soil and resource use for some of the activities as well as social risks of labour and OHS to labour/community is Moderate. Environment risks of pollution downstream and upstream are categorised as Moderate due to interface with water bodies. Environmental risk relating to Labour camp has been flagged as Moderate on environment.

Hence, the overall risk of this sub-project Dam is categorized as Moderate.

#### 5.1.2 National Legislation and WB ESS Applicability Screening

The applicability analysis of Geological and regulatory framework indicates that while, there are various legislations which will have to be followed by the contractor for the protection of environment, occupational health and safety of workers and protection of workers and employment terms. None of Indian legislation is applicable warranting obtaining clearance prior to start of construction/improvement work.

Four ESS standards are found relevant to this sub-project as per reasons given in **Table 5.1** below:

Table 5.1: WB ESF Standards applicable to the sub-project

Relevant ESS	Reasons for Applicability of the standard
ESS2: Labour and Working	Direct workers, Contracted workers(for civil and hydro-
Conditions	mechanical works) and Community workers (likely to be
	engaged for EAP and other non-structural interventions)
ESS3: Resource Efficiency,	Civil and hydro-mechanical/electrical work including
Pollution Prevention and	resource consumption requiring protection of physical
Management	environment and conservation of resources
ESS 4: Community Health and Safety	Transportation of material, labour camp near habitation; and accidental risk during repair /improvement work and
	also leading to SEA/SH GBV risk
	Community involvement during EAP preparation
ESS 10: Stakeholder	For engagement of stakeholders in all interventions
Engagement Plan	

#### 5.2.1 Mitigation and Management of Risks and Impacts

Since risks and impacts are low to moderate category, a generic and standard guidance in accordance with the ESMF shall be followed. It shall cover the following aspects:

- a. IA shall customise the generic Environmental and Social Management plan (ESMP) that has been provided in the Environmental and Social Management Framework (ESMF) and make it part of bid document for effective adherence by contractors.
- b. It is recommended that ESMP provides due measures for protection of environment quality and resource conservation (during handling of resources) in line with ESF standard ESS3 requirements. Similarly, any impacts identified has to be conserved. Likewise, due attention has to be given to Occupational Health and Safety of workers and community in line with the requirements of ESS4 and World Bank Group guidelines on Occupational Health and Safety (OHS). Hence SPMU/IA shall prepare a standard ESMP in line with outline provided in the ESMF and ensure its adherence by contractor. The standard ESMP will address the following:
  - Gender Based Violence or SEA/SH related actions (ESS1)
  - Labour Management Procedure (ESS2)
  - Resource Efficiency and Pollution Prevention (ESS3)
  - Community Health and Safety (ESS4)
  - Stakeholders Engagement Plan (ESS10)
- c. Contractor shall submit BOQ as per ESMP of the sub project and will also include environmental and social budget as part of bid submission.

Mitigation plans to meet requirements for relevant Standards with responsibility and stages are given in **Table 5.2** below:

Table 5.2: List of Mitigation Plans with responsibility and timelines

WB-ESS Triggered	Mitigation Instrument	Responsibility	Timelines
ESS2: Labour and Working Conditions	• LMP • OHS	SPMU/IA	Before mobilization of contractor
ESS 4: Community Health and Safety	GBV/SEAH	SPMU for GBV/SEAH	GBV/SEAH by appraisal
ESS3: Resource Efficiency, Pollution Prevention and Management	<ul> <li>ESMP</li> <li>Muck Management Plan</li> <li>Resource Conservation Plan</li> </ul>	SPMU/IA	Before mobilization of contractor
ESS 10: Stakeholder Engagement Plan	SEP in accordance with project SEF	SPMU/IA	By negotiation

IA shall disclose the finalised ESDD, ESMP, ESCP and other related plans on its website after formal approval from CPMU. Executive summary of proposed ESMP based on ESDD shall be translated and disclosed in local language.

#### 5.2.2 Institutional Management, Monitoring and Reporting

ESMP will be developed by SPMU/IA and will be part of the bid document of the sub project and shall be shared with CWC by SPMU for their review/ endorsement and approval. SPMU/IA shall designate a Nodal Officer to coordinate and supervise E&S activities. The SPMU will hire the qualified staffs to support management of E&S risks including Environmental Expert, Social Expert for ensuring compliance with the Bank's ESF and ESS's and ensures that these activities shall be implemented as per the procedures. Specifically, as included in the ESCP, every SPMU shall be strengthened from environmental and social risk perspective during implementation of the subprojects. A dedicated Environmental and Social staff with requisite skill shall be placed in the SPMU and will be utilized to enable (a) development/review of ESDD of each sub project either through an agency or in house, (b) E and S staff will coordinate to hire consultants where ESDDs suggest a high risk for undertaking detailed ESIA, (c) preparation of environmental and social management plans (ESMPs) based on type of risks as well subsequent implementation of mitigation measures during implementation. SPMU/IA will hire experts from outside department with relevant experience. These E&S experts will work in coordination with Project Management Consultancy (PMC) contracted by CPMU – CWC.

SPMU/IA shall advise contractors about applicable legislative requirements and ensure that contractors fully comply with applicable requirements and submit compliance reports to SPMU/IA on quarterly basis. SPMUs will share regular implementation status of ESMPs to CWC and The World Bank in line with Environmental Social Commitment Plan (ESCP) on quarterly basis.

SPMU/IA shall establish and operationalized a grievance mechanism to receive and facilitate resolution of complaints and grievances, from the communities and other stakeholders including implementation partners. Grievance redress mechanism will be designed to address concerns and complaints promptly and transparently with no impacts (for any complaints made by project affected people (PAPs). GRM will work within existing legal and cultural frameworks and shall comprise project level and respective State level redress mechanisms.

PMC for the project will have sufficient staff with skills on Environment and Social aspects. Awareness raising and capacity building on the new Environmental and Social Framework (ESF) need to be carried out for the environment and social staff engaged and this will be an area of continued focus, with a view to generate awareness at to dam level. Project Management Consultancy (PMC) shall coordinate with CWC for approval, documentation, disclosure and implementation of these ESMPs in line with project ESMF and ESCP.

Overall, the proposed activities within this Dam sub-project have low to moderate risks resulting in the overall sub-project to be categorized as Moderate risk category. These risks and impacts can be effectively mitigated with effective implementation of mitigation plans by SPMU/IA, Contractors and monitoring by PMC, SPMU and CWC

# Annexure - I: Form SF1

SI. No	Project Component	Applicable (A), Not Applicable (NA)	Environment and Social Risk Associated within dam area (DI), Beyond Dam Area (DE)	Likely Nature of Risk/Impact Water Quality (WQ), Fisheries(F), Conservation area(CA), Protected Area (PA), Ecological (E), Occupational Health (OH), Physical Environment (PE), Cultural (C), Tribal presence (T), impact on private land/assets/encroachers/squatters (LA), Labour (L), GBV risks (G), (Write
				whichever is applicable)
1	2	3	4	5
Α	Nature of Project Component Related			
1	Reservoir Desiltation	NA		
2	Major structural changes – Spillway construction (Improving ability to withstand higher floods including additional flood handling facilities as needed.)	NA		
3	Structural strengthening of dams to withstand higher earthquake loads	NA		
4	Structural Improvement/Repair work-upstream of Dam site (interfacing dam reservoir) (like Repairs to revetment/rip-rap in u/s face)	A	DI	WQ, F, OH, PE, L, G
5	Structural Improvement/Repair work -Downstream of Dam site (with no interfacing with dam reservoir) (like energy dissipating arrangement etc.)	A	DI	WQ, OH, PE, L, G
6	Re modelling earth dams to safe, stable cross sections	NA		
7	Hydro-mechanical/electrical activities with interface with dam reservoir	А	DI	OH, WQ, L, G
8	Hydro-mechanical/ electrical activities Downstream of Dam site (with no interfacing with dam reservoir)	NA		
9	Instrumentation, General lighting and SCADA systems	Α	DI	OH, L
10	Basic Facilities (like access road improvement, renovation of office, etc)	А	DI	OH, PE, L, G
11	Utility installation like standby generator, or setting up solar power systems	Α	DI	OH, L
12	Painting Work	Α	DI	WQ, OH, L
13	Water recreation activities	NA		
14	Tourism Development	NA NA		
15 16	Solar power/floating solar List any other component not	NA		
10	listed above			
i	Jungle clearance	Α	DI	E, L, G

SI. No	Project Component	Applicable (A), Not Applicable (NA)	Environment and Social Risk Associated within dam area (DI), Beyond Dam Area (DE)	Likely Nature of Risk/Impact Water Quality (WQ), Fisheries(F), Conservation area(CA), Protected Area (PA), Ecological (E), Occupational Health (OH), Physical Environment (PE), Cultural (C), Tribal presence (T), impact on private land/assets/encroachers/squatters (LA), Labour (L), GBV risks (G), (Write whichever is applicable)
1	2 Pre-construction and	3	4	5
В	construction stage major auxiliary or preparatory intervention			
1	Acquisition of forest land involved	NA		
2	Taking of private land (including physical or economic displacement, impact on livelihood; temporary loss of business)	NA		
3	Major Borrow materials requirement involved	NA		
4	Major Quarry materials requirement involved	NA		
5	Blasting involved	NA		
6	Resettlement and Rehabilitation	NA		
7	Types of project workers (Direct, Contracted, Community Workers (or Volunteers i.e. for EAP implementation)	А	DE	L, G
8	Labour Camp involved (location within dam premises or outside)	Α	DE	WQ, PE, L, G
9	Migrant labour likely to be involved	Α	DE	L, G
10	Heavy machinery to be deployed and related maintenance workshop set up involved	А	DI	OH, PE, L, G
11	Hot mix plant Requirement	NA		
12	Concrete mixture and heavy pumps to be deployed	Α	DI	OH, PE, L, G
13	Temporary land acquisition involved	NA		
14	Temporary disruption to access, livelihoods	NA		
15	Tree felling/ vegetation clearance involved	NA		
16	Haulage of machinery involved	Α	DI	OH, PE, L, G
17	Major Debris Disposal involved	Α	DE	PE, L, G
18	Major Transport of materials involved	Α	DE	PE, L, G
19	Utility shifting involved	NA		
20	Discharge of reservoir water ( lowering of reservoir water involved)	NA		
21	List any other not listed above			

# Annexure – II: Form SF2

SI. No	Applicable Sub-Project Component/ Construction preparatory Work related Sub activity ( s per SC-1)	Nature of Risk (Conforming to Column 5 of SF- 1) and nature of sub activity	Elaborate cause (risk) and its effect (Impact) on environment /social	Risk/Impact intensity for each type of risk/impact Low (L), Moderate (M), Substantial (S), High ( H)
1	2	3	4	5
Α	Project Component Related			
1.	Structural Strengthening/Improvement/Repair work - upstream of Dam site			
а	Repairs to revetment/rip-rap in u/s face	WQ, F, OH, PE, L, G	Air pollution, noise pollution, risk of reservoir water contamination and impact on fishes, generation of construction debris, Occupational health and safety risk due to working on upstream face of dam, labour and GBV risk	L
b	Special repairs to masonry portion of dam  • Reaming the drainage shaft	WQ, OH, PE, L, G	Air pollution, noise pollution, water pollution, Occupational health and safety risk, labour and GBV risk	L
	Jungle clearance	E, L, G	Impact on ecology, labour and GBV risk	L
2.	Structural Improvement/Repair work -Downstream of Dam site (with no interfacing with dam reservoir) (like repair of parapet walls, damage spillway crest, downstream training walls, etc.)			
а	Energy dissipation arrangement	WQ, OH, PE, L, G	Air pollution, noise pollution, water pollution, generation of construction waste/silt, Occupational health and safety risk, labour and GBV risk	M
b	Colour washing, Painting & chipping, Water washing and Pointing	WQ, PE, L, G	water pollution, hazardous waste, Labour and GBV risk	L
С	<ul> <li>Special repairs to</li> <li>Approach road to dam</li> <li>Road on top of dam</li> </ul>	OH, PE, L, G	Air pollution, noise pollution, construction debris, Occupational health and safety risk	M

SI. No	Applicable Sub-Project Component/ Construction preparatory Work related Sub activity ( s per SC-1)	Nature of Risk (Conforming to Column 5 of SF- 1) and nature of sub activity	Elaborate cause (risk) and its effect (Impact) on environment /social	Risk/Impact intensity for each type of risk/impact Low (L), Moderate (M), Substantial (S), High ( H)
1	2	3	4	5
d	Special repairs/constructions/improvements to buildings including electrification and fencing  • Police Guard Room & DG set Room	OH, PE, L, G	Air pollution, noise pollution, construction debris, Occupational health and safety risk	L
e	Painting gates	OH, PE, L, G	water pollution, hazardous waste, Labour and GBV risk	L
3.	Hydro-mechanical/Electrical activities Downstream of Dam site (with no interfacing with dam reservoir)			
а	Supply and erection of entrance gate and Gauge plate	PE, L, G	waste generation from removed parts, Labour& GBV risk	L
	Repairs to shutters  • Repairs/replacement of shutters with seals • Repair / renewal of hoisting arrangements	PE, L, G	waste generation from removed parts, Labour & GBV risk	L
4.	Instrumentation, General lighting and SCADA systems			
а	Providing electrification to dams  • lights on the top of the dam, gallery, approach road  • Dam Electrification	OH, PE, L, G	Occupational health and safety risk due to electrical work, waste generation from removed parts and packing material, labour and GBV risk	L
В.	Pre-construction and construction stage major auxiliary or preparatory intervention			
1	Types of project workers (Direct, Contracted, Community Workers (or Volunteers i.e. for EAP implementation)	L, G	GBV risk due to involvement of workers and local population	L
2	Labour Camp involved (location within dam premises or outside)	WQ, PE, L, G	Wastewater generation from domestic activities, waste generation, GBV risk within labour and involving community.	L
3	Migrant labour likely to be involved	L, G	Migrant labour having low degree of interface with community	L
4	Likely interface of Workers with communities	L, G	Risk of GBV due to labour interaction	L

SI. No	Applicable Sub-Project Component/ Construction preparatory Work related Sub activity ( s per SC-1)	Nature of Risk (Conforming to Column 5 of SF- 1) and nature of sub activity	Elaborate cause (risk) and its effect (Impact) on environment /social	Risk/Impact intensity for each type of risk/impact Low (L), Moderate (M), Substantial (S), High ( H)
	Σ	3	with community	3
5	Heavy machinery to be deployed and related maintenance workshop set up involved	OH, PE, L, G	Heavy machinery will be deployed for structural measures - OH risk due to machine handling, waste, wastewater and air emissions from machines operations, Labour	L
			& GBV risk	
6	Concrete mixture and heavy pumps to be deployed	OH, PE, L, G	Concrete mixture and pumps will be deployed for road repair and other civil works and de- watering - OH risk due to machine handling, waste generation, wastewater and air emissions from operations, Labour &GBV risk	L
8	Haulage of machinery involved  Debris/Silt Disposal involved	OH, PE, L, G	Machines will be hauled from different location and brought to site; OHS risk during loading/unloading and air and noise pollution during transportation, labour and GBV risk Debris will be	L
			generated from various activities - OH risk during debris handling, air and noise emissions from debris handling and transportation, water pollution risk due to debris finding its way to water body, and GBV risk due to labour involvement	

SI. No	Applicable Sub-Project Component/ Construction preparatory Work related Sub activity ( s per SC-1)	Nature of Risk (Conforming to Column 5 of SF- 1) and nature of sub activity	Elaborate cause (risk) and its effect (Impact) on environment /social	Risk/Impact intensity for each type of risk/impact Low (L), Moderate (M), Substantial (S), High ( H)
1	2	3	4	5
9	Major Transport of materials involved	OH, PE, L, G	Material will be transported from various vendors and suppliers to site for civil, hydro-mechanical work and instrumentation - OH risk during material handling, loading and unloading; ,air and noise emissions from transportation, Labour and GBV risk	L

**Criteria for Risk Evaluation:** 

Low: Localized, temporary and Negligible

Moderate: temporary, or short term and reversible under control

 ${\bf Substantial: medium\ term\ ,\ covering\ larger\ impact\ zone,\ partially\ reversible}$ 

High: significant, non-reversible, long term and can only be contained/compensated

Occupational Health and safety: it will be treated as Moderate by default as OHS effect can be kept controlled and with negligible effect with adoption of defined guidelines,

# **Annexure III: Stakeholder's consultation: List of Participants**

SI. No.	Name	Relation with Dam – Staff, contractor, worker, full time/part	Mobile Number	Address (at least village name)
		time, local, NGO		
1.	P.Rajadhorai	Executive Engineer/ Civil/DRIP/Kundah	9445360725	Kundah Upper Camp
2.	M.Kathiresan	Assistant Executive Engineer/ Civil/DRIP/Glenmorgan	9445360734	Pykara Camp
3.	P. Sinduja	Assistant Engineer/ Civil/Generation Circle/Pykara	8940209754	Pykara Camp
4.	T.R.Eswari	Switch Board Assistant / Generation Circle/Pykara	9751057111	Glenmorgan Camp
5.	M. Sivaji,(farmer)	Public in Karumullimund .	9159463582.	S/o. Malliarasu, Karumullimund , Kamaraj Bridge HullathiPanchayat, The Nilgiris.
6.	N. Oveker Kuttan,	Public in Karumullimund ,.	9487082727.	S/o.Naran, Karumullimund , Kamaraj Bridge Hullathi Panchayat, The Nilgiris
7.	C.Poonjolai,	Public in Karumullimund ,.	-	W/o. (late)Chinnan, Karumullimund , Kamaraj Bridge Hullathi Panchayat, The Nilgiris.