

ENVIRONMENT ASSESSMENT REPORT(EA)

For

**UG Electrical Cable Works Covering Cuddalore Municipality
(Vinayaga Nagar, Semmandalam ,Varadharajan Nagar, Annandale,
Sorakalpattu, Seetharam Nagar , Pudupalayam, R.P. Nagar, Kamaraj
Nagar, Devanampattinam, Sothikkuppam, Sivanandhapuram,
Sellankuppam, VSR Palayam etc settlements of Cuddalore
Municipality (Package 2)**



Tamil Nadu Distribution and Generation Corporation Ltd. (TANGEDCO)



Submitted By N_Arc Consulting

**N_Arc Consulting
402, 403 Devika Tower,
Nehru Place
New Delhi - 110019**

**26 May, 2016
Rev - 02**

ENVIRONMENT ASSESSMENT REPORT(EA)

For

**UG Electrical Cable Works Covering Cuddalore Municipality
(Vinayaga Nagar, Semmandalam ,Varadharajan Nagar, Annandale,
Sorakalpattu, Seetharam Nagar , Pudupalayam, R.P. Nagar, Kamaraj
Nagar, Devanampattinam, Sothikkuppam, Sivanandhapuram,
Sellankuppam, VSR Palayam etc settlements of Cuddalore
Municipality (Package 2)**



CONTENTS

| | |
|---|-----------|
| Chapter 1 Environment Assessment Background..... | 5 |
| 1.1 INTRODUCTION CDRRP | 5 |
| 1.2 UNDERGROUND CABLE NETWORK - TANGEDCO PACKAGES | 7 |
| 1.3 ENVIRONMENTAL ASSESSMENT AND EMP FOR PACKAGE -2, CUDDALORE TOWN | 10 |
| 1.4 STRUCTURE OF THE REPORT | 10 |
| Chapter 2 Project Descriptions (Package 2) | 12 |
| 2.1 LOCATION | 12 |
| 2.2 DETAILS OF PROJECT (PACKAGE-2) | 12 |
| 2.3 KEY FEATURES IN THE PROJECT (PACKAGE-2) AREA..... | 13 |
| CHAPTER 3 POLICY, LEGAL AND REGULATORY FRAMEWORK..... | 16 |
| 3.1 NATIONAL/STATE POLICIES AND LEGAL FRAMEWORKS | 16 |
| 3.2 WORLD BANK POLICIES..... | 19 |
| 3.3 REQUIRED APPROVAL, CONSENT AND PERMITS | 19 |
| CHAPTER 4 ENVIRONMENTAL BASELINE..... | 23 |
| 4.1 METEOROLOGY | 23 |
| 4.2 PHYSICAL ENVIRONMENT | 23 |
| 4.2.1 LAND RESOURCES | 23 |
| 4.2.2 AMBIENT AIR QUALITY | 24 |
| 4.2.3 WATER RESOURCES | 25 |
| 4.2.4 NOISE ENVIRONMENT..... | 25 |
| 4.3 BIOLOGICAL ENVIRONMENT | 26 |
| 4.3.1 FLORA | 26 |
| 4.3.2 FAUNA..... | 26 |
| 4.4 SOCIO-ECONOMIC ENVIRONMENT | 27 |
| 4.4.1 DEMOGRAPHIC FEATURES CUDDALORE MUNICIPALITY | 27 |
| 4.4.2 HOUSEHOLDS AND POPULATION UNDER PROJECT (PACKAGE-2) | 28 |
| CHAPTER 5 ANTICIPATED ENVIRONMENTAL IMPACTS..... | 29 |
| 5.1 DURING CONSTRUCTION PHASE..... | 29 |
| 5.1.1 PHYSICAL ENVIRONMENT | 29 |
| 5.1.2 BIOLOGICAL ENVIRONMENT..... | 31 |
| 5.2 DURING OPERATION PHASE..... | 31 |
| 5.2.1 PHYSICAL ENVIRONMENT | 31 |
| 5.2.2 BIOLOGICAL ENVIRONMENT..... | 31 |
| CHAPTER 6 ANALYSIS OF ALTERNATIVES | 32 |
| 6.1 NO PROJECT ALTERNATIVE | 32 |
| 6.2 ELECTRICAL UG CABLE ROUTE ALTERNATIVES | 33 |
| 6.3 ELECTRICAL UG CABLE ROUTE ALTERNATIVE WITHIN ALTERNATIVE II CORRIDOR..... | 33 |
| 6.4 ALTERNATIVES FOR RIVERS/WETLAND AND RAILWAY LINE CROSSING | 34 |
| 6.5 ALTERNATIVES TO MINIMISE TREE CUTTING / IMPACTS OF TREES..... | 35 |
| 6.6 ALTERNATIVES FOR REUSE AND WASTE MINIMIZATION | 35 |



| | |
|---|-----------|
| CHAPTER 7 MITIGATION MEASURES | 36 |
| 7.1 DURING CONSTRUCTION PHASE..... | 36 |
| 7.1.1 PHYSICAL ENVIRONMENT | 37 |
| 7.1.2 BIOLOGICAL ENVIRONMENT..... | 39 |
| 7.2 DURING OPERATION PHASE..... | 39 |
| 7.2.1 PHYSICAL ENVIRONMENT | 39 |
| 7.2.2 BIOLOGICAL ENVIRONMENT..... | 39 |
| CHAPTER 8 STAKEHOLDER CONSULTATION AND INFORMATION DISCLOSURE | 40 |
| 8.1 CONSULTATIONS WITH INSTITUTIONAL STAKEHOLDERS..... | 40 |
| 8.2 INFORMAL CONSULTATION WITH LOCAL POTENTIALLY AFFECTED COMMUNITIES..... | 41 |
| 8.3 FORMAL PUBLIC CONSULTATION..... | 42 |
| 8.4 DISCLOSURE FOR ESA& EMP | 43 |
| CHAPTER 9 ENVIRONMENTAL MANAGEMENT PLAN (EMP) | 44 |
| 9.1 COMPONENTS OF EMP | 44 |
| 9.2 INSTITUTIONAL RESPONSIBILITIES, MITIGATION AND MONITORING | 44 |
| 9.2.1 EMP INSTITUTIONAL ARRANGEMENTS AND RESPONSIBILITIES..... | 44 |
| 9.2.2 EMP MITIGATION AND MONITORING | 48 |
| 9.2.3 ENVIRONMENTAL MONITORING..... | 56 |
| 9.2.4 CHANCE FIND PROCEDURES | 60 |
| 9.2.5 INCIDENT MANAGEMENT AND EMERGENCY RESPONSE PROCEDURES..... | 61 |
| 9.2.6 CORRECTIVE ACTIONS..... | 62 |
| 9.2.7 RECORD KEEPING AND REPORTING | 62 |
| 9.2.8 CAPACITY BUILDING | 63 |
| CHAPTER 10 RISK ASSESSMENT AND DISASTER MANAGEMENT..... | 69 |
| 10.1 RISK ASSESSMENT..... | 69 |
| 10.2 HAZARD RISK AND VULNERABILITY OF THE PROJECT AREA..... | 73 |
| CHAPTER 11 EMP REVIEW IMPLEMENTATION PLAN & BUDGET ESTIMATION..... | 77 |
| 11.1 EMP REVIEW | 77 |
| 11.2 EMP IMPLEMENTATION PLAN AND SCHEDULE | 77 |
| 11.3 EMP COSTS SUMMARY | 81 |
| LIST OF FIGURES | |
| FIGURE 1: LOCATION MAP OF CUDDALORE TOWN | 7 |
| FIGURE 2: LOCATION MAP OF NAGAPATTINAM AND VELANKANNI | 8 |
| FIGURE 3: INSTITUTIONAL ARRANGEMENTS FOR THE EMP IMPLEMENTATION..... | 45 |
| FIGURE 4: ORGANIZATIONAL STRUCTURE OF PIU..... | 78 |
| LIST OF TABLES | |
| TABLE 1 : CDRRP COMPONENTS AND SUB-COMPONENTS | 5 |



| | | |
|----------|--|----|
| TABLE 2 | : SUB-PROJECT PACKAGES | 9 |
| TABLE 3 | : EXISTING OH NETWORK OF THE PACKAGE - 2 | 12 |
| TABLE 4 | : PROPOSED UG CABLE NETWORK OF THE PACKAGE - 2..... | 12 |
| TABLE 5 | : EXISTING FEATURES OF PROJECT (PACKAGE-2) | 14 |
| TABLE 6 | : LIST OF MAJOR CROSSINGS | 20 |
| TABLE 7 | : APPROVAL, CONSENT AND PERMITS REQUIREMENT MATRIX | 20 |
| TABLE 8 | : BASIC DEMOGRAPHIC FEATURES OF CUDDALORE MUNICIPALITY | 27 |
| TABLE 9 | : SCRAP MATERIALS FROM EXISTING OH NETWORKS | 30 |
| TABLE 10 | : LIST OF STAKEHOLDERS DURING INSTITUTIONAL CONSULTATION | 40 |
| TABLE 11 | : DETAILS OF INFORMAL CONSULTATIONS HELD IN CUDDALORE MUNICIPALITY | 42 |
| TABLE 12 | : ROLES AND RESPONSIBILITIES FOR EMP IMPLEMENTATION | 45 |
| TABLE 13 | : ENVIRONMENTAL MITIGATION MANAGEMENT, SUPERVISION, AND REVIEW PLAN..... | 50 |
| TABLE 14 | : ENVIRONMENTAL MONITORING PLAN..... | 58 |
| TABLE 15 | : TRAINING SCHEDULE | 66 |
| TABLE 16 | : ESMP IMPLEMENTATION PLAN | 79 |
| TABLE 17 | : EMP COST SUMMARY | 81 |

LISTS OF ANNEX

- Annex 1 : Strip Layout Plan of Underground Electrical Cables
- Annex 1 (A) : Layout of Anna Stadium Switching Station.
- Annex 1 (B) : Precautions to protect the NAG DEVATHA (Anthill) shrine at Anna Stadium Switching Station
- Annex 2 : Roads And Street Wise Location And Numbers Of The Sensitive Sites, Vendors, Ramps, Nearby Trees, Road Crossings, River Crossings, Railway Crossings, Nearby Open Drains, Dense Settlements, High Activity Area (Markets, Bus Stops) Etc.
- Annexure 3: Public consultation meeting



List of Abbreviations

| | |
|----------|---|
| AE/AEE | ASSISTANT ENGINEER/ASSISTANT EXECUTIVE ENGINEER |
| CDRRP | COASTAL DISASTER RISK REDUCTION PROJECT |
| CRZ | COASTAL REGULATION ZONE |
| CZMA | COASTAL ZONE MANAGEMENT AUTHORITY |
| CZMP | COASTAL ZONE MANAGEMENT PLAN |
| ESE | ENVIRONMENTAL/SOCIAL EXPERT |
| EIA | ENVIRONMENTAL IMPACT ASSESSMENT |
| ESMF | ENVIRONMENTAL AND SOCIAL MANAGEMENT FRAMEWORK |
| ESMP | ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN |
| GoTN | GOVERNMENT OF TAMIL NADU |
| HT | HIGH TENSION |
| IA | IMPLEMENTING AGENCY |
| LT | LOW TENSION |
| MoEF | MINISTRY OF ENVIRONMENT AND FOREST |
| OHL | OVERHEAD LINE |
| PIU | PROJECT IMPLEMENTATION UNIT |
| PM | PARTICULATE MATTER |
| PMU | PROJECT MANAGEMENT UNIT |
| PIU | PROJECT IMPLEMENTATION UNIT |
| SE | SUPERINTENDING ENGINEER |
| SIPCOT | STATE INDUSTRIES PROMOTION CORPORATION OF TAMIL NADU |
| SPCB | STATE POLLUTION CONTROL BOARD |
| TANGEDCO | TAMIL NADU GENERATION AND DISTRIBUTION CORPORATION LTD. |
| TNPCB | TAMIL NADU POLLUTION CONTROL BOARD |
| UG | UNDERGROUND |
| WB | WORLD BANK |



Chapter 1

EA Background

1.1 Introduction CDRRP

To reduce the vulnerability of the coastal communities to a range of natural hazards such as cyclone, storm surge, floods, tsunamis etc. over the longer term, the government of Tamil Nadu has requested World Bank for financial assistance. As suggested by World Bank a new project namely Coastal Disaster Risk Reduction Project (CDRRP) was prepared and the same was finalized for further planning and implementation.

The CDRRP objective was to safeguard the coastal communities through building resilient infrastructure, enhancing livelihood and coastal risk management capacity of stakeholders and improving the recipient's capacity to respond promptly and effectively to an eligible crisis or emergency.

The CDRRP is comprised of 4 components with a number of subcomponents as under (Table1):

Table 1: CDRRP Components and Sub-Components

| Components | Sub- Components |
|--|--|
| Component 1: Vulnerability Reduction | <p>Sub-Component 1.1: Resilient Housing</p> <p>Sub-Component 1.2: Multipurpose evacuation Shelters, Emergency evacuation routes and Early warning systems</p> <p>Sub-Component 1.3: Cyclone Resilient Electrical Network</p> |
| Component 2: Sustainable Fisheries Works Pertaining to fisheries Sector | <p>Sub-Component 2.1: Fisheries Infrastructures [on going & New]</p> <p>Sub-Component 2.2: FIMSUL II Implementation of marine Fisheries Co-management, improved Capacities and Knowledge management, Fisheries livelihood support, Management support and Providing Wireless Communication</p> |



| | |
|---|---|
| | Facilities |
| Component 3: Capacity building in Disaster Risk Management | <p>Sub- Component 3.1: Strengthening of State Disaster Management Authority, Setting up a Comprehensive GIS platform and GIS cell in the SDMA</p> <p>Sub- Component 3.2: Community based Disaster Risk Management Program</p> <p>Sub- Component 3.3: Curriculum Development for Disaster Risk Reduction in schools and Training institutions</p> <p>Sub-Component 3.4: Integrated Coastal Zone Management</p> |
| Component 4: Implementation Support | |

The total project cost under CDRRP for Tamil Nadu appropriated was US\$ 190 million.

An Environmental Management Framework (EMF) for the CDRRP was prepared by Project Management Unit, Government of Tamil Nadu with an objective to i) Enhance positive and sustainable environmental and social outcomes associated with Project implementation; ii) Support the integration of environmental and social aspects associated with the numerous sub-projects into the decision making process; iii) Support displaced persons in their efforts to restore their livelihoods and living standards and compensate any loss of livelihood or assets; iv) Enhance positive environmental and social outcomes; v) Minimize environmental degradation as a result of either individual sub-projects or their cumulative effects; vi) Protect human health; and viii) Minimize impacts on cultural property.

The EMF for CDRRP projects requires preparation of Environmental assessment prior to the implementation of the CDRRP components and sub-projects complaint with applicable laws and regulation of



India/Tamil Nadu State and with relevant bank policies on Environmental& Social Development Issues.

1.2 Underground Cable Network - TANGEDCO Packages

This project is sub component 1.3 of Component 1, of CDRRP. The sub-component is planned for implementation in the coastal towns of Cuddalore, Nagapattinam and Velankanni in the District of Cuddalore, and Nagapattinam of Tamil Nadu (Figure 1 and 2).

Figure 1: Location Map of Cuddalore Town







Figure 2: Location Map of Nagapattinam and Velankanni





The sub-component is comprised of 7 packages, 3 packages in the Cuddalore district and 4 packages in the Nagapattinam district (Table 2).

Table 2: Sub-Project Packages

| Package | Feeder Name | Town/Districts |
|------------------|---------------------------|---|
| Package 1 | Manjakuppam | Cuddalore Town, Cuddalore District |
| | Vandipalayam | |
| Package 2 | Cuddalore New Town | |
| | Sellankuppam | |
| Package 3 | Alpettai | |
| | Suthukulam | |
| | Pentesia | |
| Package 4 | Nagapattinam Town | Nagapattinam Town, Nagapattinam District |
| Package 5 | Thonithurai | |
| | Nagore | |
| | Velipalayam Water Works | |
| Package 6 | Velipalayam | Velankanni Town, Nagapattinam District |
| Package 7 | Velankanni | |

The objective of the sub-component packages is to avoid risk exposure to cyclone, winds and related hazards to the existing electrical networks through replacement of overhead (OH) lines with underground (UG) cables. The Implementing Agency (IA) of the sub-component packages is TANGEDCO. This sub-component packages expected to benefit coastal community towns and villages of Cuddalore and Nagapattinam Districts, particularly in terms of an early resumption of power / electricity in the aftermath of natural disasters.

ESA of the sub-component envisages minor construction-related reversible physical environmental impacts, e.g. storage and disposal of debris including occupational health impacts to unskilled workforce and community health and safety concerns to the nearby settlements.

ESMF for the Component 1 sub-component 1.3 recommended an ESA study with EMP / RAP (as needed) integrating OHS issues for implementation by the IA with the help of consultants. This ESA



report has been prepared to meet the EMF requirement by the consultant and encloses EMP as per the ESA study.

1.3 Environmental Assessment and EMP for Package -2, CuddaloreTown

This Environmental Assessment (EA) for the Underground Electricity/Power Cable Network at Cuddalore New Town, Sellankuppam & some part of Manjakuppam feeders in Cuddalore Town, Cuddalore district under Package No.2, is prepared in line with the EMF based on the guidelines specified under Indian Regulatory Framework and guidelines/ policies of World Bank (WB).

1.4 Structure of the Report

This EA report is organized in 11 chapters.

Chapter 1 briefly describes CDRRP components and sub-projects within the components highlighting on the objectives of the CDRRP and associated packages. It also summarizes the EMF requirements while undertaking EMP study and preparation of needed EMP and RAP for the sub-project Packages

Chapter 2 highlights on the Project's descriptions (Package-2);

Chapter 3 reviews the relevant environmental and social safeguard policies, and legislative framework of the Government of India/Tamil Nadu State including the applicable Bank Policies highlighting on the requirement of needed clearance with timelines for the Project (Package -2);

Chapter 4 presents the Project (Package-2) area environmental baseline features;

Chapter 5 is dedicated for the assessment and identification of Project impacts (Package -2);

Chapter 6 analyses the Project's (Package-2) Alternatives;

Chapter 7 presents the descriptions of mitigation measures to avoid, minimize and or compensate the adverse impacts identified for the Project (Package-2).



Chapter 8 presents the Stakeholder / public consultations with focus on the impacts and construction phase issues for the Project's Packages in the Cuddalore district.

Chapter 9 presents the Specific environmental management/monitoring plan to mitigate and manage impacts for the project (Package-2)

Chapter 10 presents Risk Assessment and Disaster Management

Chapter 11 presents EMP Review implementation plan and Budget estimation.



Project Descriptions (Package-2)

Chapter 2

2.1 Location

The Project (Package-2) is located in the Cuddalore district, covering nearly 9km² area in the southern parts of Cuddalore Municipality along the coast line. The key settlements covered by this Project are Vinayaga Nagar, Devanampattinam, Ishwari Nagar, Durai Sami Nagar, Nehru Nagar, Anna Nagar, Court, VGP Nagar, Semmandalam, Varadharajan Nagar, Annandale, Sorakalpattu, Seetharam Nagar, Pudupalayam, R.P. Nagar, Kamaraj Nagar, Devanampattinam, Sothikkuppam, Sivanandhapuram, Sellankuppam, VSR Palayam, Etc. Settlements.

2.2 Details of Project (Package-2)

Project (Package-2) proposes to convert about 59.7 km of HT line and about 90.88 km of LT line (Table 3) into underground electrical cable (Table 4). The estimated cost of the Package is Rs. 157.50 crores.

Table 3: Existing OH network of the Package –2

| S.N O. | Feeder Name | HT Length (kms) | No. of DTs | LT Length (in km) | Feeder Load (in Amp) | 1 ph consumer | 3 ph consumer |
|--------------------|---------------|-----------------|------------|-------------------|----------------------|---------------|---------------|
| 1 | New Town | 33.45 | 252 | 60.1 | 220 | 6980 | 2992 |
| 2 | Sellanakuppam | 12.65 | 140 | 24.98 | 214 | 6548 | 920 |
| 3 | Manjakuppam | 13.6 | 113 | 5.8 | ---- | 555 | 193 |
| Grand total | | 59.7 | 505 | 90.88 | | 14083 | 4105 |

Table 4: Proposed UG Cable network of the Package–2

| Feeder Name | New Town feeder-2 | New Town feeder-6 | New Town feeder-8 | Manjakuppam feeder-7 | Sellanakuppam feeder-5 | Sellanakuppam feeder-9 | Grand Total |
|---------------------|-------------------|-------------------|-------------------|----------------------|------------------------|------------------------|-------------|
| HT Length(km) | 14.064 | 11.812 | 15.010 | 13.82 | 12.90 | 9.698 | 77.304 |
| LT Length(km) | 38.866 | 16.529 | 5.545 | 6.453 | 37.38 | 36.499 | 141.272 |
| Service cables (km) | 127.600 | 82.920 | 20.360 | 29.92 | 148.16 | 150.320 | 559.28 |



| Feeder Name | New Town feeder-2 | New Town feeder-6 | New Town feeder-8 | Manjakuppam feeder-7 | Sellanakuppam feeder-5 | Sellanakuppam feeder-9 | Grand Total |
|-----------------------------|----------------------|----------------------|----------------------|-------------------------|---------------------------|---------------------------|-------------|
| Street light cables (km. | 8.66 | 7.36 | 5.82 | 5.36 | 6.56 | 5.544 | 39.304 |
| DTs (Nos.) | 68 | 88 | 99 | 113 | 96 | 44 | 508 |
| LT Panel (Nos.) | 33 | 25 | 4 | 5 | 29 | 28 | 124 |
| Feeder Pillars(Nos.) | 121 | 61 | 12 | 17 | 99 | 107 | 417 |
| Service Pillars (Nos.) | 489 | 225 | 63 | 125 | 507 | 478 | 1887 |
| Trenchless crossings (Nos.) | 16 | 25 | 15 | 2 | 16 | 23 | 97 |
| Pipe crossings(Nos.) | 304 | 138 | 114 | 105 | 307 | 207 | 1175 |
| RMU (Nos.) | 72 | 101 | 97 | 111 | 95 | 49 | 525 |

2.3 Key Features in the Project (Package-2) Area

A detailed strip layout plan of the underground electrical cables, DTs, Feeder Pillars, and Service Pillars is attached in Annexure 1. The layout strip maps have been prepared based on the GPS survey. It shows the alignment of the UG cable networks along with locations of DTs, Feeder Pillars and Service Pillars including the locations of the key sensitive features such as open drains, schools, health facilities, shrines, trees, road crossings, railway crossings, rivers/streams/drain crossings vendor's standing areas, structural ramps etc. Each of the roads and streets are numbered such that the key sensitive features could be easily identified and located with reference to Drawing Nos., Map Nos. and Road/Street Nos.

Key Project (Package-2) features are summarized in Table 5.

**Table 5: Existing Features of Project (Package-2)**

| S.No | Features | Quantity |
|-------------|--|---|
| 1 | Required Land | Public Land (Roads and Streets) |
| 2 | Name of the Village / Location | Cuddalore Municipality (Vinayaga Nagar, Devanampattinam, Ishwari Nagar, Durai Sami Nagar, Nehru Nagar, Anna Nagar, Court, VGP Nagar, Semmandalam, Varadharajan Nagar, Annandale, Sorakalpattu, Seetharam Nagar, Pudupalayam, R.P. Nagar, Kamaraj Nagar, Devanampattinam, Sothikkuppam, Sivanandhapuram, Sellankuppam, VSR Palayam etc.) |
| 3 | Terrain | Plain |
| 4 | Existing Land use | Roads and street |
| 5 | Railway crossing (Nos) | 1 |
| 6 | NH Crossing (Nos) | 44 |
| 7 | SH crossing (Nos.) | 12 |
| 8 | Other road crossing (Nos.) | 821 |
| 9 | Religious Structures within 50 m UG trench) | 90 |
| 12 | Health Facilities within 50 m from UG Trench (Hospitals) nearby (Nos.) | 14 |
| 13 | Educational institutions within 50m UG Trench nearby (Nos.) | 26 |
| 14 | Major River crossings (Nos.) | 2 |
| 15 | Nallah/Stream Crossing (Nos.) | 8 |
| 16 | Vendor's Locations (Nos.) | 19 |
| 17 | Vendor (Nos.) | 113 |
| 18 | Ramp Crossings (Nos.) | 126 |
| 19 | (a) No of Locations with Trees | 8 |



| | | |
|----|--|--|
| | (b) Number of trees within 5 m from the UG Trench (Nos.) | 24 |
| 21 | Forest Areas | Nil |
| 22 | CRZ Areas | Yes (CRZ –II and CRZ III) |
| 23 | Tribal Area, if any | Nil |
| 24 | Dense settlement locations (Nos.) | 15 |
| 25 | High Activity Area locations (Nos.) | 12 (Markets, Bus Stops, and Tempo stands etc.) |

The Key Project (Package-2) activities are: i) underground laying of the electrical cables, ii) installation and testing of the underground electrical cable network and iii) dismantling of the OH cables, DTs, and electrical poles.

The electrical cables will be laid underground by opening of trenches along the existing road infrastructure. The direct impact of the UG trench limits within the width and depth of excavation while indirect access impacts extends throughout the corridor.

Width and the depth of the excavated trenches will vary from 0.3 to 1.06m and 0.82 to 1.2m respectively depending on the numbers of HT, LT, and service cables to be laid in the trench. A combination of man and machine will be used for the trench excavation installation of DTs, Feeder Pillars, Service pillars and dismantling of the OH cables, DTs and electrical poles.

Estimated construction schedule for Package 2 is 21 months.

Estimated numbers of construction workers for the package is 320 per day during the construction period.



CHAPTER 3

POLICY, LEGAL AND REGULATORY RAMEWORK

The key policies and legal frameworks (National, State and World Bank) attracted by the underground cabling works under the Project (Package-2) have been briefly highlighted hereunder.

3.1 National/State Policies and Legal Frameworks

Keeping in view of the underground electric cable layout, location and activities, the key National environmental legislation triggered are:

- Environment (Protection) Act, 1986
- Environmental Impact Assessment Notification 2006,
- Coastal Regulation Zone (CRZ) Notification 2011 (as amended)
- Water (Prevention and Control of Pollution) Act, 1974
- Air (Prevention and Control of Pollution) Act, 1981
- Hazardous Waste (Management, Handling and Transboundary Movement) Rules 2008 as amended in 2016.
- Ancient Monuments and Archaeological Sites and Remains Act, 1958
- The control of National Highways (Land and Traffic) Act, 2002
- The Tamil Nadu Highways Act, 2001
- Tamil Nadu Town and Country Planning Act, 1971
- Tamil Nadu Panchayats Act, 1994
- The Street Vendors (Protection of Livelihood and Regulation of Street Vending) Act, 2014
- Contract Labour Act, 1970;
- The Bonded Labour System (Abolition) Act, 1976,
- Child labour (Prohibition and Regulation) Act 1986 along with Rules, 1988
- Children (Pledging of labour) Act, 1933 (as amended in 2002)

Environmental (Protection) Act, 1986 is the umbrella legislation enacted for the protection of environment. Environment (Protection) Rules under this act including Environmental Impact Assessment Notification (2006) and Coastal Zone Regulation (CRZ) Regulation, 1991 and CRZ notification 2011 stipulates legal procedures to be complied prior the inaction of the development works.



The underground electrical cable project is exempted for environmental studies as per EIA Notification 2006. But due to its location and type of development, it is triggered by CRZ, 2011 Notification of the Environmental (Protection) Act, 1986.

This notification prohibits certain development activities totally within CRZ while regulates some of the development activities with the clearance of Ministry of Environment and Forest (MoEF) on the recommendations of concerned State or Union Territory Coastal Zone Management Authority (CZMA).

The proposed project is permitted activity under the section 4.ii.d of the CRZ Notification 2011.

Water (Prevention and Control of Pollution) Act, 1974 is likely to be attracted by the action of the contractors, particularly related to disposal of spoils at or near the pathways of the monsoon run off or the water bodies located adjacently. Similarly, the Air (Prevention and Control of Pollution) Act, 1981 is likely to be attracted by fugitive emissions of the excavated earth in the given wind conditions in the Project (Package-2) area.

As the underground electric cable works locates within the jurisdiction of the Highways, the control of National Highways (Land and Traffic) Act, 2002 and The Tamil Nadu Highways Act, 2001 are triggered.

The Tamil Nadu Town and Country Planning Act, 1971 and Tamil Nadu Panchayats Act, 1994 are triggered because; i) the sub-project plan be integrated with the overall development plans of the Towns and Panchayats; ii) use of the Municipal/ Panchayat operated / maintained roads for the sub-projects and iii) establishment of construction and labour camps.

The Street Vendors (Protection of Livelihood and Regulation of Street Vending) Act, 2014; Minimum Wages Act, 1948; Contract Labour Act, 1970; The Bonded Labour System (Abolition) Act, 1976; Child labour (Prohibition and Regulation) Act 1986 along with Rules, 1988; and Children (Pledging of labour) Act, 1933 (as amended in 2002) are triggered because the Project (Package-2) is likely to i) temporarily displace vendors, and ii) involves workers of all types and age.



The Street Vendors (Protection of Livelihood and Regulation of Street Vending) Act, 2014: Government of India (GOI) recently enacted the act that specifically aims to protect the rights of urban street vendors and to regulate street vending activities. It provides for Survey of street vendors and protection from eviction or relocation; issuance of certificate for vending; provides for rights and obligations of street vendors; development of street vending plans; organizing of capacity building programs to enable the street vendors to exercise the rights contemplated under this Act; undertake research, education and training programs to advance knowledge and understanding of the role of the informal sector in the economy, in general and the street vendors, in particular and to raise awareness.

As per Street vendors Act.2014, the definitions refers therein are as under:-

“Street Vendors” means a person engaged in vending of articles , goods , wares, food item or merchandise of everyday use or offering services to the general public, in a street, lane side walk, footpath, pavement , public park or any public place or private area, from a temporary built up structure or by moving from place to place and includes hawker, peddler, squatter and all other synonymous terms which may be local or region specific; and the words “street vending” with their grammatical variations and cognate expressions, shall be construed accordingly

“Town Vending Committee” means the body constituted by the appropriate Government under section 22;

“vending zone” means an area or a place or a location designated as such by the local authority, on the recommendations of the Town Vending Committee, for the specific use by street vendors for street vending and includes footpath, side walk, pavement, embankment, portions of a street, waiting area for public or any such place considered suitable for vending activities and providing services to the general public.

Further, the Act requires that no street vendor shall be evicted or relocated till a survey is conducted and a Certificate of vending is issued by Town Vending Committee formed under Section 22 of the Act. According to Section 18 of the act, the local authority may, on



the recommendations of the Town Vending Committee, declare a zone or part of it to be a no-vending zone for any public purpose and relocate the street vendors vending in that area. No street vendor shall be relocated or evicted by the local authority from the place specified in the certificate of vending unless he has been given thirty days' notice. However, every street vendor, who possesses a certificate of vending, shall, in case of his relocation under section 18, be entitled for new site or area, as the case may be, for carrying out his vending activities as may be determined by the local authority, in consultation with the Town Vending Committee.

This is applicable to Tamil Nadu as well.

3.2 World Bank Policies

In view of the Project (Package-2) layout, location, construction and operational activities, the envisaged potential impacts of the project are minor, temporary and fully reversible. For this reason the sub-project is environmentally screened as "Category B" project. Since the Project (Package-2) physically interacts with the already modified land resource triggers the following World Bank Policies:

- OP/BP 4.01 Environmental Assessment
- OP/BP 4.11 Physical Cultural Resources

The policy for Physical and Cultural Resource is potentially attracted in the cultural and historical places. The sub-project envisages excavation along the streets for the laying of UG cable to connect the sites of cultural and historical significance and there is a likelihood of chance finding of cultural and historical artefacts.

Considering the project layout it is not expected to trigger the OP/BP 4.12 Involuntary Resettlement Policy and OP/BP 4.10 Indigenous Peoples Policy. Temporary disturbances to vehicular and pedestrian access, vegetable vendor markets etc, however, is potential during the construction period.

3.3 Required Approval, Consent and Permits

To comply with the above stated Acts and Regulation provisions, prior to the Project (Package-2) implementation, conforming to this EMP, and in page with the legislative framework of the Government of Tamil Nadu /India, Implementing Agency (TANGEDCO) shall



procure Approval, Consent and Permits from the following agencies
(**Table 7**).

Table 6:List of Major Crossing (Package-2)

| S.No | TYPE OF CROSSING | NO. OF CROSSING | LOCATION |
|------|------------------|-----------------|-----------------------------------|
| 1 | N.H. 45A | 2 | DTR-08 MANGAI MAHAL |
| 2 | N.H. 45A | 1 | NEAR KSM SCHOOL |
| 3 | N.H. 45A | 2 | MARKET COMMITTEE SS-II |
| 4 | N.H. 45A | 2 | MARKET COMMITTEE SS-I |
| 5 | N.H. 45A | 1 | NEAR KSM SS-IV |
| 6 | N.H. 45A | 1 | IPPENAR SS-II |
| 7 | N.H. 45A | 1 | NEAR VELLI VINYAGAR SS-I |
| 8 | N.H. 45A | 1 | NEAR SELLANAKUPPAM BUS STOP |
| 9 | N.H. 45A | 1 | NEAR TVS SHOWROOM |
| 10 | N.H. 45A | 2 | VELLI VINYAGAR SS-II |
| 11 | N.H. 45A | 5 | VELLI VINYAGAR SS-I |
| 12 | RAILWAY | 1 | VSR PALAYAM RAILWAY GATE |
| 13 | N.H. 45A | 1 | NEAR KVS COMPLEX OLD TOWN |
| 14 | N.H. 45A | 2 | NEAR JUBLE CLUB |
| 15 | N.H. 45A | 1 | KALLA CHETTY STREET |
| 16 | N.H. 45A | 1 | GANDHI PARK O.T. |
| 17 | N.H. 45A | 2 | MANIKUND SS-II |
| 18 | N.H. 45A | 2 | NEAR SUTHUKULLAM RAILWAY GATE |
| 19 | N.H. 45A | 2 | NEAR PETROL BUNK |
| 20 | N.H. 45A | 2 | POLICE STATION SS LT NETWORK |
| 21 | N.H. 45A | 2 | JUBLE CLUB SS LT NETWORK |
| 22 | N.H. 45A | 1 | MERKET SS-I LT NETWORK |
| 23 | N.H. 45A | 1 | AGRO SS LT NETWORK |
| 24 | N.H. 45A | 1 | FWA SS-I LT NETWORK |
| 25 | S.H.9 | 1 | NEAR EMPLOYMENT OFFICE |
| 26 | S.H.9 | 1 | NEAR CHURCH PONDY BY PASS |
| 27 | S.H.9 | 1 | NEAR ASHOK LEYLAND TRACTOR AGENCY |
| 28 | S.H.9 | 1 | PAPPAMAL NAGAR SS |
| 29 | S.H.9 | 1 | KONDUR SS-XI |
| 30 | S.H.9 | 1 | S.N. CHAVADI BUS STOP |
| 31 | S.H.9 | 1 | MANAKOLLI SS-III |
| 32 | S.H.9 | 1 | NEAR HONDA ABVR NELLIKUPPAM ROAD |
| 33 | S.H.9 | 2 | SUNDRAM NAGAR SS-I |



| | | | |
|----|--------|---|------------------------------|
| 34 | S.H.9 | 1 | GENERAL HOSPITAL CUDDALORE |
| 35 | S.H.9 | 1 | BSNL OFFICE NELLIKUPPAM ROAD |
| 36 | S.H.9 | 1 | CIRCUIT HOUSE |
| 37 | NH-45A | 1 | OPP. SURIYAPRIYA HOTEL |
| 38 | NH-45A | 1 | NEAR ALC CHURCH |
| 39 | NH-45A | 1 | NEAR WOODLAND HOTEL |
| 40 | NH-45A | 1 | NEAR MUNICIPALITY OFFICE |
| 41 | NH-45A | 1 | NEAR BANK OF BARODA |
| 42 | NH-45A | 1 | NEAR RAJATHI SHOWROOM |
| 43 | NH-45A | 1 | NEAR GDM SS-I |



Table 7: Approval, Consent and Permits Requirement Matrix

| Types of Clearance | Authority for clearance | Lead Time of clearance application before implementation ¹ | Responsible agency for clearance application | Over sighting Agency |
|---|---|---|--|----------------------|
| No Objection Certificate for CRZ Clearance application | District Coastal Zone Management Authority | A month before CRZ Clearance Application | Project Implementation Unit | TANGEDCO |
| CRZ Clearance | State of Tamil Nadu Coastal Zone Management Authority | Six month before implementation | Project Implementation Unit | TANGEDCO |
| Consent Under Air (Prevention and Control of Pollution) Act, 1981 | Tamil Nadu State Pollution Control Board | Prior to commencement of works | Project Implementation Unit | TANGEDCO |
| Consent Under Water (Prevention and Control of Pollution) Act, 1974 | Tamil Nadu State Pollution Control Board | Prior to commencement of works | Project Implementation Unit | TANGEDCO |
| Consent in compliance to the control of National Highways (Land and Traffic) Act, 2002 (Clearance for NH Crossings) | National Highway Authority | Prior to commencement of works | Sub - Project Implementation Unit | TANGEDCO |
| Consent in compliance to the Tamil Nadu Highways Act, 2001 (Clearance for SH Crossing) | Tamil Nadu State Highway Authority | Prior to commencement of works | Sub - Project Implementation Unit | TANGEDCO |

¹ Lead time for clearance application to various agencies is estimated based on the legal time requirement for clearance and general practices in the region such that the permissions and approval are acquired at least two months before project actual construction.



| Types of Clearance | Authority for clearance | Lead Time of clearance application before implementation ¹ | Responsible agency for clearance application | Over sighting Agency |
|---|--|---|--|----------------------|
| Consent in compliance to The Tamil Nadu Town and Country Planning Act, 1971 and Tamil Nadu Panchayats Act, 1994 | Planning Department Cuddalore Municipality, | Prior to commencement of works | Sub - Project Implementation Unit | TANGEDCO |
| Consent with the Utility Service Agencies | Cable Agencies Water Supply, Drainage and Sewage Agencies | Prior to commencement of works | Sub - Project Implementation Unit | TANGEDCO |



CHAPTER 4

ENVIRONMENTAL BASELINE

This chapter presents baseline profile of the Project (Package-2) area. Since the baseline environmental scenario is more or less consistent in the Cuddalore Municipality, the following sections provide an environmental setting of Cuddalore Municipality and specific features related to Package 2 (where available).

4.1 Climate

The climate of the Cuddalore area is tropical monsoon type. The temperature during winter seldom goes below 18°C, while in peak summer it might exceed 39°C. The area receives rain from both the northeast and southwest monsoon. The average annual rainfall ranges between 1300 to 1400mm, maximum being in the northeast monsoon (October to December). The southwest monsoon (June to September) is relatively mild, while minimum rainfall occurs in the month of March. In the area relative humidity ranges between 62% to 80%, minimum being in the month of March and maximum in the months of November and December. In general the wind speed ranges between 4 to 13 km/hour, maximum being in the months of June through December coinciding with the southwest and northeast monsoons.

4.2 Physical Environment

4.2.1 Land Resources

The Cuddalore Municipality and its adjoining area represents a central section of the pelagic coastline on the east coast of Tamil Nadu. Topographically, it represents the edge of a gradually falling landscape. The slopes are extremely flat on the landward side and the same is generally true on the seaward side as well. Morphologically, this part of the coastal tract consists of an upland plain (denudation), flood plain (fluvial), deltaic plain and coastal plain (marine)² developed over the Cauvery delta. The coast relief is disturbed by estuaries and lagoons formed along the river and their distributaries (South Pennaiyar, Uppannar and Gadilam River system)

²Chandrasekar N 1992 Beach placer mineral exploration along the central Tamil Nadu coast; unpublished Ph.D thesis, Madurai Kamaraj University, Madurai, Tamil Nadu, India.; Mohan P M, Shepherd K, Suresh Gandhi M and Rajamanickam G V 2000 Evolution of Quaternary sediments along the coast between Vedaranyam and Rameshwaram, Tamil Nadu; J. Geol. Soc. India 56 271–28.



behind the coast line. These lagoons or estuaries are narrow water bodies separated from the open ocean by spits and barrier bars/islands. Beach ridges representing barrier bars/islands are present along the coast line of the sub-project area, which lie almost parallel to the present shoreline indicating that the shoreline is receding towards the sea³. Since, the sub-project influence area is located on the beach ridge systems, effects of heavy rainfall and storm surge is imminent. The coastal landforms of the sub-project are subjected to three seasonal meteorological cycles in a year such as NE monsoon (October–December), SW monsoon (June–September), and non-monsoon (January–May). In addition to the above yearly cycles, the coastline landscape is remolded by the occasional cyclones storm surge usually in the northeast monsoon period.

Geologically, the Cuddalore Municipality and adjoining area is comprised of unconsolidated recent deposits of fluvial, fluvio-marine, aeolian and marine origin. In general, the shore areas and estuaries are made up of marine tidal flat deposits comprising of black clay overlain by beach sand and sand dunes at the immediate shore front, while further inland marine -paleo- tidal flat deposits comprising of brown to grey brown medium sand deposits exists. Further onshore fluvial flood basin deposits made up of clay and sandy clay occurs. These soft quaternary deposits yield easily to denudation by the force of nature such as tidal waves, cyclones, and monsoon runoff in areas not protected by vegetation cover.

As of the date, Cuddalore area land use is predominantly occupied by dense to scattered urban settlements, followed by cultivable lands with miscellaneous tree crops, barren lands and water bodies. Forest cover is insignificant, except for the coconut and casuarina plantation at the shore line behind the beaches and remnant of the mangroves along the river estuaries.

4.2.2 Ambient Air Quality

SPCB ambient air quality monitoring data is not available for Cuddalore Municipal area. In some places of Cuddalore municipality near the waste management sites concentrations of PM 10 is

³Revathy G, Suresh Gandhi M, Chandrasekar N and Rajamanickam G V 2002. Coastal land forms in between Nagapattinam and Porto Novo, Tamil Nadu, east coast of India; *Indian J. Geomorphol.* 7(1& 2) 119–133.



reported to exceed the threshold limits of CPCB and ranged from 134.3-198.4 $\mu\text{g}/\text{m}^3$ in pre monsoon and 117.5-112.8 $\mu\text{g}/\text{m}^3$ in the post monsoon⁴. The field observations in 2015, particularly along the National and State Highways and the market centers, PM 10 values are expected to be within the PCB threshold limits

4.2.3 Water Resources

The surface water resources lie in a zone of water mixing where sea water mixes with the fresh water of the rivers such as South Pennaiyar, Gadilam & Uppannar and associated estuaries/lagoons and river distributaries. Water quality parameters of Cuddalore municipality are reported to show elevated pollutants in estuary suggests increasing pollution due to discharge of State Industries Promotion Corporation of Tamil Nadu (SIPCOT) industrial effluents which often exceeds CPCB standards particularly in toxic metals and nutrient concentrations.

The groundwater potential of the Project (Package-2) coast line is variable based on the rainfall, recharge etc. Four different aquifer systems have been identified namely: i) water table, ii) filter peine, iii) shallow and, iv) deep aquifer system. The groundwater is mainly confined on the coastal sand dunes. Wide variation occurs in the water quality of fresh water and saline aquifers depending on the hydro-geological situation and has a risk of sea water intrusion due to over exploitation. TNPCB is monitoring the quality of water from the Cuddalore area. According to TNPCB⁵ the quality of water is normal in the monitoring station chosen for overall assessment. The groundwater water table show wide fluctuation seasonally. It fluctuates from nearly 2.5m from surface to 10 m, being near surface at the peak of northeast monsoon and minimum towards the end of summer.

4.2.4 Noise Environment

Monitoring database for the noise levels in the Cuddalore area are not available. In view of the road side and market area activities,

4B.AbrahamLingan, G. Poyyamoli, and U.JagadeeshChandira Boss; 2014.Assessment of Air Pollution and Its Impacts near Municipal Solid Waste Dumping Site Kammiyampet, Cuddalore, India. International Journal of Innovative Research in Science, Engineering and Technology, Vol. 3, Issue 5, May 2014

⁵ Personnel communication, 2015



expected noise level at the day time and night time could be as high as 70 and 50 dB (A) in the busy road corridors and market centers.

4.3 Biological Environment

4.3.1 Flora

The Project (Package-2) areas are devoid of officially designated forest areas⁶. Patches of littoral highly denuded and degraded coastal grass and scrub with occasional trees could be seen adjoining shoreline in some sections. The, remnant littoral forests trees is constituted of *Thespesiapopulnea*, *Lanneacoramandela*, *Ficus religiosa*, *Ficus hispida*, *Calophyllum inophyllum*, *Morinda coreia*, *Syzygium cumini*, *Pongamia pinnata*, *Azadirachta indica*, *Madhuca longifolia*, *Borassus flabellifer*, *Vitex negundo*, *Calamus rotang* and *Pandanus odoratissimus*. In most areas, the natural forests are largely replaced by casuarinas, cashew (*Anacardium occidentale*) and coconut plantations. Other horticultural species including the palm (*Borassus flabellifer*) and a variety of fruit trees including jack.

4.3.2 Fauna

The terrestrial as well as the aquatic habitats of the Project (Package-2) area are highly modified man made habitats with only few patches of degraded natural habitats. Wildlife in these manmade habitats is those which are resilient to the human activities. Among mammals only few small carnivore such as terrestrial rodents (*Tatera indica*), have been reported. Among herpetofauna, flapshell turtle (*Lissemys punctata*), water snakes (*Xenocrophis piscator*, *Cerberus rhyncops* and *Atretium schistosum*), Dog-faced water snake (*Cerberus rhyncops*), and frogs (*Bufomelanostictus*, *Polypedates maculatus*, *Hoplobatrachus crassus*, *Hoplobatrachus tigerinus*, *Euphlyctis cyanophlyctis*, *Euphlyctis hexadactylus*, *Limnonectes limnocharis*, *Microhyla ornata*, *Ramanella variegata*, *Kaloulataprobatica* and *Tomopterna olivacea*) have been reported¹⁰. Waterfowl (storks, herons and egrets) were the most common birds in the backwater estuaries.

⁶ State of Environment Report Tamil Nadu



4.4 Socio-economic Environment

4.4.1 Demographic Features Cuddalore Municipality

The basic demographic characteristics of Cuddalore Municipality are presented in Table 8.

Table 8: Basic Demographic Features of Cuddalore Municipality

| Description | Male | Female | Total |
|----------------------|--------|--------|---------|
| Population | 85,593 | 87,768 | 173,361 |
| Child (0-6 years) | 8153 | 7787 | 15940 |
| Sex Ratio | - | - | 1025 |
| Child Ratio | - | - | 955 |
| Literates | 72083 | 67305 | 139388 |
| Average literacy (%) | 93.03 | 84.15 | 88.54 |

Source: Census India, 2011

The Cuddalore Municipality has a total population of 173,636 of which 85,700 (49.36 %) are males while 87,936 (50.64%) are females as per census India 2011. The total population of children (0-6) in Cuddalore Town is 15940. The child forms 9.19 % of total population of Cuddalore town. There were 8153 boys while 7787 are girls. The sex ratio of Cuddalore Town is 1025 per 1000 males against Tamil Nadu State average of 996. The child sex ratio of girls is 955 per 1000 boys compared to Tamil Nadu state average of 943 as per census India 2011.

In education sector, total literates in Cuddalore town are 139,388 of which 72,083 are males while 67,305 are females. Average literacy rate of Cuddalore town is 88.54 percent higher than Tamil Nadu state average of 80.09 %. The male and female literacy was 93.08 and 84.15 percent respectively (Census India, 2011).

Currently Cuddalore municipality has total administration over 42,174 houses to which it supplies basic amenities like water and sewerage. It is also authorize to build roads within Municipality limits and impose taxes on properties coming under its jurisdiction.



According to the Census India 2011 the population of Schedule Caste (SC) constitutes 13.22 % while Schedule Tribe (ST) population was 0.30 % of total population in Cuddalore municipality.

The slums constitute a significant chunk of the total population. Out of the total population, the slum comprises nearly 30 % in Cuddalore Municipality.

Out of total population, 62,115 were engaged in work or business activity. Of this 48,047 were males while 14,068 were females. In census survey, worker is defined as person who does business, job, service, and cultivator and labor activity. Of total 62115 working population, 84.07% were engaged in Main Work while 15.93 % of total workers were engaged in Marginal Work (Census India, 2011).

4.4.2 Households and Population under Project (Package-2)

Project (Package-2) serves a total of 14000 households/service connections and comprises about 65600 of people in total. It is envisaged that the male female ratio, and educational attainments of the population under the Project is similar to that of Cuddalore Municipality.



CHAPTER 5

ANTICIPATED ENVIRONMENTAL IMPACTS

An analysis of the expected project activities in conjunction with the urban and semi-urban setting in the given work sites (road corridors) and associated ecological backdrop leads to the identification of the following impact for the electrical UG cable construction and operation works.

5.1 During Construction Phase

5.1.1 Physical Environment

Land Use

Temporary change in land use along the electrical underground cable alignment is envisaged during the construction phase. The present lands chosen for electric cable laying are built up areas such as roads and streets which will be reinstated after the cable laying operations.

Environmental Pollution (Air, Water, Noise and Land)

The project actions, particularly trenching and backfilling operations of UG cable laying and dismantling of the OH electrical networks are the key elements which are potential of environmental pollution related to air, water, land and noise.

Air Pollution

Air pollution, particularly fugitive emissions from the excavated earth mismanagement and movement of vehicles carrying the construction material, etc. will result in the emission of dust particles thereby affecting ambient air quality marginally at the site. To minimize the air pollution sprinkling of water twice a day is proposed over the excavated soil of trench. Cost for sprinkling water is taken Rs.500 per 200M so for total trench of 127.7 Km, total cost for water sprinkling is 6.39 Lakhs rupees. Necessary provisions has been made for monitoring the air quality by the contractor during pre construction and construction phase



Water Pollution

There is no significant water pollution during the construction and operation phase. It is recommended to avoid trenching operation works during monsoon season.

Land Pollution

Land pollution related to disposal of the excavated soil, or the sludge of transformer oil on lands, or dumping of the offsite reusable materials in the storage yards of TANGEDCO and other potential scrap materials (Table 9) has potentials of adding the existing land pollution at the storage yards.

Table 9: Scrap Materials from Existing OH networks

| S.No | Description | Project (Package-2) | | |
|------|--------------------------|---------------------|--------|-------|
| | | Cuddalore District | | |
| | | R | Ro | S |
| 1 | HT Line Conductor (km) | R | Ro | S |
| 2 | LT Line conductor (km) | 0 | 36.66 | 24.44 |
| 3 | Service line cable (km) | 0 | 46.104 | 30.74 |
| 4 | Transformers (No) | 0 | 0 | 316.2 |
| 5 | Poles (Nos) | 426 | 24 | 0 |
| 6 | Insulator | 0 | 2927 | 1952 |
| 7 | AB Switch (Nos) | 0 | 9854 | 14782 |
| 8 | Lightning Arrester (Nos) | 0 | 233 | 0 |
| 9 | Cross Arm MT | 0 | 296 | 444 |

Note: R = Reused in the UG cable network, RO = Can be reused offsite in other OH lines, S = Scrap cannot be reused

Noise Pollution

Noise pollution related to excavation equipment, workers activities and movement of construction vehicles are of concern. The concern of noise pollution is high particularly during the night hours as in some of the stretches, construction activities will have to undertaken during the night time to minimise traffic congestions. Necessary provisions have been made for monitoring the noise level by the contractor during pre construction and construction phase.



5.1.2 Biological Environment

Flora

Approximately 24 local planted trees within 5 m distance from the alignment of the Underground electrical cables trench. These trees are located at 8 locations. Details of the location of the sites, number of nearby locating trees and street name is presented in Annex 2. During underground electric cable laying operation there is potential of damage to the tree roots.

Fauna

The proposed land for underground electric cable laying are not used for grazing by domestic animals like cow, buffalo, goats etc; hence negligible disturbance to local animals is anticipated during construction.

5.2 During Operation Phase

5.2.1 Physical Environment

Land Use

The Project works will not bring any change in the land use, except for the small areas at the locations of DTs, Feeder Pillars, Service Pillars by the side of the roads in the public land.

Environmental Pollution

The project is not expected to bring any unwanted air pollution and noise pollution during the project operation phase.

5.2.2 Biological Environment

The Project maintenance works during the operation phase is not envisaged to impart impacts on the surrounding flora and fauna.



CHAPTER 6

ANALYSIS OF ALTERNATIVES

The Project (Package-2) alternatives have been evaluated keeping in view of the Project's objectives and environmental sustainability.

6.1 No Project Alternative

The Project(Package 2) with an objective to replace the overhead electrical HT/LT network by the UG HT/LT network is conceived after the aftermath of Thane Cyclone.

The concept of electrical UG cable evolved because of its robustness to the effects of high speed cyclonic wind gust and flooding compared to the overhead electrical networks. The other advantages of the electrical UG cables compared to the overhead HT/LT network are:

- Enhancement of aesthetic beauty of the sea shore and settlements due to removal of the ugly looking networks of HT/LT electrical lines
- Reduction on the vehicular accident risks due to removal of HT and LT poles along the road side
- Avoid recurrent risk of damage to the overhead electrical networks due to Natural Calamity.
- Avoid risk of theft of energy by direct hooking in overhead lines
- Increase electrical system reliability
- Eliminate the risk of electrocution which is high in overhead HT/LT networks
- Minimize normal wear and tear risk of the electrical network system which is high in overhead HT/LT
- Increased efficiency of the man power in attending the fuse off call which is rather inefficient in overhead electrical system
- Reduce the vulnerability of power supply restoration to the coastal communities on the aftermath of the natural hazards such as cyclone, storm surge, flood and tsunami etc. over the longer term.

In view of the above advantages of electrical UG cables against the overhead electrical networks, there is no project alternative better



than U/G cabling to upgrade the present distribution system in order to enhance its reliability and sustainability. It is therefore, the existing overhead electrical networks are discarded in favor of the electrical UG cable networks.

6.2 Electrical UG Cable Route Alternatives

In the given geo-physical backdrop, two potential alternative alignments for UG cable laying could be conceived, i) Alternative I - along the existing OH HT/LT alignment, and ii) Alternative II - along the existing road corridors .

Alternative I alignment in some sections, while connecting the substations with the settlement areas, pass through the private land and properties. Following this alternative route for UG cables will involve acquisition of private land and property.

The Alternative – II, on the other hand along the existing road network does not involve implication on the private land and property. This option has better construction easement than the Alternative I. As alternative II option has superior construction easement and also avoids land acquisition and other upfront social issues related to land and property acquisition is selected as the best and sustainable alternative compared to Alternative I from environmental and social safeguard aspect.

6.3 Electrical UG Cable Route Alternative within Alternative II Corridor

Haphazard placing of the UG cable within the Alternative II Corridor (existing roads) has potential to damage the other utility infrastructures networks such as communication cables, storm water drainage, sewage mains and collectors, drinking water supply mains and distribution lines etc. Most of the road corridors of the Project (Package-2) area have one or other types or combination of all utility services buried under the roads.

To minimize the risks of disruption of the existing utility services during construction, the alignments of the UG cables has to be planned only after obtaining the precise alignments and depths of the other underground utility infrastructures on the road corridor as far as possible. In case such precise information on the existing utilities



alignments and depths are not available, the construction contractor shall be informed of the situation and made responsible to minimize the damage and for the restoration of the utility services within stipulated time as agreed between the service provider and the service recipient. A working mechanism shall be designed to better address this problem and provisions will be made in the project requirements so that responsibility is fixed.

6.4 Alternatives for Rivers/Wetland and Railway Line Crossing

The service areas of the electrical UG cables extend across rivers, creeks, depressed/water logged areas and railway lines. Electrical UG cables will have to cross these vulnerable areas. In the context of the sub-project's Package 2 area, three options could be conceived: i) UG cable laying beneath the wetlands, Rivers and Railway lines, ii) Dedicated cross –over structures across such areas, and iii) Using the existing crossing structures such as Overhead pole crossing, bridges, culverts, underground tunnels etc.

Laying electrical UG cables underneath the wetlands and River will be avoided in any case, as this involve damage to the aquatic biota, habitat and water quality. Apart from this, across the river and wetland, special permission will be required as such crossing sites invariably locate within CRZ II and III as per CRZ notification. For the Railway line crossing, special permission, clearance and approval is required from the Railway authorities.

Dedicated cross over structures option also has a risk of damage to the surrounding ecological system of wetlands and River, while it will require special permission, clearance and approval from Railway authorities for Rail line crossing. Besides, this also involves high financial costs.

Use of the existing pole structures, bridges and culverts and underground tunnels across the rivers, creeks and railway line avoid issues related to ecological damage, water quality, lengthy approval processes etc. This option, however, has potential of increasing the length of the UG cable system. Compared to the costs involved in the first two options, cost of the additional UG cables is cheap. It is therefore this option is opted as the best sustainable option from environmental and economic perspective.



6.5 Alternatives to Minimise Tree cutting / impacts of trees

The Project (Package -2) UG cable trenches pass along the area with standing trees (24 Nos. within 5m distance) at 6 locations (refer Annex 1 and Annex 2). The UG trenches are flexible structures and can be aligned by slight alteration of the route to safeguard the standing trees. It is therefore to avoid the damage/loss of standing trees, the contractors shall abide by such practices of slight alteration of the cable route in such areas.

6.6 Alternatives for Reuse and Waste Minimization

The Project (Package 2) waste stream relates to: i) dismantling of the existing overhead network with wastes materials such as transformers, conductors, poles etc. and ii) excavated earth while laying the electrical UG cables.

In the context of the Project area, these wastes could have multiple reuse options such as: i) reuse of the existing transformers and oil contained in DTs by filtering in the UG cable network system and elsewhere in a different project area ii) reuse of overhead conductors in the rural area electrification project elsewhere iii) reuse of the electrical poles for street lighting (many of the electrical poles in the sub-project area are also used for street lighting and they can be left where they are for street lighting) and iv) reuse of the excavated earth for backfilling and compaction of the UG cable trenches.

The reuse options listed will reduce the burden of waste management on site and off site and shall be applied wherever applicable. The remaining dismantled wastes related to overhead electrical networks shall be discharged through the authorized waste disposal vendors. Remaining excavated earth after backfilling will be transported to land fill site of the Cuddalore Municipality. As this is inert material, it can be used as soil cover of the municipal solid waste.



CHAPTER 7

ENVIRONMENTAL MITIGATION MEASURES

This section prescribes the environmental and social mitigation measures for the environmental and social safeguard from the anticipated identified impacts.

7.1 During Construction Phase

First and foremost mitigation measures for all types of anticipated impacts is to make local communities aware of the Project works, anticipated impacts resulting from the construction activities and mitigation actions planned for environmental and social safeguards. For the preparation of the local communities following measures are prescribed prior to the start of the construction activities at all construction sites.

- **Information to the local communities :** The project manager, social expert will use various communication tools like Print (brochure, leaflet, flyer, and newspaper both local and national); Electronic (FM radio, TV) in disseminating the project related information to the project affected people and the community. Prior to the start of the construction works, the contractor in co-ordination with the IA shall disseminate information related to project construction particularly schedules of the construction works through public notices at newspaper, Radios, miking, distribution of pamphlets to the potentially affected communities (road users, utility service users, shop keepers, vendors, education and health institutions, local shrines, traffic police, municipal authorities and ward offices sets etc.).The information will also be provided on the potential impacts and measures to be taken to address the anticipated impacts and expected timings of reinstatement of damaged infrastructures and disrupted services. The notices, brochures and pamphlets will provide information on the project construction route, potential impacts and its gravity and steps taken by the project to minimize the impacts. These and similar efforts of information dissemination and disclosures will also be continued during project implementation periods. The mode of communication to disseminate information will be in local languages understandable to general public, affected communities and stakeholders. The



affected vendors will be notified before 30 days of construction start as per the legal provision. At least one month advance notice will be given to the affected farmers for crop harvest.

- **Project Information:** The contractor install Project Information Boards within the project area at important locations (minimum 3 locations) indicating the project information like (area of project), Contractor details (Name, phone number , address), project duration , project cost, Name of Implementing Agency and contact details of grievance redressal cell.
- ***Frequent interaction with the stakeholders:*** Frequent and regular interaction with the involved stakeholders (community leaders, shop keepers, vendors, utility service providers, municipal and ward level administrative authorities, traffic police, community watch groupsets) prior to the pre-construction and during construction till reinstatement of damaged infrastructure and disrupted services should be a priority activity of the contractors in coordination with IA.

7.1.1 Physical Environment

Land Use

- **Reinstatement and Rehabilitation of the Temporarily affected land:** The road infrastructure and temporary camp sites disrupted by the trenching operation shall be reinstated as to the approval conditions of the concerned road authority and the landowners.

Environmental Pollution (Air, Water, Noise and Land)

Air Pollution:

- **Strict compliance to work schedules of the day:** UG cable laying operations will comply with a work schedule that ensures completion of trench excavation, laying of the cable and backfilling on the same day. Such action limits the fugitive dust emissions from the excavated materials.
- **Water sprinkling:** In the given climatic conditions, moisture content of the excavated earth could be lost within few hours of excavation and the loose earth could be easily picked up by the wind gusts. To minimize the wind born fugitive dust emissions



from the excavated earth, light water sprinkling shall be exercised at least two times a day in the late morning and afternoon.

- **Deposition of the excavated earth on the footpath side of the road:** The excavated earth from the UG cable trenches shall be placed on the foot path side of the road to minimize the wind borne fugitive emissions from the spoil material by the whirling air currents of the moving vehicles. Necessary protection arrangements will be made to retain the excavated earth piled near the drainage on either side of the road so that the flow of drainage will not be choked.

Water Pollution

- **Avoid UG cable trenching operation in the monsoon season:** The Project work sites experiences high amount of precipitation in the monsoon season (September – December) and is usually associated with high water runoff. To minimize the water pollution effects of monsoon runoff washout, the monsoon season shall be avoided for the UG cable trenching operation.
- **Chemical Testing of the Transformer oil:** Prior to the dismantling of the existing transformer, the oil used in the transformer shall be checked by the contractors for PCBs. The PCB contaminated oil shall be managed separately through authorised vendors.
- **Prohibition on the discharge of solid and liquid wastes on the pathways of receiving water bodies:** All solid and liquid wastes generated at the construction sites, and in the camps shall not be discharged to the pathways of the receiving water bodies.

Land Pollution

- **Construction site and Camp Waste Management:** Solid and liquid waste generated at the construction sites or at the camps shall be properly collected, stored, and managed. Left over inert earth materials shall be transported to landfill site of the Cuddalore municipality, while the spent oils and lubricants or other hazardous waste are disposed through the authorised vendors
- **Management of the Overhead Electric Network Wastes:** The onsite unused waste materials of the OH electric cable networks shall be managed through the authorised vendors.



These materials shall not be stored in the TANGEDCO sites for later reuse, as there is no space for storing the materials.

Noise Pollution

- **Restriction on the use of noisy equipment's at the night time working areas:** Noisy equipment's and vehicles shall be restricted for use in areas where the work schedule requires night time works.

7.1.2 Biological Environment

Flora

- **Protection of trees of the underground electrical cable alignment:** The trees located along to the underground electric cables (Refer Annex 2, for locations) shall be protected by slightly altering the alignment of the cable to protect the trees.

7.2 During Operation phase

7.2.1 Physical Environment

As adverse impacts are not anticipated, mitigation measures are not proposed.

7.2.2 Biological Environment

As adverse impacts are not anticipated, mitigation measures are not proposed.

**CHAPTER 8****STAKEHOLDER CONSULTATION
AND INFORMATION
DISCLOSURE****8.1 Consultations with Institutional Stakeholders**

Stakeholders' consultation has been done to collect the following specific information.

- Site visit for underground electric cable networking
- Alternative alignments for underground electric networking
- Any ecological sensitive area passing through / close to underground electric cable networking sites
- Project features related with environmental and social issues
- Secondary data base on utility services, socio-economic features, health concerns available maps etc of the Project area

List of key stakeholders consulted during 3-9 April, 2015, for the project at institutional level is given in Table 10.

Table 10: List of stakeholders during Institutional Consultation

| S.N | Institution | Person Consulted | Designation |
|------------|--|-------------------------|------------------------------|
| 1 | Tamil Nadu Generation and Distribution Corporation (TANGEDCO), Office of Superintendent Engineer , Cuddalore | Mr. R. Ayyappan | Executive Engineer /General |
| 2 | TANGEDCO, Office of Executive Engineer , Operation and maintenance Cuddalore | Mr. Kamaraj | Executive Engineer |
| 3 | TANGEDCO, Office of Executive Engineer , Operation and maintenance | Mr. S. Kumar | Assistant Executive Engineer |



| S.N | Institution | Person Consulted | Designation |
|-----|---|--------------------|-----------------------------------|
| | Cuddalore | | |
| 4 | Tamil Nadu Water and Drainage Board (TWADB) –Cuddalore | Mr. Ram Nath | Executive Engineer |
| 5 | BSNL - Cuddalore | Mrs. K. Shantha | Divisional Engineer |
| 6 | BSNL - Cuddalore | Mr. T. Ramchrijam | SDE |
| 7 | BSNL - Cuddalore | Mr. M. DuraiRajan | SDE |
| 8 | Office of Divisional Engineer, Highway Department - Cuddalore | Mr. Rajendiran | AE (Highway) |
| 9 | Cuddalore Municipality | Mr. R.Murugesan | Municipal Commissioner |
| 10 | Cuddalore Municipality | Mr. K. Murugesan | EE |
| 11 | Cuddalore Municipality | Dr. N. Shiva Kumar | Municipal and Port Health Officer |
| 12 | Pollution Control Board, Cuddalore | Mr. A. Raja | Environment Engineer |
| 13 | Traffic Police , Cuddalore | Mr. K. DandaPani | Inspector |

8.2 Informal Consultation with Local Potentially Affected Communities

The informal meetings and discussions with the temporary shopkeepers and vendors likely to be affected in various locations within the project sites and town were conducted. Table 11 presents the places of such meetings and dates of the meetings, while Annex 3 represents the lists of the consulted people at different locations.

**Table 11: Details of Informal Consultations Held in Cuddalore Municipality**

| Location/street | Municipality / Town | Types of Vending | Date | Total numbers of people consulted |
|------------------------|----------------------------|--|-------------|--|
| Old City Bus Stand | Cuddalore | Fruits & vegetables | 31/7/2015 | 13 |
| Fish Market, Old Town | Cuddalore | Fish, fruit, vegetables | 31/7/2015 | 8 |
| Main Bus Stand Area | Cuddalore | Vegetables, fruit, melamine items, watches, locks, flowers, etc. | 4/8/2015 | 12 |

The Key issues /concerns raised by the consulted vendors are as follows:

- The vendors are not against the project of conversion of OH lines to UG lines but their main concerns were to ensure running of their business without disturbance.
- The vending business is the main source of family income and they cannot tolerate any types of involuntary disruption and dislocation of their business, however they did not show any objection, if alternative location is provided nearby to run their business during the construction period of one or two days
- The construction works should be done fast and restoration of damaged road (vending location) should be completed as soon as possible
- They also suggested to work and complete a particular stretch at night so that they can run their business as usual at day time

8.3 Formal Public Consultation

Before finalization of ESA document, due consultation with public at large was done by issuance of the notice and invitation through the Collector office of Cuddalore district. More than 47 participants took



part in the consultation meeting. In the meeting the summary draft ESA report was made available to the participating members of the consultation meeting. The comments / suggestion offered by the public were given due weightage and incorporated in this ESA report. The stakeholder consultation meeting was also covered in the local newspaper with priority news.

Minutes of Meetings, Public Notification, invitation letters, excerpts of the consultation meeting and lists of participants attended including Newspaper coverage of the meetings are attached in Annex 4 as enclosure 1 to 6.

8.4 Disclosure of ESA Report

This ESA Report shall be disclosed in full in English language and Tamil language on PMUs and TANGEDCO's websites (homepages). Hard copies in English and Tamil shall be made available for public at district Collector's office, municipality office and local TANGEDCO offices. These documents shall be made available till certificate of completion is issued to contractor. PMU & TANGEDCO shall ensure that these documents are disclosed as per the EMP provisions and World Bank guidelines.



CHAPTER 9

ENVIRONMENTAL MANAGEMENT PLAN (EMP)

9.1 Components of EMP

The EMP consists of a set of mitigations, monitoring and institutional measures to be taken for the project to avoid, minimize and mitigate adverse environmental impacts and enhance positive impacts. The plan also includes the action needed for implementation of these measures. The major components of the Environmental Management Plan are:

- Institutional arrangements and responsibilities
- Mitigation of potentially adverse impacts and supervision and auditing during project implementation and operation;
- Environmental and Social monitoring;
- Chance Find Procedures;
- Incident management and emergency response procedures;
- Corrective actions,
- Record keeping and reporting
- Complain handling and Grievance redress;
- Capacity building
- EMP review and update
- EMP implementation schedules and plans
- EMP costs


9.2 Institutional Responsibilities, Mitigation and Monitoring

9.2.1 EMP Institutional Arrangements and Responsibilities

The TANGEDCO will ensure implementation of the project EMP with the support of its environmental and social staff. **Figure 3** shows the institutional arrangement for implementation of the EMP.



Figure 3: Institutional Arrangements for the EMP Implementation



The roles and responsibilities of the involved parties in the EMP implementation are depicted in **Table 12**.

Table 12: Roles and Responsibilities for EMP Implementation

| EMP Implementing Partners | Roles and Responsibilities |
|--|--|
| Project Management Unit (PMU) Government of Tamil Nadu & TANGEDCO | Overall co-ordination of the Project's EMP activities; Interactions with the different Implementing Agencies on the status / progress of the sub-projects, consultants / contractors employed by these Implementing Agencies and NGOs |



| EMP Implementing Partners | Roles and Responsibilities |
|--|--|
| | <p>supporting implementation; Co-ordination on EMP activities with the World Bank</p> |
| <p>Project Manager- (SE/Cuddalore EDC/Cuddalore)Tamil Nadu Generation and Distribution Corporation (TANGEDCO -PM)</p> | <p>Overall responsibility for environmental and social performance of and implementation of EMP Decision-maker on applicable policies to the Project works Oversight supervisory role during the construction phase Review reports of the Supervising engineers Approves changes to the EMP, as necessary, as part of an adaptive approach to environmental and social management of the Project works in line with EMF of CDRRP. Responsible for working with stakeholders in developing an conflict free approach Arrange or co-ordinate for the acquisition required approval consent, permission from the respective governmental institutions on the request of the contractors and the Supervising engineers</p> |
| <p>Project Implementation Unit (PIU) EE/Nodal officer CDRRP(EE/O&M/ Cuddalore)</p> | <p>Develop an environmental steering Committee headed by the Project Environmental Officer comprising members from Planning Departments of Municipal/Town Panchayat, Traffic Police, District Magistrate Office, and Civil Society to ensure that actual implementation of the environmental/Social monitoring and management is carried out; Provide training on the environmental aspects of the project to the staffs of TANGEDCO and contractors and the roles of the concerned parties for the environment and social safeguard of the sub-project; Periodic review of the environmental monitoring reports including site visits and feed back to the TANGEDCO Representing the project at community meetings; Ensure effective community liaison and fulfilling</p> |



| EMP Implementing Partners | Roles and Responsibilities |
|---|---|
| | commitments to facilitate public consultation throughout the project cycle |
| Supervising Field Engineer (AE/AEE) (deals Environmental activities) | <p>Management, implementation, monitoring and compliance of the EMP and any approval conditions, including construction supervision and performance of all contractors and subcontractor; Review of EMP performance and implementation of correction actions, or stop work procedures, in the event of breaches of EMP conditions, that may lead to serious impacts on local communities, or affect the reputation of the project; Ensure effective communication and dissemination of the content and requirements of the EMP to contractors and subcontractors; Assisting the contractor with implementation of EMP; Monitoring of EMP performance; Report environmental performance of the sub-projects to TANGEDCO, PIU, PMU and World Bank; Prepare environmental reports summarizing project activities, as required; Participate at community meetings organized by PIU; Request to TANGEDCO for the required approval, consent, permission as required by the formats as required by the law.</p> |
| Contractor (Environmental Expert) | <p>A reference to the Environment Assessment and EMP has been made in the bidding documents for the reference of contractor so as to adhere to it strictly. Preparation of the management plans and take approvals from the supervising engineers as required by EMP Implementation of the EMP Prepare and maintain records and all required reporting data as stipulated by the EMP, for submission to the Supervising Engineer</p> |



| EMP Implementing Partners | Roles and Responsibilities |
|-----------------------------|--|
| | <p>Ensure that all construction personnel and subcontractors are informed of the intent of the EMP and are made aware of the required measures for environmental compliance and performance</p> <p>During construction, maintain traffic safety along roadside construction sites in co-ordination with the traffic police and local communities with special emphasis on the key sensitive sites and market areas</p> |
| Project Stakeholders | <p>Constitute Citizen Monitoring Committee with at least 33% of women members</p> <p>Participate in the consultation meetings organized by the PIU</p> <p>Participate in the onsite monitoring and review of the environmental performance reports of the supervising engineers</p> <p>Provide feedback to the TANGEDCO for the corrective actions, if so required</p> |

9.2.2 EMP Mitigation and Monitoring

The identified environmental issues and suggested mitigation measures with institutional arrangements for implementation, supervision and auditing have been provided in matrix format (Environmental Management Plan) in Table 13. The EMP framework has specifically assigned roles to the responsible stakeholders in conjunction with what to implement, when to implement and where to implement. Similarly, it has also assigned roles for supervising and over sighting authority specifying what indicators were to be monitored for timely corrective actions. For each of the mitigation measures prescribed financial resources required is also estimated. The required financial resources are broadly categorized into two groups:

- i) Resource in built with contract bid: This includes cost items which are customarily inbuilt with contract bid such as on site spoil management, reinstatement of damaged utilities etc.



- Such costs have not been estimated separately as these costs are already inbuilt with contract bid, and
- ii) Resources which are not included in contract bid: This includes costs customarily not included in contract bid such as dust suppression, chemical testing, compensation to vendors etc. These costs have been estimated in consideration of work schedules and time to accomplish the tasks besides sensitivity of the potential issue.

Apart from the above, there are certain mitigation items which do not require additional costs, but only managerial efforts. To ensure that such measures are implemented, it is prescribed to include additional clauses in the contract bid documents.

Prime responsibility for the implementation of prescribed measures lies with agency/stakeholder indicated as responsible for implementation, whereas the role of indicated supervisor and over sighting agency is to ensure that the measures are implemented in time as prescribed. The role of the IA is to ensure the needed resources.



Table 13: Environmental Mitigation Management, Supervision, and Review Plan

| Possible Impacts | Mitigation objective / Standard | Mitigation Measures* | Agency responsible for mitigation | Supervision Indicators | Agency responsible for Supervision | Over sighting or Agency | Estimated costs (IC) |
|----------------------------------|---|---|-----------------------------------|---|------------------------------------|-------------------------|-----------------------|
| During Pre-construction | | | | | | | |
| Conflict with Approval Agencies | Avoid conflict with approval agencies | Acquisition of permits and approvals as required | PIU | Approval, permit or consent letters | TANGEDCO– (EE O&M Cuddalore) | SE / PM | 400000 ⁷ |
| During Construction Phase | | | | | | | |
| Physical Environment | | | | | | | |
| Land Use | Reinstate the land use to pre-project stage | Reinstatement of road infrastructure concomitant to trench filling at all sites | Contractor | Site visit, observation, and reinstatement certificates | AE/AEE | EE(Nodal officer CDRRP) | Include in civil bid |
| Air Pollution | Minimize air pollution | Strict compliance to work schedules of the | Contractor | Compliance to the | AE/AEE | EE/Nodal officer | Include the clause in |

⁷ This is provisional cost. It may be required for the preparation of required maps from the authorized authorities for CRZ classification of the work sites. Such authorities may require some fees against such works.



| Possible Impacts | Mitigation objective / Standard | Mitigation Measures* | Agency responsible for mitigation | Supervision Indicators | Agency responsible for Supervision | Over sighting or Agency | Estimated costs (IC) |
|------------------|---------------------------------|--|-----------------------------------|--|------------------------------------|-------------------------|--|
| | | day in the dense settlement, high activity areas and sensitive sites | | conditions | | CDRRP | the contract bid as responsibility of contractor |
| | | Water sprinkling at least twice a day (9 Am and 1.30PM) | Contractor | Site visit, observation, and community feed back | AE/AEE | EE/Nodal officer CDRRP | 638500 @ 500/200m |
| | | Deposition of the excavated earth on the footpath side of the road during construction and transport / management of the left spoil in the municipal waste management sites concomitant to | Contractor | Compliance to the conditions | AE/AEE | EE/Nodal officer CDRRP | Inbuilt in Civil Bid |



| Possible Impacts | Mitigation objective / Standard | Mitigation Measures* | Agency responsible for mitigation | Supervision Indicators | Agency responsible for Supervision | Over sighting or Agency | Estimated costs (IC) |
|------------------|------------------------------------|---|-----------------------------------|---|------------------------------------|-------------------------|--|
| | | completion of trench filling operations | | | | | |
| Water Pollution | avoid and minimize water pollution | Avoid UG cable trenching operation in the monsoon season | Contractor | Compliance to the conditions | AE/AEE | EE/Nodal officer CDRRP | Include the clause in the contract bid as responsibility of contractor |
| | | Chemical Testing of the Transformer oil from 508 transformers | Contractor | Test results from laboratory | AE/AEE | EE/Nodal officer CDRRP | 254000 @ 500/ transformer |
| | | Prohibition on the discharge of solid and liquid wastes on the pathways of receiving water bodies | Contractor | Site visit on active construction sites and camps | AE/AEE | EE/Nodal officer CDRRP | Inbuilt in Civil Bid |
| Land Pollution | Avoid land Pollution | Construction and Camp Waste Management Provision | Contractor | Site visit on active | AE/AEE | EE/Nodal officer | Inbuilt in Civil Bid |



| Possible Impacts | Mitigation objective / Standard | Mitigation Measures* | Agency responsible for mitigation | Supervision Indicators | Agency responsible for Supervision | Over sighting or Agency | Estimated costs (IC) |
|------------------|---------------------------------|--|-----------------------------------|---|------------------------------------|-------------------------|--|
| | | of adequate sanitation facilities Garbage collection through adequate collection bins and disposal to Municipal system. | | construction sites and camps | | CDRRP | |
| | | Management of the Overhead Electric Network Wastes (within a month of OH the dismantling works) | Contractor and TANGEDCO - PM | Site visit, records of contract with the authorized vendors | TANGEDCO-AE/AEE | PMU | 350000 ⁸ (lump sum) |
| Noise Pollution | Minimize noise pollution | Restriction on the use of noisy equipment's at the night time working areas | Contractor | Compliance to the conditions | AE/AEE | EE/Nodal officer CDRRP | Include the clause in the contract bid as responsibility |

⁸This is provisional cost, which may be required for public notification for auction and charges for management by authorized vendors etc.



| Possible Impacts | Mitigation objective / Standard | Mitigation Measures* | Agency responsible for mitigation | Supervision Indicators | Agency responsible for Supervision | Over sighting or Agency | Estimated costs (IC) |
|-------------------------------|---------------------------------|--|-----------------------------------|---|------------------------------------|-------------------------|--|
| | | | | | | | ty of contractor |
| Biological Environment | | | | | | | |
| Flora | Avoid loss of tree | Protection of trees (within 5 m of the UG trench) of the underground electrical cable alignment at 6 sites (refer Annex 2) by changing alignment of UG trench as required. | Contractor | Site observation and records of tree damage | AE/AEE | EE/Nodal officer CDRRP | Include the clause in the contract bid as responsibility of contractor |
| During Operation phase | | | | | | | |
| Physical Environment | | | | | | | |
| No Impact | | | | | | | |
| Biological Environment | | | | | | | |
| No Impact | | | | | | | |

Note: For details of the mitigation measures refer Chapter 7



Work Supervision

Scheduled supervision and review of Project (Package-2) construction activities is required to ensure that works are undertaken in accordance with the Project design, environmental plans, permits, approvals, contract conditions, and the principles outlined in this EMP. The overall contractual responsibility of the supervision and monitoring works of the contractor's rests with the Supervising engineers. However, on the environmental matters the supervision and reviews will be mainly carried out by the Environmental/Social expert of supervising engineer while contractor will implement the corrective actions, EMP provisions, other contractual obligations and permit and approval provisions. Supervision oversight will be carried out by PIU.

Pre-construction Phase Pre-construction inspections of the Project sites shall be jointly undertaken by the supervising engineer, contractor and the PIU once the construction contractor has surveyed and pegged each site. These inspections will serve to:

- confirm the location of Project sites;
- identify site specific construction and environmental issues;
- oversight access, services and sensitive sites that will be temporarily disrupted during construction;
- Plan construction phasing at Project sites.

During the inspection, the Environmental/Social expert of Supervising engineer and contractor shall discuss and agree upon the above issues. In particular, the Social expert will document the type and location of all sensitive sites and market services that are to be temporarily disrupted and provide a copy of this to the contractor.

Construction Phase - The AE/AEE shall undertake daily, weekly and monthly inspections of construction sites, work areas, and workforce camps during the construction period. This will involve the protocols described below.

- excavation activities - daily
- stockpiling of excavated material- daily
- spoil disposal - daily



- chemical, fuel and other storage - weekly
- site rehabilitation works – daily
- workforce camps - monthly
- displaced vendors - daily

If any activities are not being undertaken in accordance with the contract and EMP conditions, the AE/AEE shall document these activities and specify corrective measures. A copy of the work order will be passed to the contractor personnel at site and PIU.

Post Construction Phase - The AE/AEE shall undertake a post-construction certification inspection of each completed site. The AE/AEE shall inspect all reinstated access and local services of all temporarily disrupted areas. The AE/AEE shall certify each site if it is in accordance with all contract and EMP conditions, or provide a written list of remedial actions to the contractor to be completed prior to certification.

Environmental Review (Audit)

PIU head will undertake internal environmental review at least once every month. PMU shall undertake an external compliance quarterly to assess the project's compliance with the EMP, the effectiveness of mitigation measures and institutional development, and whether or not any unanticipated effects occurred as a result of project activities and report to The World Bank. The review shall be based on a site inspection and the monitoring reports of the contractors, AE/AEE and PIU internal review.

9.2.3 Environmental Monitoring

Environmental monitoring will occur during Project design/pre-construction, construction and operation, to provide baseline data, confirm project compliance and to detect any adverse impacts/non-compliances.

Front Line Monitoring - Construction contractor as a responsible front line implementation agency shall monitor all of its activities on day to day basis.



Internal Monitoring - Internal monitoring of the mitigation measures will also be carried out by AE/AEE as a part of supervision and monitoring.

PIU will conduct instrumental monitoring for baseline data in the pre-construction phase, while contractors will conduct instrumental monitoring of the environmental indicators for compliance and impact monitoring during Pre-construction and construction phase.

Table 14 provides the matrix of environmental indicators, monitoring methods, monitoring locations, monitoring frequency and monitoring responsibility along with the costs.



Table14:Environmental Monitoring Plan

| Monitoring Indicator | Monitoring method | Monitoring Location | Monitoring Frequency | Responsibility | Costs (IC) |
|--|---|---|---|----------------|-----------------------|
| Pre-construction phase – Baseline Monitoring | | | | | |
| 24 hours PM10 and PM 2.5 | High Volume Air sampler | Two places at the centre of the Project area (Dense settlement area) | Once | Contractor | 30000.00 @ 15000/site |
| 24 hours Noise Level (leq. dBA) | Sound Level Meter | Two Places at the Centre of the Project area (Dense settlement area) | Once | Contractor | 10000.00 @5000/site |
| Construction Phase – Compliance and Impact Monitoring | | | | | |
| 24 hours PM10 and PM 2.5 | High Volume Air sampler | At the sites of Baseline monitoring at the time of construction/excavation on this site | Once during active construction period | Contractor | 30000.00@ 15000/site |
| 24 hours Noise Level (leq. dBA) | Sound Level Meter | At the site of Baseline monitoring at the time of construction/excavation on this site | Once in active construction period | Contractor | 10000.00@ 5000/site |
| Water Supply | Laboratory Analysis for parameters E-coli bacteria, | All residential construction camps | Once a month during construction period | Contractor | 25000 (lump sum) |



| | | | | | |
|--|--|--|------------------------|--------------------------------------|---|
| Environmental Mitigation measures listed in Table 13 | Site observation and consultation with communities and Vendors | All Project sites as per Annexure 1 and Annexure 2 | Daily, weekly, monthly | AE/AEE/EE/Nodal officer CDRRP of PIU | Cost included in construction management cost |
|--|--|--|------------------------|--------------------------------------|---|



Database of environmental monitoring results will be established by AE/AEE. If monitoring results indicate non-conformance, the AE/AEE shall inform the project PIU immediately, and written orders for appropriate remedial action shall be passed to contractor for compliance by AE/AEE.

External Monitoring - An external monitoring of the Project's environmental and social performance shall be conducted by PMU. The guideline and recommendations of the external monitoring shall be passed through PIU for corrective actions.

9.2.4 Chance Find Procedures

The Project is not expected to affect the visible on surface archeological artifacts. In the event that an archeological resource is discovered during the UG cable trenching process a Chance Find Procedure will be implemented. A Chance Find includes record keeping and expert verification procedures, chain of custody instructions for movable finds, and clear criteria for potential temporary work stoppages that could be required for rapid disposition of issues related to the finds. In accordance with this Procedure, work will cease on a site where archaeological material is found. The construction contractor with the find of the archeological artifacts will immediately stop the work and report to AE/AEE. The AE/AEE will inspect and secure the site, and will then contact State Department of Archaeology through PIU for advice and arrange for a survey or salvage work as appropriate.

The project implementation area has a long history of religious activities including construction of shrines at different times. Some of these shrines still exist while a few may have been turned into rubbles. In view of such potential, there is likely to involve chance find during UG cable trenching. To ensure that the chance find objects of archeological value are duly taken care of, a provisional sum of Rupees 1000000 has been allocated for the package works. The costs shall cover the Charges for the experts from Archaeology departments, study of the artefacts, and relocation on or off site of the artefacts etc.



9.2.5 Incident Management and Emergency Response Procedures

Incident Management Procedures

The contractor and the AE/AEE will prepare Incident Management Procedures for the Project work phases. Joint meeting of the AE/AEE and the contractors at the onset of the construction shall emphasize the importance of documenting all environmental and social incidents. The contractor shall immediately report all incidents to the AE/AEE at site. These incidents may include:

- theft or misplacement of construction materials;
- outbreak of epidemic
- fatal and serious accidents
- construction activities undertaken outside approved sites;
- damage to private or Government structures or land;
- hazardous material spills; and,

The AE/AEE and contractor shall investigate and act on all incidents by:

- identifying the cause of the incident;
- identifying and implementing necessary corrective action(s);
- identifying personnel responsible for carrying out corrective action(s);
- Implementing or modifying controls necessary to avoid repetition; and, recording any changes required in written procedures.

Emergency Response Procedures

The contractor and AE/AEE will develop and implement *Emergency Response Procedures* for the construction phases. The following steps shall be included in the procedures.

- **Define the Problem**
 - The immediate problem is established, to facilitate a review of available options for short-term action.
- **Manage the Situation**
 - The safety of any persons, either workers or others involved in Project construction or operation, is to be ensured as a first priority.



- Environmental damage is to be quickly minimized. All emergency action should take place as soon as possible after the event.

9.2.6 Corrective Actions

Environmental non-conformances usually require the implementation of corrective actions specified in non-conformance reports.

Construction Phase - The contractors will implement the corrective action/s recommended by the AE/AEE. The contractor shall then notify the AE/AEE of the completion of the corrective action/s. The AE/AEE will verify the satisfactory implementation of corrective actions during the subsequent inspection and sign off on the non-conformance/s if satisfactorily rectified, or make a further request, if unsatisfactory. AE/AEE will submit a non-conformity statement to PIU that will be certified by PIU.

Operation Phase - During Project operation, TANGEDCO will approve the corrective action/s recommended by the Maintenance Section of TANGEDCO. Maintenance Section of TANGEDCO shall implement the corrective actions in the time specified and shall notify the TANGEDCO of the completion of the corrective action/s so that the satisfactory implementation can be verified by the concerned authority of TANGEDCO.

9.2.7 Record Keeping and Reporting

Two types of reporting and documentation will be required during the construction phase. The construction contractor will document and report monthly progress for internal reporting, While the AE/AEE/PIU will prepare an environmental and social monitoring and compliance report quarterly for external circulation to the stakeholders.

The contractor will prepare a monthly report of the environmental measures implemented and corrective actions undertaken for the month. The report shall include the followings:

- Environmental measures implemented for the month



- Corrective actions implemented for the month
- Instrumental monitoring results of the month
- Compliance status of the EMP, and permit conditions for the month
- Reasons of noncompliance and plans to comply with schedule
- Employee records of the month (non-immigrant and immigrant etc.)
- Monthly reports on Safety Practices, All accidents and corrective actions undertaken
- Records of the work accomplishment (line length of UG cable laying) for the month
- Records of excavation volume for the month
- Records of spoil management volume for the month
- Records of incident managements for the month
- Records of emergency response if any for the month
- Records of Chance finds if any

The AE/AEE and PIU jointly will prepare an environmental social performance report quarterly based on supervision, monitoring and auditing of the project. The report besides the elements of contractor reporting will incorporate the results of supervision and monitoring and instrumental monitoring including corrective actions recommended, corrective actions accomplished, grievances received, grievances addressed etc. and recommendations for EMP modification if any.

In the operation phase, the Maintenance Section of TANGEDCO (AE/AEE/EE/Nodal officer CDRRP) will prepare an environmental and social performance report quarterly throughout the project operation period.

9.2.8 Capacity Building

Though there is environmental cell at the central level of TANGEDCO, at the district and sub-project division level there is general lack of such sections to oversight the environmental and social related issues. The sub-project division is primarily responsible for day in day out execution of works related to safeguards during project implementation and operation. In other words, there is limited capacity of the existing staffs. It is therefore to improve the work quality, for better results, to easily manage challenges and to minimize environment and social impacts etc., training is needed at the sub-project division and district level.



In order to capacitate the all those responsible for the management, implementation and operation of any aspect of the EMP at the sub-project division level and district level need adequate training for their role and responsibilities related to sub-project safeguard issues. Training records shall be maintained on site, for each employee, to provide evidence for auditing/inspection purposes. Specific training requirements concerning EMP shall include.

- Principles and procedures for environmental impact assessment
- Fundamentals of environmental management
- Compliance assessment, monitoring and follow-up
- Environmental audits
- Community relations and public consultation procedures;
- Air, noise and water sampling procedure
- Waste management
- Fuel and hazardous materials management
- Construction camp management
- Community health and safety issues
- Occupational health and safety issues
- Specific issues related to construction impacts such as access disruption, sensitive sites, archeological sites etc.

The proposed training will be of cascade mode. About 20 master trainers will be trained by a reputed institution; these master trainers in turn will train all the concerned project management and operation staffs including the contractor's field personnel. The tentative cost of master training of 20 master trainers is estimated as Rs. 1,50,000. Similarly estimated budget for the capacity building training to the project staff of TANGEDCO by master trainers is Rs. 2,50,000, which shall cover fees to the trainer involved previously in similar projects, allowances to trainee, stationary and other space arrangements.

Training will be provided at three stages, one in pre-construction phase, and another during construction phase and other one in final phase.



Table 15 Training Schedule

| S.No. | Training Concept | No. of Trainees | Duration | Expenditure | Output |
|----------|---|-----------------|----------|-------------|--|
| 1 | Training or master trainers: (i) donor's IR, IP and environment safeguards policy principles, scope and triggers, definitions, and management; (ii) process and procedures of conducting ESA preparation of EMP; (iii) principles and procedures of land acquisition; (iv) public consultation and participation; (v) entitlements and compensation & assistance disbursement mechanisms including livelihood restoration and relocation; (vi) grievance redress; (vii) implementation of resettlement plan/indigenous peoples plan; and (viii) monitoring of EMP/RAP and VCDP implementation and its reporting | 20 | 5 days | 1,50,000 | Production of master trainers having sound knowledge on social and environmental safeguard management process and procedures |
| 2 | Build safeguard capacity of officials/staff of TANGEDCO and also some persons of contractor in terms of screening of likely potential impact, conduct social assessment, processes and procedures of impact mitigation, implementation of EMPs, continuing meaningful consultations with | 20 | 2 Days | 1,00,000 | Better quality of work to meet & Safe working environment |



| | | | | | |
|---|--|----|--------|----------|---|
| | project affected peoples, documentation and reporting of all safeguard activities and safeguards plan disclosure. | | | | |
| 3 | Training about UG Cable laying , installation , Jointing, charging and commissioning adhering to social and environmental procedures prescribed in the EMP | 20 | 2 Days | 1,00,000 | For efficient supervision of the work |
| 4 | Training about operation and maintenance of UG Cable distribution system& co-ordination procedure for dismantling of existing OH lines adhering to social and environmental procedures prescribed in the EMP | 20 | 2 Days | 50000 | For trouble free run of UG Cable network and Proper Planning of Dismantling |



CHAPTER 10

RISK ASSESSMENT AND DISASTER MANAGEMENT

10.1 Risk Assessment

10.1.1 Need for Risks assessment

The purpose of this assessment is to offer guidance on those factors that should be addressed by TANGEDCO or by the Contractor and their personnel during construction and operation phase to ensure that the Health, Safety and Environment risks to personnel or assets are minimized. This project is of the nature of cable laying in the excavated trench of minimum depth of 1.2 metres and necessary risk response strategies have been considered by avoiding high-risk activities, adding resources or time, adopting a familiar approach instead of an innovative one. The activities undertaken in the project have very low potential for hazards and disasters during various operations. Effective action at the appropriate time can minimize or avoid the potential loss caused due to accidents. The mitigation scopes are incorporated in Environment Management Plan (EMP) appropriately considering the likely probability of the risk and its consequences.

10.1.2 Occupational Health and Safety Management System:

10.1.2.1 During implementation phase

HSE management system will be in place for ensuring whether proper attention is paid to the health and safety of individuals working in the Project as well as protection of environment from the environmental impacts associated with underground cable laying works. Training will be imparted on OHS issues prior to commencement of works. Necessary provision has also been made for periodic health check-up of the work



force and proper monitoring mechanisms will be in place during implementation and operation phase.

10.1.2.2 Planning the work :

Excavation work should be properly managed to control risks through planning the work based on cable plans available and adopting practices. Most underground utility services such as sewage, Water pipelines and Communication lines belongs to Government utilities such as Municipality, TWAD Board etc. and

underground communication service cables and gas pipelines belongs to private network operators. If a pipeline/ cable recorded in the route of proposed Underground cable, appropriate assistance or advice should be sought from the concerned utility. If digging has to start before such assistance or advice has been obtained, extreme care should be taken. Careful planning and risk assessments are essential before the work starts. Risk assessments should consider how the works are to be carried out, ensuring local circumstances are taken into account.

10.1.2.3 Safe digging practices

Excavation work should be carried out carefully and follow recognized safe digging practices. For locating below ground service lines routes, excavation shall be taken with trial pits at 200 metres intervals that will be dug using suitable hand tools only. Final exposure of the service by horizontal digging is recommended, as the force applied to hand tools can be controlled more effectively.

During laying of Underground Cables all trenches when left open for the period of time shall have safety barricades. Necessary protective equipment is to be provided to all work forces who are engaged in laying of underground cables. No materials/ cables are to be placed or stacked near



the edge of any excavation. No load is to be placed or moved near the edge of excavation, where it is likely to cause collapse on the work side. Safe distance shall be maintained from the edge of trench. No load/personnel movement across trench is encouraged. Manual handling awareness will be spread for load and electrical cables.

10.1.2.4 Safety towards Working in the Vicinity of Traffic:

When working on road or in the vicinity of traffic, traffic management must be carried out. Prior to commencing underground cable laying works, approval shall be obtained from the agency responsible for the care, control and management of the roads and traffic. Action should also be taken to ensure that all other required authorizations are obtained prior to the commencement of works to avoid increasing the risk of undesired traffic incidents. In addition, other agencies such as emergency services, police, public transport etc. in the area need to be informed well in advance of starting the underground cable laying works. Where the proposed traffic management involves modification to existing signal phasing, number of traffic lanes and / or timing on roads, the proposed changes are to be approved through traffic police.

10.1.2.5 Public Safety:

Cable route markers shall be installed to indicate the route of all underground power cables. Compaction to specified standard site, clearing of debris and refuse, Restoration of site after laying underground cables are essential. Proper marking with danger board sign over electrical cable route and emergency contact numbers are to be displayed.

10.1.2.6 Occupational Health & Safety During Maintenance phase:

A hazard assessment must be carried out by the work crew prior to commencement of maintenance work to ensure that all hazards have been identified and assessed. The appropriate controls have been put in place to



mitigate the hazards. All members of the work crew are aware of the hazards. The safety of the public and other workers has been ensured. TANGEDCO will notify the concern utility if they have any proposed work in the vicinity of underground services of other utility. Necessary personnel safety equipment shall be provided to workers. No workers shall physically handle a distribution cable of any type, if its condition is suspect or doubtful unless the cable is proved to be de-energized.

No personnel shall physically handle a high-voltage cable, while it is live unless it is completely surrounded by an earthed sheath or screen, or both, and precautions are taken, where necessary, to avoid danger from induced voltages and transferred earth potentials. Also, it is essential to prevent public access to the underground cable site or substation property with effective fencing and clear sign board indicating the dangers of the different facilities. The public will be kept clear of all equipment maintenance area. Only EB Persons should access or operate electrical equipments that must be kept locked.

A high-voltage cable shall be isolated, earthed and proved to be de-energised on site prior to commencing maintenance work on the cable. Placing any pressure or load on exposed cables and/or cable joints is not permitted. This is inclusive of stepping on to or using the cable or cable joint for support whilst working on or near the asset. If this is physically impractical, it must be consulted on an alternate work method. Mitigation measures are required to minimise impacts and ensure safety of work force as well as public during dismantling of over head infrastructure that have been included in the contractor scope along with cost provisions wherever required.



Safe operating procedures will be laid down and the personnel will be informed of the safety protocol required. Employees will be given periodical training on various safety precautions to be followed during the operation of the plant. This training will make the workers safety conscious and make them confident to handle any type of emergency situation.

10.2 Hazard Risk and Vulnerability of the Project area:

The underground cable laying sub project is spread across Cuddalore Town, which is under a low risk seismic zone (Zone II). The sub-project influence area is located on the beach ridge systems, effects of heavy rainfall and storm surge is imminent. The coastal landforms of the sub-project are subjected to three seasonal meteorological cycles in a year such as North East monsoon (October–December), South West monsoon (June–September), and non-monsoon (January–May). In addition to the above yearly cycles, the coastline landscape is remoulded by the occasional cyclones usually in the northeast monsoon period.

10.2.1 Disaster Management:

This public utility services project, does not involve any super structures which warrant earthquake resistant designs. Historical data indicates September – December months are the most probable months for occurrence of hydro meteorological depressions, cyclones and severe cyclonic storms in Cuddalore. Therefore, cable laying operations will be stalled for brief periods, in the event of any occurrence of cyclones/ inclement weather conditions during the implementation phase. **This UG cable work is proposed under Disaster Risk Reduction project with the aim to have a resilient underground electrical network, to counter damages, during and after cyclones, thunderstorm and other such natural calamities along coastline of Cuddalore Town.** The network is safer to public lives and property, particularly of people



belonging to lower economic strata of society during natural calamities. Areas covered under this Project are expected to practically remain unaffected in future from power disruptions and associated implications during or after cyclone/ high winds or natural calamities/ inclement weather conditions, hence the project will not cause any impact on weather and climate. Also, the project does not involve large scale construction activities like area development or industrial or other infrastructure development projects, which can induce some impacts on the local climate.

The impacts and the required mitigation measures during construction and operation phase are incorporated in the EMP. The EMP is integrated in the contract/ bidding documents as mandatory contractual obligations. Hence, the contractor is expected to be fully conversant with the EMP requirements of CDRRP underground cable works.

10.2.2 Emergency Preparedness Plan:

- 1) Most electrical accidents occur because individuals are working on or near equipment which is thought to be dead but which is, in fact, live (or) working on or near equipment which is known to be live, but where those involved are without adequate training or appropriate equipment, or they have not taken adequate precautions. Hence only those with adequate knowledge or experience should work in installation of electrical equipment that could cause danger or injury.
- 2) First aid facilities and free emergency care shall be provided to all workforce and no cost shall be recovered from them on this account.
- 3) Appropriate medical services should be taken up on war footing to limit post incident and to combat epidemics particularly water borne diseases
- 4) Water Quality monitoring mechanisms should be in place to prevent outbreak of epidemics and necessary provision made in EMP.



- 5) Arrangements will be made with local Police, Transport and Taluk administration in case of major accidents. Adequate fire safety equipment and fire extinguishers with dry chemical, foam spray, water spray should be kept in the storage yard.
- 6) During natural calamities period the work force will be accommodated in the Multi-Purpose Evacuation Shelter constructed under CDRRP.
- 7) Mechanisms are in place within department to deal with inter-department co-operation on emergency response.

10.2.3 Contact number of the District Officers in case of emergency

| Sl.No | District officials | Contact number | |
|-------|---|--------------------------|--------------------------|
| 1 | District Officer (i/c), Fire and Rescue Services | 04142 -294603, 293400 | 9445086406 |
| 2 | Superintendent of Police | 04142-284330, 295161 | |
| 3 | Revenue Divisional Office | 04142-231284 | 9445000426 |
| 4 | Superintending Engineer, TANGEDCO/ Cuddalore EDC | 04142-223793 | 9445856222 |
| 5 | Executive Engineer (O&M) TANGEDCO Cuddalore | 04142-221220 | 9445855938 |
| 6 | Executive Engineer/Operation, Capper Hills/Cuddalore | 04142-289117 | 9445855959 |
| 7 | Divisional Engineer /Highways | 04142-294555 | 9443227055 |
| 8 | Divisional Engineer (Rural Roads), Cuddalore | 04142-294706 | 9443349501 |
| 9 | Regional Transport Officer, Cuddalore | 04142-234035 | 9488030990 |
| 10 | Joint Director of Medical & Rural Health Services, Cuddalore | 04142-230052 | 9444982662 |
| 11 | Medical Mobile Unit Deputy Director (Health), Cuddalore | 04142-235134 | 9488990249 9442534652 |
| 12 | Superintending Engineer, TWAD Board Cuddalore-Villupuram Circle, Cuddalore. | 04142-235811 | 9443114828 |



10.2.4 List of the Multi-Purpose Evacuation Shelter

| Sl.No | Location | Details |
|-------|---------------------------|-----------------|
| 1 | Sothikuppam | School building |
| 2 | Kudikadu H/O Eachankadu | Community Hall |
| 3 | Killai [North] MGR Thittu | Community Hall |
| 4 | Killai [North] Kozhaiayru | Community Hall |
| 5 | Veerankoilthittu | Community Hall |



CHAPTER 11

EMP REVIEW, IMPLEMENTATION PLAN AND BUDGET ESTIMATION

11.1 EMP Review

The AE/AEE and PIU jointly shall review the EMP regularly. The review of the EMP shall consider i) adequacy of data collection and analysis; ii) reporting; iii) non-compliances; and iv) corrective actions implemented etc. if the outcome of the review indicate need of the update of EMP to make it more effective, the sections of the EMP may be updated in consultation with Project Manager, contractor and other stakeholders. Since EMP is the Specific/ Official document for environmental and social safeguard vis-à-vis Project sustainability, the updated EMP document shall be numbered as number of amendments with due dates and circulated to all the concerned parties for compliance till further notice.

11.2 EMP Implementation Plan and Schedule

TANGEDCO, Project Manager assumes overall responsibility for the implementation of this EMP. For the overall oversight of the EMP, the Project Manager shall constitute a PIU within its organizational structure. The PIU shall establish co-ordination with other stakeholders for the EMP implementation and monitoring. The organizational structure of PIU is given in *figure 4* and EMP implementation plan is presented in *Table 16*.




Figure-4 Organizational Structure of PIU



The overall EMP implementation plan shall comply the followings

Table 16: EMP Implementation Plan

| Implementation Item | Description | By When | Whom |
|---|--|--|--|
| Preparation of bid document and specification for Construction Contractor | To prepare environmental and social requirements for the Construction Contractor | One month before the final call for Contractors and Supervising engineers | DPR Consultant |
| Formation of PIU | Oversight unit for environmental and social safeguard for the Project | Within a month of the receipt of the detailed design report | TANGEDCO |
| Application for approval, consent and permits | Applications required for the approval , consent and permits etc. from different authorities | Six months before the start of construction | EE/Nodal officer CDRRP |
| Establish a Project Information Centre | The PIU shall establish a project Information Centre to disseminate the Project information to stakeholder and carryout stakeholder consultation | Three months before the project construction works | EE/Nodal officer CDRRP |
| Establishment of Grievance Redress Committee | Establish a grievance Redress committee as prescribed by this EMP | One month before the start of the construction works | EE CDRRP Head quarters |
| EMP training | Develop a training plan outlining training requirements, to PIUs, and areas of capacity building etc. | Within a week of contract award by PIU, AE/AEE and contractor initially and as need felt later during construction phase | EE CDRRP Head quarters through training centre of circle level |



| Implementation Item | Description | By When | Whom |
|---|--|--|--|
| Construction Management Plans | The Construction Contractor shall be responsible for in the preparation of the management plans as prescribed this EMP for approval by the AE/AEE/PIU: | Within a month of contract award | Contractor |
| Implementation of the environmental management measures | The construction contractor has the key responsibility for the implementation of the environmental management measures stipulated in this EMP | With the start of the construction Throughout construction phase | AE/AEE/EE/Nodal officer CDRRP |
| Supervision, Auditing and Monitoring of EMP | AE/AEE, PIU, PMU shall conduct supervision, auditing and monitoring and monitoring works of the Project | With the start of the construction works till the completion of the construction works | CE/SE/TANGEDCO Auditors of World Bank , AG's Audit , AE/AEE/EE/Nodal officer CDRRP |



11.3 EMP Costs

Estimated costs for the implementation of the EMP are presented in **Table 17**. Costs have been defined on an initial set up basis. TANGEDCO will revise these costs and develop annual operating costs for the EMP.

Table 17: EMP Cost Summary

| EMP Component | Estimated Cost (Indian Currency) |
|---|----------------------------------|
| Environmental mitigation and management cost* | 1542500.00 |
| Environmental Monitoring costs** | 105000.00 |
| Environmental clearance Charges by TANGEDCO | 300000.00 |
| Chance finds and other miscellaneous by TANGEDCO*** | 1000000.00 |
| Grand Total | 2947500.00 |

Note:


**Cost estimation is derived from Table 13*

*** Cost estimation is derived from Table 14*

**** Cost estimation is derived from Section 9.2.4*

































Capacity building cost included in Social Report

PROPOSED HT DISTRIBUTION LAYOUT PLAN MANJAKUPPAM FEEDER NO.-7,
SWITCHING STATION : NEAR ANNA STADIUM EXISTING FEEDER-MANJAKUPPAM



NOTE:-



1. THIS DRAWING IS TO SCALE 1:1
2. ALL DIMENSION ARE IN METER.
3. THIS LAYOUT HAS BEEN PREPARED ON THE BASIS OF GPS SURVEY AND PHYSICAL SURVEY/VERIFICATION OF EXISTING SYSTEM.
4. THE TOPOLOGICAL FEATURES LIKE ROAD, BUILDINGS,PARKS & OTHERS FEATURES HAVE BEEN SHOWN ON THE BASIS OF INFORMATION COLLECTED PHYSICALLY.
5. FOR ALL NATIONAL HIGHWAY & STATE HIGHWAY CROSSINGS, IT IS PROPOSED TO HAVE TRENCHLESS CROSSING ARRANGEMENT WHERE EVER NECESSARY
6. ALL ROAD, STREET, ACCESS TO ALL IMPORTANT BUILDING ESTABLISHMENT ETC.,CROSSING ARE PROPOSED BY HUME PIPE BEFORE LAYING THE CABLE.
7. THE UNDER GROUND CABLEING TO BE LAID IN BURIED TRENCH, AND THE CABLE TRENCH LAYOUT/SECTION DRAWING TO BE REFERRED
8. MANNAKUPPAM FEEDER-7 IS PART OF EXISTING MANNAKUPPAM FEEDER WHICH WAS FED FROM NATHAPATTU SUB STATION

| LEGEND: — | |
|---|---|
|  | PROPOSED HT CABLE 1 |
|  | UPGRADED HT CABLE 2 |
|  | 3CX185 Samm. CABLE |
|  | OPEN DRAIN |
|  | WATER PIPE LINE |
|  | BSNL LINE |
|  | SEWAGE |
|  | EXISTING DTR |
|  | R-APDRP DTR |
|  | PROPOSED DTR |
|  | 3 WAY RMU WITHOUT SCADA WITH BREAKER |
|  | 4 WAY RMU WITH BREAKER (RRL) |
|  | 5 WAY RMU WITH BREAKER (RRLl) |
|  | 4 WAY RMU WITH LOAD BREAK SWITCH (RRR) |
|  | 4 WAY RMU WITH LOAD BREAK SWITCH (RRRl) |
|  | 4 WAY RMU WITH BREAKER(RRR-L) |
|  | 3 WAY RMU WITH LOAD BREAK SWITCH (RRR) |
|  | 3 WAY RMU WITH BREAKER (RR-L) |
|  | TRENCHLESS CROSSING |
|  | PIPE CROSSING |
|  | ROAD CROSSING |
|  | TEMPLE/CHURCH/MOSQUE |
|  | WATER WORKS |
|  | HOUSE/SHOP/COMPANY |
|  | TREE |
|  | CANAL |
|  | SCHOOL/COLLEGE/TI |
|  | VENDOR |
|  | PETROL PUMP |
|  | STAIRS/ RAMP |
|  | HOSPITAL/CLINIC |
|  | RAILWAY CROSSING |

MAP SHEET NO.
MM7 P-01
 HT

| |
|---------------------------------------|
| NAME OF THE SUBSTATION - ANNA STADIUM |
| NAME OF EXISTING FEEDER - MANAKUPPAM |
| NAME OF PROPOSED FEEDER - FEEDER 07 |

| | |
|--|-----------|
| PROPOSED FEEDER LENGTH | 13.165 KM |
| 30x400 Sqmm. CABLE | |
| OVERHEAD HT LINE LENGTH | 0.000 KM |
| 30x185 Sqmm. CABLE | |
| TOTAL LOAD | 1.356 KM |
| | 8520 KVA |
| TOTAL DTR | 113 Nos. |
| EXISTING DTR | 30 Nos. |
| R-40DP DTR | 83 Nos. |
| PROPOSED DTR | 00 Nos. |
| UPGRADED DTR | 00 Nos. |
| 3 WAY RMU WITH BREAKER WITHOUT SCADA RRL | 57 Nos. |
| 3 WAY RMU WITH LOAD BREAK SWITCH RRR | 09 Nos. |
| 4 WAY RMU WITH LOAD BREAK SWITCH RRRR | 02 Nos. |
| 3 WAY RMU WITH BREAKER RRL | 27 Nos. |
| 4 WAY RMU WITH BREAKER RRL | 04 Nos. |
| 4 WAY RMU WITH TWO BREAKER RRL | 11 Nos. |
| 5 WAY RMU WITH THREE BREAKER RRL | 01 Nos. |
| TOTAL TRENCHLESS | 00 Nos. |
| TOTAL PIPE CROSSING | 71 Nos. |
| RAILWAY CROSSING | 00 Nos. |

| | | | |
|---------------------|---|----------|---|
| WORK ORDER DETAILS: | I.T.No.CE/PLG&RC/SC/RE&(D)/EE/PC-I/A1/ F.CDRRP/D 58/2015,dt.16.2.2015 | | |
| CLIENT: | TAMILNADU GENERATION AND DISTRIBUTION CORPORATION LTD.(TANEDCO),EASTERN WING, ANNA Salai, -600002 | | |
| CONSULTANT |  N-ARC CONSULTING NEW DELHI | | |
| NAME OF PROJECT: | COASTAL DISASTER RISK REDUCTION PROJECT (CDRRP)-CONVERSION OF EXISTING OVERHEAD LINES INTO UNDERGROUND CABLES FOR CUDALORE, NAGAPATTINAM AND VELAKKANMI COASTAL TOWNS IN CUDALORE AND NAGAPATTINAM DISTRICTS. | |  Scale 1:2 |
| TITLE: | PROPOSED NETWORK HT LINE MAJAKUPPAM FEEDER-2 SWITCHING STATION: NEAR ANNA STADIUM | | TotalsH 1 / 1 |
| DRAWN | CHECKED | APPROVED | DATE |
| DEVI SINGH | TARUN | NITIN | 03.10.15 |
| DRG. NO. | TANEDCO/NARC/CDL/MKM/HT/PK01/003 | | REV. 0 |




NT 6 P-02

HT




| | |
|--|---|
| | PROPOSED HT CABLE 1 |
| | UPGRADED HT CABLE 2 |
| | 3CX185 Sqmm. CABLE |
| | OPEN DRAIN |
| | WATER PIPE LINE |
| | BSNL LINE |
| | SEWAGE |
| | EXISTING DTR |
| | R-APDRP DTR |
| | PROPOSED DTR |
| | 4 WAY RMU WITH BREAKER (RRLL) |
| | 3 WAY RMU WITHOUT SCADA WITH BREAKER (RR-L) |
| | 5 WAY RMU WITH BREAKER (RRLLL) |
| | 4 WAY RMU WITH LOAD BREAK SWITCH (RRRR) |
| | 4 WAY RMU WITH BREAKER (RRR-L) |
| | 3 WAY RMU WITH LOAD BREAK SWITCH (RRR) |
| | 3 WAY RMU WITH BREAKER (RR-L) |
| | TRENCHLESS CROSSING |
| | PIPE CROSSING |
| | ROAD CROSSING |
| | TEMPLE/CHURCH/MOSQUE |
| | WATER WORKS |
| | HOUSE/SHOP/COMPANY |
| | TREE |
| | CANAL |
| | SCHOOL/COLLAG/ITI |
| | VENDOR |
| | PETROL PUMP |
| | STAIRS/ RAMP |
| | HOSPITAL/CLINIC |
| | RAILWAY CROSSING |
































| | |
|---------------------------------------|-------------|
| NAME OF THE SUBSTATION – ANNA STADIUM | |
| NAME OF EXISTING FEEDER– NEW TOWN | |
| PROPOSED FEEDER – FEEDER 6 N.T. | |
| 3CX400 Sqmm. CABLE | – 11.250 KM |
| 3CX185 Sqmm. CABLE | – 1.320 KM |
| TOTAL LOAD | 10512 kVA |
| TOTAL DTR | 88 Nos. |
| EXISTING DTR | 37 Nos. |
| R–APDRP DTR | 48 Nos. |
| UPGRADED DTR | 02 Nos. |
| PROPOSED DTR | 01 Nos. |
| 3 WAY RMU WITHOUT SCADA WITH BREAKER | 39 Nos. |
| 3 WAY RMU WITH LOAD BREAK SWITCH | 11 Nos. |
| 4 WAY RMU WITH LOAD BREAK SWITCH | 05 Nos. |
| 3 WAY RMU WITH BREAKER | 43 Nos. |
| 4 WAY RMU WITH BREAKER RRR–L | 01 Nos. |
| 4 WAY RMU WITH BREAKER RR–LL | 01 Nos. |
| 5 WAY RMU WITH BREAKER RRLLL | 01 Nos. |
| TOTAL TRENCHLESS | 17 Nos. |
| TOTAL PIPE CROSSING | 60 Nos. |
| BRIDGE CROSSING | 00 Nos. |

| | | | | |
|---------------------|---|----------|------------|---|
| WORK ORDER DETAILS: | Lr.No.CE/PLG&RC/SC/RE&I(D)/EE/PC-1/A1/ F.CDRRP/D 58/2015,dt.16.2.2015 | | | |
| CLIENT: | TAMILNADU GENERATION AND DISTRIBUTION CORPORATION LTD.(TANGEDCO),EASTERN WING, ANNA Salai,-600002 | | | |
| CONSULTANT | N_ARC CONSULTING NEW DELHI | | | |
| PROJECT TITLE: | COASTAL DISASTER RISK REDUCTION PROJECT (CDRRP)-CONVERSION OF EXISTING OVERHEAD LINES INTO UNDERGROUND CABLES FOR CUDDALORE ,NAGAPATTINAM AND VELANKANNI COASTAL TOWNS IN CUDDALORE AND NAGAPATTINAM DISTRICTS. | | |  |
| | | | | Scale 1:1 |
| TITLE: | PROPOSED HT DISTRIBUTION LAYOUT PLAN 6 NO. FEEDER FOR UNDER GROUND CABLING | | | Total Sh. 1/1 |
| DRAWN | CHECKED | APPROVED | DATE | Sheets 1 |
| GAURAV | TARUN | NITIN | 14.06.2016 | |
| DRG. NO. | TANGEDCO/NARC/CUD/F6/NT/PKG2/HT | | | REV. 1 |

| | | | |
|--|-------------|------|------------|
| | | | |
| | | | |
| | | | 14.01.2016 |
| | DESCRIPTION | APP. | DATE |

PROPOSED HT UG CABLE LAYOUT PLAN FOR FEEDER-8 NEW TOWN, SUBSTATION : ANNA STADIUM



NT 8 P-02
HT

| | |
|---|---|
|  | PROPOSED HT CABLE 1 |
|  | UPGRADED HT CABLE 2 |
|  | 30x185 Sqmm. CABLE |
|  | OPEN DRAIN |
|  | WATER PIPE LINE |
|  | B9XL LINE |
|  | SEWAGE |
|  | EXISTING DTR |
|  | R-ADPP DTR |
|  | PROPOSED DTR |
|  | 3 WAY R/W/ WITHOUT BREAKER (RR-1) |
|  | 4 WAY R/W/ WITH BREAKER (RELL) |
|  | 5 WAY R/W/ WITH BREAKER (RELL) |
|  | 4 WAY R/W/ WITH LOAD BREAK SWITCH (RRR) |
|  | 4 WAY R/W/ WITH BREAKER(RR-1) |
|  | 3 WAY R/W/ WITH LOAD BREAK SWITCH (RRR) |
|  | 3 WAY R/W/ WITH BREAKER (RR-1) |
|  | TRENCHLESS CROSSING |
|  | PIPE CROSSING |
|  | ROAD CROSSING |
|  | TEMPLE/CHURCH/MOSQUE |
|  | WATER WORKS |
|  | HOUSE/SHOP/COMPANY |
|  | CANAL |
|  | TREE |
|  | SCHOOL/COLLEGE/IN |
|  | VENDOR |
|  | PETROL PUMP |
|  | STAIRS/ RAMP |
|  | HOSPITAL/CLINIC |
|  | RAILWAY CROSSING |



DETAILS:-

| | |
|--|-------------|
| NAME OF THE SUBSTATION – ANNA STADIUM | |
| NAME OF EXISTING FEEDER – NEW TOWN | |
| PROPOSED FEEDER – FEEDER 8 N.T. | |
| 3CX440 Sqmm. CABLE | – 14,295 KM |
| 3X103 IBS Sqmm. CABLE | – 1,485 KM |
| TOTAL LOAD | 7643 KVA |
| TOTAL DTR | 99 Nos. |
| EXISTING DTR | 29 Nos. |
| R-APDRP DTR | 68 Nos. |
| UPGRADED DTR | 02 Nos. |
| PROPOSED DTR | 00 Nos. |
| 5 WAY RMU WITH WITH BREAKER RELL | 05 Nos. |
| 3 WAY RMU WITHOUT SCADA WITH BREAKER | 50 Nos. |
| 4 WAY RMU WITH BREAKER RELL | 01 Nos. |
| 3 WAY RMU WITH LOAD BREAK SWITCH | 10 Nos. |
| 4 WAY RMU WITH LOAD BREAK SWITCH (RRRR) | 01 Nos. |
| 3 WAY RMU WITH BREAKER | 29 Nos. |
| 4 WAY RMU WITH BREAKER | 01 Nos. |
| TOTAL TRENCHLESS | 15 Nos. |
| TOTAL PIPE CROSSING | 87 Nos. |
| RIVER CROSSING | 02 Nos. |

| | | | |
|--------------------------|--|--|------------|
| | | | |
| | | | |
| UPGRADED NETWORK HT LINE | | | 19.10.2016 |

| | | | |
|---|---|----------|------------|
| WORK ORDER DETAILS: | L-NO/GC/PI/GARC/SC/REA(0)/EE/PC-I/A1/ F-CORR/D 36/ 2015/dt.16.2.2015 | | |
| CLIENT: | TAMILNADU GENERATION AND DISTRIBUTION CORPORATION LTD.(TANDECOO),EASTERN WING, | | |
|  | | | |
| CONSULTANT |  N_ARC CONSULTING NEW DELHI | | |
| NAME OF PROJECT | COASTAL DISASTER RISK REDUCTION PROJECT (CORR)-CONVERSION OF EXISTING OVERHEAD LINES INTO CUDUPOLARE, NAGAPATTINAM AND VELANKANNI COASTAL TOWNS IN CUDUPOLARE AND NAGAPATTINAM DISTRICTS. | | |
| TITLE: | PROPOSED HT/GC CABLE LAYOUT PLAN FOR FEEDER & NEW TOWN SUBSTATION : ANNA STADIUM. | | |
| DRAWN | CHECKED | APPROVED | DATE |
| DEVI SINGH | NAIYEN | NITIN | 19.10.2015 |
| DRG. NO. | TANDECOO/NAARC/CUD/78/N/PK02/HT | | |
| REV. | 1 | | |

PROPOSED HT UG CABLE LAYOUT PLAN FOR
FEEDER-5 SELANAKUPPAM, SWITCHING SUBSTATION CUSTOM



SEL 5 P-02
HT


| | |
|--|--|
| | PROPOSED HT CABLE 1 |
| | UPGRADED HT CABLE 2 |
| | 3CX185 Sqmm. CABLE |
| | OPEN DRAIN |
| | WATER PIPE LINE |
| | BSNL LINE |
| | SEWAGE |
| | EXISTING DTR |
| | R-APDRP DTR |
| | PROPOSED DTR |
| | 3 WAY RMU WITHOUT SCADA WITH BREAKER |
| | 4 WAY RMU WITH BREAKER (RRL) |
| | 5 WAY RMU WITH BREAKER (RRL) |
| | 4 WAY RMU WITH LOAD BREAK SWITCH (RRR) |
| | 4 WAY RMU WITH BREAKER (RRR-1) |
| | 3 WAY RMU WITH LOAD BREAK SWITCH (RRR) |
| | 3CX185 Sqmm. CABLE BREAKER (RR-1) |
| | TRENCHLESS CROSSING |
| | PIPE CROSSING |
| | ROAD CROSSING |
| | TEMPLE/CHURCH/MOSQUE |
| | WATER WORKS |
| | HOUSE/SHOP/COMPANY |
| | TREE |
| | CANAL |
| | SCHOOL/COLLEGE/ITI |
| | VENDOR |
| | PETROL PUMP |
| | STAIRS/ RAMP |
| | HOSPITAL/CLINIC |
| | RAILWAY CROSSING |


DETAILS:-

| | | |
|--|---|-----------|
| NAME OF THE SUBSTATION | - | CUSTOM |
| NAME OF EXISTING FEEDER - SELANAKUPPAM | | |
| PROPOSED FEEDER - FEEDER 5 | | |
| 3CX400 Sqmm. CABLE | - | 12.234 KM |
| 3CX185 Sqmm. CABLE | - | 1.440 KM |
| TOTAL LOAD | | 9110 KVA |
| TOTAL DTR | | 96 Nos. |
| EXISTING DTR | | 23 Nos. |
| R-APDRP DTR | | 65 Nos. |
| UPGRADED DTR | | 07 Nos. |
| PROPOSED DTR | | 01 Nos. |
| 3 WAY RMU WITHOUT SCADA RRL | | 24 Nos. |
| 3 WAY RMU WITH LOAD BREAK SWITCH | | 09 Nos. |
| 3 WAY RMU WITH BREAKER | | 00 Nos. |
| 4 WAY RMU WITH BREAKER | | 46 Nos. |
| 5 WAY RMU WITH THREE BREAKER (RRL) | | 07 Nos. |
| 4 WAY RMU WITH TWO BREAKER (RRL) | | 01 Nos. |
| TOTAL TRENCHLESS | | 08 Nos. |
| TOTAL PIPE CROSSING | | 07 Nos. |
| RIVER/NALA CROSSING | | 94 Nos. |
| | | 03 Nos. |

| DESCRIPTION | APP. | DATE | REV. |
|----------------|----------------------------------|----------|----------|
| 00 FIRST ISSUE | | 03.03.17 | 01 |
| DRAWN | CHECKED | APPROVED | DATE |
| SUKHVINDER | NAVEEN | NITIN | 03.03.17 |
| DRG. NO. | TANGEDCO/NARC/CUD/SELF-5/PKG2/HT | | |

| | |
|---------------------|---|
| WORK ORDER DETAILS: | Lr.No.CE/PIG&RC/SC/RE&(D)/EE/PC-1/A1/F.CDRP/D 58/2015.dt.16.2.2015 |
| CLIENT: | TAMILNADU GENERATION AND DISTRIBUTION CORPORATION LTD.(TANGEDCO),EASTERN WING, ANNA Saloi,-600002 |
| CONSULTANT | N_ARC CONSULTING NEW DELHI |



| | | |
|------------------|--|---|
| NAME OF PROJECT: | COASTAL DISASTER RISK REDUCTION PROJECT (CDRRP) –CONVERSION OF EXISTING OVERHEAD LINES INTO UNDERGROUND CABLES FOR CUDALORE ,NAGAPATTINAM AND VELANKANNI COASTAL TOWNS IN CUDALORE AND NAGAPATTINAM DISTRICTS. |  |
| | | Scale 1 : 1 |































Scale 1:1

WORKING NORTH

PROPOSED HT UG CABLE LAYOUT PLAN FOR FEEDER-9 SELLANKUPPAM, SUBSTATION : CUSTOM


SEL 9 P-02
HT


| | |
|---|---|
|  | PROPOSED HT CABLE 1 |
|  | UPGRADED HT CABLE 2 |
|  | 3CX/85 Samm. CABLE |
|  | WATER DRAIN |
|  | WATER PIPE LINE |
|  | BSNL LINE |
|  | SEWAGE |
|  | EXISTING DTR |
|  | R-ADDP DTR |
|  | 3 WAY R/W WITHOUT SODA WITH BREAKER (RR-L) |
|  | 4 WAY R/W WITH LOAD BREAK SWITCH (RRR) |
|  | 4 WAY R/W WITH BREAKER(RR-L) |
|  | 3 WAY R/W WITH LOAD (RR-L) |
|  | 3 WAY R/W WITH BREAKER (RR-L) |
|  | TRENCHLESS CROSSING |
|  | PIPE CROSSING |
|  | ROAD CROSSING |
|  | TEMPLE/CHURCH/MOSQUE |
|  | WATER WORKS |
|  | HOUSE/SHOP/COMPANY |
|  | TREE |
|  | CANAL |
|  | SCHOOL/COLLEGE/ITI |
|  | VENDOR |
|  | PETROL PUMP |
|  | STAIRS/ RAMP |
|  | HOSPITAL/CLINIC |
|  | RAILWAY CROSSING |

DETAILS:-

| | |
|--------------------------------------|------------|
| NAME OF THE SUBSTATION – CUSTOM | |
| NAME OF EXISTING FEEDER – FEEDER 9 | |
| PROPOSED FEEDER – FEEDER 9 | |
| 3CX400 Sqmm. CABLE | – 9.256 KM |
| 3CX185 Sqmm. CABLE | – 0.630 KM |
| TOTAL LOAD | 7948 KVA |
| TOTAL DTR | 44 Nos. |
| EXISTING DTR | 16 Nos. |
| R-4PDRP DTR | 14 Nos. |
| UPGRADED DTR | 07 Nos. |
| PROPOSED DTR | 07 Nos. |
| 3 WAY RMU WITHOUT SCADA WITH BREAKER | 08 Nos. |
| 3 WAY RMU WITH LOAD BREAK SWITCH | 04 Nos. |
| 4 WAY RMU WITH LOAD BREAK SWITCH | 02 Nos. |
| 3 WAY RMU WITH BREAKER | 28 Nos. |
| 4 WAY RMU WITH BREAKER | 06 Nos. |
| TOTAL TRENCHLESS | 08 Nos. |
| TOTAL PIPE CROSSING | 46 Nos. |
| RAILWAY CROSSING | 02 Nos. |

| | | | |
|--|--------------------------|--|------------|
| | | | |
| | | | |
| | | | |
| | UPGRADED NETWORK HT LINE | | 27.10.2015 |

| | | | | |
|---------------------|---|----------|------------|--|
| WORK ORDER DETAILS: | L:\N\06\PIG&RC\SC\RE2(0)\EE\PC-1\A1\F.CORP\0_58\2015.dwg, 6.2.2015 | | | |
| CLIENT: | TAMILJAAU GENERATION AND DISTRIBUTION CORPORATION LTD.(TANGEDCO),EASTERN WING. | | | |
| CONSULTANT | N_ARC CONSULTING NEW DELHI | | | |
| NAME OF PROJECT | COASTAL DISASTER RISK REDUCTION PROJECT (CORAP)-CONVERSION OF EXISTING OVERHEAD LINES INTO SUBGROUNDED LINES IN CUDALORE AND MADAPATINAM TOWNS IN CUDALORE AND MADAPATINAM DISTRICTS. | | | SCALE 1:1  |
| TITLE: | PROPOSED HT UC CABLE LAYOUT PLAN FOR FEEDER @ SELAKKUNIPPRAM SUBSTATION : CUSTOM | | | TotalSh 1/1 |
| DRAWN | CHECKED | APPROVED | DATE | Sheets 1/1 |
| DEVI SINGH | NAWEN | NITIN | 27.10.2015 | 1 |
| DRG. NO. | TANGEDCO/NAARC/CUD/SELF-9/PKG52/HT | | | REV. 0 |



EXECUTIVE ENGINEER / CORP. SC (P&T) (D)
O/o SUPERINTENDING ENGINEER (D)
144, ANNASALAI, CHENNAI - 600 002

▲ Exg place of 2 Nos tree to be transplanted

✳ Proposed place of above 2 Nos tree to be transplanted

Proposed building area to be constructed by the contractor

Annexure : I B

Precautions to protect the Nag Devatha (Anthill) Shrine at Anna Stadium Switching Station:

1. Contractor would properly barricade the shrine area by providing a compound wall as shown in the sketch.
2. Also, building construction work will be started by the Contractor, only after construction of compound wall between Nag Devatha Anthill and proposed structure for separation.
3. The above will be monitored by TANGEDCO during execution of work.
4. TANGEDCO and contractor would take all safety precautions so as not to cause any harm to the shrine and not to obstruct the people praying / Performing Pooja at the shrine by providing a separate entrance to shrine as shown in the site plan.
5. Contractor would not store material near or around the shrine and would not encroach into the shrine area as wall would be constructed between switching station structure and Anthill.
6. All efforts would be earnestly taken for avoiding causing of harm to the shrine

Annexure 2 - Roads and Street wise location and numbers of the sensitive sites, vendors, ramps, nearby trees, road crossings, river crossings, railway crossings, nearby open drains, dense settlements, High activity area (markets, bus stops) etc.

| ENVIRONMENTAL & SOCIAL DETAILS | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------------------|------------------------------|---------------|-----------------|--------|-----------|--------|--------|----------|---------|-----------------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|--------------------------------|--|
| PACKAGE NO.2 | | | | | PACKAGE-2 | | | | | | | | | | | | | | | | | | | | |
| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | |
| | | | | | | | | | | | | L | R | | | | | | | | | | | | |
| | | | | | | | | | | Sellankuppam Feeder 5 | | | | | | | | | | | | | | | |
| 1 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-13 | 4 | | | | | | | | Yes | Yes | | | | | 1 | | | 11 | | Right/Left | | |
| 2 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-399 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 3 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-400 | | | | | | | | | Yes | No | | | | | | | | 1 | | | | |
| 4 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-401 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 5 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-403 | | | | | | | | | No | Yes | | | | | | | | 2 | | Right/Left | | |
| 6 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-405 | | | | | | | | | No | Yes | | | | | | | | 4 | | Right/Left | | |
| 7 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-410 | | | | | | | | | No | No | | | | | | | | 2 | | | | |
| 8 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | NH 45A (R-3) | | 1 | | 1 | | 2 | | | Yes | Yes | | | | | 2 | | 9 | | | Right/Left | Towards St-425 | |
| 9 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-4 | 2 | | | | | | | | Yes | No | | | | | | | | 9 | | Right/Left | Towards DTR-130,Towards St-434 | |
| 10 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-412 | | 1 | | | | | | | No | No | | | | | 2 | | | 2 | | Right/Left | | |
| 11 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-435 | | 1 | | | | | | | No | Yes | | | | | | | | 1 | | Right | Towards DTR-13, towards St-439 | |
| 12 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-434 | | | | | | | | | No | No | | | | | | | | 3 | | Right | Away from R-4 | |
| 13 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-436 | 2 | | | | | | | | Yes | No | | | | | | | | | | | | |
| 14 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-418 | | | | | | | | 7 | No | No | | | | | | | | 5 | | Right/Left | Towards DTR-17 | |
| 15 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-420 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | | |
| 16 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-422 | | | | | | | | | No | Yes | | | | | | | | 4 | | Right/Left | Towards R-19 | |
| 17 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-19 | 1 | | | 1 | 2 | | | 1 | Yes | Yes | | | | | | | | 10 | | Right/Left | Towards R-20, towards R-4 | |
| 18 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-486 | | | | | | | | 1 | No | No | | | | | | | | 2 | | Right/Left | Towards DTR-22 | |
| 19 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-20 | | | | | | | | | No | No | | | | | | | | 9 | | Right/Left | Towards DTR-43 | |
| 20 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-9 | | | | | | | | | No | No | | | | | | | | 4 | | Right/Left | Towards DTR-44 | |
| 21 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-468 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 22 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-470 | 1 | | | | | | | | No | No | | | | | | | | 1 | | Right | Towards St-470/A | |
| 23 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-472 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | | |
| 24 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-474 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 25 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-476 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards R-20 | |
| 26 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-478 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | | |
| 27 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-480 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 28 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-482 | | | | | | | | | No | No | | | | | | | | 3 | | Right/Left | | |
| 29 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-6 | | | | | | | | | No | No | | | | | | | | 10 | | Left | Towards St-460 | |
| 30 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-6/A | | | | | | | | | | | | | | | | | | 1 | | Right/Left | Towards DTR-35 | |
| 31 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-446 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards St-447, towards St-445 | |
| 32 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-449 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 33 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-451 | | | | | | | | | No | No | | | | | | | | 1 | | Right | Towards St-450 | |
| 34 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-453 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 35 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-455 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 36 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-457 | | | | | | | | | No | No | | | | | | | | 1 | | | | |
| 37 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-459 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Away from R-6 | |
| 38 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-462 | | | | | | | | | No | No | | | | | | | | 1 | | Right | Towards DTR-29 | |
| 39 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-465 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | | |
| 40 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-21 | | | | | | | | | No | No | | | | | | | | 2 | | Left | Towards R-21/A | |
| 41 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-21/A | | | | | | | | | No | No | | | | | | | | | | Right | Towards R-21/B | |
| 42 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | R-21/B | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards DTR-33 | |
| 43 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-447 | | | | | | | | | No | No | | | | | | | | 2 | | Left | Towards DTR-27A | |
| 44 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-448 | | | | | | | | | No | No | | | | | | | | | | Right | Towards DTR-26 | |
| 45 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-460 | | | | | | | | | No | No | | | | | | | | | | Right | Towards DTR-28 | |
| 46 | TANGEDCO/CDL/FEDDER-5/HT-000 | SEL5 P-02/HT | St-463 | | | | | | | | | No | No | | | | | | | | 2 | | Right | Towards DTR-34A | |
| 47 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 48 | LT | | | | | | | | | | | | | | | | | | | | | | | | |
| 49 | | SEL5 P-02/1 | St-705 | | | | | | | | | | | | | | | | | | | | | | |
| 50 | | | St-397 | | | | | | | | | | | | | | | | | | 1 | | | | |
| 51 | | | St-397/A | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 52 | | | St-707 | | | | | | | | | | | | | | | | | | 3 | | Right/Left | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|-------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|
| 53 | | | St-398 | | | | | | | | | Yes | No | | | | | | | | 1 | | Right/Left | |
| 54 | | | St-706 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 55 | | | St-710 | | | | | | | | | Yes | No | | | | | | | | 1 | | Right | Away from St-398 |
| 56 | | | St-708 | | | | | | | | | Yes | No | | | | | | | | | | | |
| 57 | | | St-709 | | | | | | | | | Yes | No | | | | | | | | 1 | | | |
| 58 | | SEL5 P-02/3 | St-712 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 59 | | | St-713 | | | | | | | | | | | | | | | | | | 1 | | | |
| 60 | | | St-715 | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 61 | | | St-401 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-13 |
| 62 | | | St-402 | | | | | | | | | No | Yes | | | | | | | | | | Right/Left | |
| 63 | | | St-406 | | | | | | | | | No | Yes | | | | | | | | 3 | | Right/Left | |
| 64 | | | St-712 | 1 | | | | | | | | | | | | | | | | | | | Right | Away from St-402 |
| 65 | | | St-719 | 1 | | | | | | | | | | | | | | | | | | | | |
| 66 | | SEL5 P-02/4 | St-721 | | | | | | | | | No | Yes | | | | | | | | 1 | | Right/Left | |
| 67 | | | St-722 | | | | | | | | | | | | | | | | | | 1 | | | |
| 68 | | | St-723 | | | | | | | | | Yes | No | | | | | | | | | | Right/Left | |
| 69 | | | St-404 | | | | | | | | | No | Yes | | | | | | | | 1 | | Right/Left | |
| 70 | | | St-725 | | | | | | | | | Yes | No | | | | | | | | | | Right/Left | |
| 71 | | | St-726 | | | | | | | | | Yes | No | | | | | | | | | | Right/Left | |
| 72 | | | St-724 | | | | | | | | | | | | | | | | | | | | | |
| 73 | | | St-729 | | | | | | | | | No | Yes | | | | | | | | 2 | | Right/Left | |
| 74 | | SEL5 P-02/5 | St-731 | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-729 |
| 75 | | | St-728 | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-729 |
| 76 | | SEL5 P-02/7 | St-413 | | | | | | | | | No | Yes | | | | | | | | | | Right/Left | |
| 77 | | | St-733 | | | | | | | | | | | | | | | | | | 1 | | | |
| 78 | | SEL5 P-02/9 | St-441 | | | | | | | | | | | | | | | | | | 1 | | Right | |
| 79 | | | St-442 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 80 | | | St-734 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 81 | | | St-735 | | | | | | | | | | | | | | | | | | 1 | | | |
| 82 | | | St-736 | | | | | | | | | | | | | | | | | | 1 | | | |
| 83 | | | St-737 | | | | | | | | | | | | | | | | | | 1 | | | |
| 84 | | | St-439 | | | | | | | | | | | | | | | | | | 2 | | Left | Towards DTR-13 |
| 85 | | SEL5 P-02/10 | St-437 | | 1 | | | | | | | No | Yes | | | | | | | | | | Right | Away from St-439 |
| 86 | | | St-438 | | | | | | | | | Yes | No | | | | | | | | | | Right/left | |
| 87 | | | St-434/A | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-435 |
| 88 | | | St-740 | | | | | | | | | | | | | | | | | | | | Left | Away from St-435 |
| 89 | | SEL5 P-02/11 | St-417 | | | | | | | | | | Yes | | | | | | | | | | Right | Towards St-415 |
| 90 | | | St-416 | | | | | | | | | Yes | No | | | | | | | | 1 | | Left | Away from R-3 |
| 91 | | SEL5 P-02/12 | St-419 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 92 | | | St-743 | | | | | | | | | | | | | | | | | | | | Right | Away from St-420 |
| 93 | | | St-744 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 94 | | | St-746 | | | | | | | | | | | | | | | | | | | | Right | Away from St-744 |
| 95 | | | St-747 | | | | | | | | | | | | | | | | | | | | Right | Away from St-746 |
| 96 | | | St-421 | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 97 | | | St-750 | | | | | | | | | | | | | | | | | | 2 | | Right/Left | |
| 98 | | SEL5 P-02/13 | St-751 | | | | | | | | | | | | | | | | | | | | Left | Towards St752 |
| 99 | | | St-748 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 100 | | | St-749 | 1 | | | | | | | | | | | | | | | | | | | Right | Away from St-748 |
| 101 | | | St-754 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 102 | | | St-755 | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 103 | | | St-756 | | | | | | | | | | | | | | | | | | | | Right | Away from St-755 |
| 104 | | | St-757 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-422 |
| 105 | | | St-758 | | | | | | | | | | | | | | | | | | 1 | | | |
| 106 | | | St-424 | | | | | | | | | | | | | | | | | | 2 | | Right/Left | |
| 107 | | | St-761 | | | | | | | | | | | | | | | | | | 1 | | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | | |
|------|---------------------------------|-----------------------|----------------------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|-----------------|------------------|---------------|
| 108 | | SEL5 P-02/14 | St-763 | | | | | | | | | | | | | | | | | | | | Right | Away from St-424 | | | |
| 109 | | | St-759 | | | | | | | | | | | | | | | | | | | | Left | Away from St-424 | | | |
| 110 | | | St-760 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-424 | | | |
| 111 | | SEL5 P-02/15 | St-433 | | | | | | | | | No | Yes | | | | | | | | | 1 | | Right/Left | | | |
| 112 | | | St-431 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | Right/Left | | |
| 113 | | | St-430 | | | | | | | | | | Yes | No | | | | | | | | | | | Right/Left | | |
| 114 | | | St-429 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | Right/Left | | |
| 115 | | | St-765 | | | | | | | | | | No | Yes | | | | | | | | | | | Right/Left | | |
| 116 | | | St-769 | | | | | | | | | | No | Yes | | | | | | | | | | | Left | Away from St-422 | |
| 117 | | | St-766 | | | | | | | | | | No | Yes | | | | | | | | | 1 | | Right/Left | | |
| 118 | | | St-426 | | | | | | | | | | Yes | No | | | | | | | | | | | Right/Left | | |
| 119 | | | St-764 | | | | | | | | | | Yes | No | | | | | | | | | | | Right | Away from R-19 | |
| 120 | | SEL5 P-02/17 | St-775 | | | | | | | | | | | | | | | | | | | 1 | | | | | |
| 121 | | | St-771 | | 1 | | | | | | | | | | | | | | | | | | | | | | |
| 122 | | SEL5 P-02/18 | St-444 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-788 | | |
| 123 | | | St-450 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-787 | | |
| 124 | | | St-452 | | | | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-786 | |
| 125 | | | St-454 | | | | | | | | | | | | | | | | | | | | 2 | | Right/Left | | |
| 126 | | | St-456 | | | | | | | | | | | | | | | | | | | | | | Left | Towards St-784 | |
| 127 | | | St-461 | | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 128 | | | St-795 | | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 129 | | | St-777 | | | | | | | | | | | | | | | | | | | | | | Right | Away from St-795 | |
| 130 | | | R-12 | | | | | | | | | | | | | | | | | | | | | | Right | Away from R-6 | |
| 131 | | | St-464 | | | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-6 |
| 132 | | | St-466 | | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 133 | | | St-778 | | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 134 | | | St-779 | | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 135 | | | St-789 | | | | | | | | | | | | | | | | | | | | | 3 | | Right/Left | |
| 136 | | | St-788 | | | | | | | | | | | | | | | | | | | | | | Right | Towards St-488 | |
| 137 | | SEL5 P-02/19 | St-792 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-791 | | |
| 138 | | | St-793 | | | | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-794 | |
| 139 | | SEL5 P-02/20 | St-469 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-468 | | |
| 140 | | | St-471 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 141 | | | St-475 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 142 | | | St-477 | | | | | | | | | | | | | | | | | | | | | | Right | Towards St-470 | |
| 143 | | | St-479 | | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 144 | | | St-481 | | | | | | | | | | | | | | | | | | | | | | Right | Towards St-470 | |
| 145 | | | St-483 | | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 146 | | | St-484 | | | | | | | | | | | | | | | | | | | | 1 | | Left | Toward R-20 | |
| | | Sellankuppam Feeder 9 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-16 | 3 | | | | | | | 4 | Yes | No | | | | | 1 | | | | 1 | | Left | Towards R-3 | | |
| 2 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-576 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 3 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-577 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 4 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-578 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 5 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-579 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 6 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-580 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 7 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-581 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 8 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-582 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 9 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-583 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 10 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-584 | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |
| 11 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-3 | 7 | | | | | 16 | | 2 | Yes | Yes | | | 2 Petrol Pump | | | | 20 | 2 | | | Right/Left | Towards R-3/A | | |
| 12 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-3/A | 4 | | | 1 | | | | 2 | No | No | | | | | | | | | | | Left | Towards DTR-44 | | |
| 13 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-586 | | | | | | | | | Yes | No | | | | | | | | | 3 | | Right/Left | Towards DTR-15 | | |
| 14 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-587 | | | | | | | | | Yes | No | | | | | | | | | 3 | | Right/Left | Towards DTR-18 | | |
| 15 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-588 | 1 | | | | | | | | Yes | Yes | | | 1 | | | | | | 2 | | Right/Left | Towards DTR--17 | | |
| 16 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | Cuddlore Port Rd. (St-591) | | | | | | | | | No | No | | | | | | | | | 1 | | | | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|---------------------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|---------------------------------|
| 17 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-592 | | | | | | | | | Yes | Yes | | | 1 | | 1 | | 2 | 5 | | Right/Left | Towards DTR-22 |
| 18 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-593 | | | | | | | | | Yes | Yes | | | | | | | | 2 | | Right/Left | |
| 19 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-594 | | | | | | | | | No | No | | | | | | | | | | Left | Towards DTR-24 |
| 20 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-595 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 21 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-598 | | | | | | | | | Yes | Yes | | | | | | | | | | Right/Left | Towards DTR-25 |
| 22 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-599 | 1 | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards DTR-29 |
| 23 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-599/A | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards DTR-28 |
| 24 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-601 | | | | | | | | | No | No | | | | 1 | | | | | | Right | Towards DTR-30, away from R-3 |
| 25 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-602 | | | | | | | | | No | No | | | | | | | | 1 | | Right | Towards R-3 |
| 26 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-604 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 27 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-605 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 28 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-607 | | | | | | | | 1 | No | No | | | | | | | | 1 | | Right | Towards DTR-33, away from R-3 |
| 29 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-608 | | | | | | | | | No | No | | | | | | | | 3 | | Left | Towards St-613, towards St-1080 |
| 30 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-608/A | 1 | | | | | | | | No | No | | | | | | | | 4 | | Right/Left | Towards DTR-38 |
| 31 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-620 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | |
| 32 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-613 | 1 | | | | | | | 3 | No | No | | | | | | | | | | Right/Left | Towards DTR-40 |
| 33 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-615 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 34 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-616 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards DTR-42 |
| 35 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-17 | 1 | | | | | | | 5 | No | No | | | | | | 1 | | 8 | | Right/Left | Towards R-17/A |
| 36 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-17/A | 2 | | | | | | | | No | No | | | | | | | | 3 | | Right/Left | Towards DTR-11 |
| 37 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | R-18 | 1 | | | | | | | | No | No | | | | | | | | 3 | | Right/Left | Towards DTR-09 |
| 38 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-633 | 1 | | | | | | | 3 | No | No | | | | | | | | 2 | | Right/Left | Towards DTR-11 |
| 39 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-634 | | | | | | | | | No | No | | | | | | | | | | RightLeft | Towards DTR-06 |
| 40 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-623 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 41 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-625 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 42 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-627 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 43 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-629 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 44 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-631 | | | | | | | | | No | No | | | | | | | | 2 | | | |
| 45 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-632 | | | | | | | | | | | | | | | | | | 1 | | | |
| 46 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | NH 532 (R-23) | 1 | | | | | | | | | | | | | | | | | | | | |
| 47 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | SEL09 P-2/HT | St-637 | | | | | | | | | | | | | | | | | | 1 | | | |
| 48 | | | | | | | | | | | | | | | | | | | | | | | | |
| 49 | LT | | | | | | | | | | | | | | | | | | | | | | | |
| 50 | | SEL09 P-2/2 | St-985 | | | | | | | | 2 | | | | | | | | | | | | Right/Left | |
| 51 | | | St-986 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 52 | | | St-987 | | | | | | | | | | | | | | | | | | 2 | | Right | Towards St-987/A |
| 53 | | | St-988 | | | | | | | | 2 | | | | | | | | | | 1 | | Right/Left | |
| 54 | | | St-992 | | | | | | | | | | | | | | | | | | 1 | | Left | Towrads St-992/A |
| 55 | | | St-994 | | | | | | | | | | | | | | | | | | | | Right | Towards St-994/A |
| 56 | | | St-989 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 57 | | | St-990 | | | | | | | | | | | | | | | | | | | | Right | Towards St-991 |
| 58 | | | St-993 | 1 | | | | | | | | | | | | | | | | | | | | |
| 59 | | SEL09 P-2/3 | St-995 | | | | | | | | | | | | | | | | | | 1 | | | |
| 60 | | SEL09 P-2/4 | St-998 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-633 |
| 61 | | | St-1000 | | | | | | | | | | | | | | | | | | | | Left | Towards St-635 |
| 62 | | | St-635 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 63 | | | St-997 | 1 | | | | | | | | | | | | | | | | | | | | |
| 64 | | SEL09 P-2/5 | St-1002 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 65 | | | St-1003 | | | | | | | | | | | | | | | | | | | | Left | Away fom St-1005 |
| 66 | | | St-1005 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 67 | | | St-1004 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 68 | | | St-1004/A | | | | | | | | | | | | | | | | | | | | Left | Away from St-1004 |
| 69 | | | St-1006 | | | | | | | | 2 | | | | | | | | | | 1 | | Right/Left | |
| 70 | | | St-1009 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1008 |
| 71 | | SEL09 P-2/6 | St-1011 | 1 | | | | | | | | | | | | | | | | | 1 | | Left | Away from R-17/A |
| 72 | | | St-1013 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-17/A |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STRE ET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | |
|------|-------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|-----------------------------|-----------------------|--------------------------------------|----------------|-------------------|---------------------|
| 73 | | SEL09 P-2/7 | St-1016 | 1 | | | | | | | | | | | | | | | | | 1 | | Right/Left | | | |
| 74 | | | St-1017 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1016 | |
| 75 | | | St-1024 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 76 | | | St-1023 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 77 | | | St-1021/A | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1021 | |
| 78 | | | St-1022 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1022/A | |
| 79 | | | St-1015 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 80 | | | St-1014 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 81 | | SEL09 P-2/9 | St-1029 | | | | | | | | | No | Yes | | | | | | | | | 3 | | Right/Left | | |
| 82 | | | St-1030 | | | | | | | | | | No | Yes | | | | | | | | | 2 | | Right/Left | |
| 83 | | SEL09 P-2/10 | St-1106 | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | | |
| 84 | | | St-1107 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 85 | | | St-1108 | 1 | | | | | | | | | Yes | No | | | | | | | | | 1 | | | |
| 86 | | SEL09 P-2/11 | St-1031 | 1 | | | | | | | | No | Yes | | | | | | | | | 1 | | Right | Toward St-1032 | |
| 87 | | | St-1032 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 88 | | | St-1034 | | | | | | | | | | Yes | Yes | | | | | | | | | 2 | | Right/Left | |
| 89 | | | St-1033 | | | | | | | | | | Yes | Yes | | | 1 | | | | | | 2 | | Right/Left | |
| 90 | | | St-588/A | | | | | | | | | | Yes | Yes | | | 1 | | | | | | 1 | | Right/Left | |
| 91 | | | St-1035 | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 92 | | | St-1036 | | | | | | | | | | Yes | Yes | | | | | | | | | | | Left | Away from St-588/A |
| 93 | | | St-1037 | | | | | | | | | | Yes | Yes | | | | | | | | | | | Left | Away from St-588/A |
| 94 | | SEL09 P-2/13 | St-1047 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 95 | | | St-1039 | | | | | | | 12 | | | | | | | | | | | | | 3 | | Right/Left | |
| 96 | | | St-1040 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 97 | | | St-1042 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 98 | | | St-1043 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 99 | | | St-1038 | | | | | | | 32 | | | Yes | No | | | 1 | | | | | | 1 | | | |
| 100 | | | St-1046 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 101 | | | St-1105 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 102 | | | St-1044 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 103 | | | St-1045 | | | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 104 | | SEL09 P-2/14 | St-1041 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1039 | |
| 105 | | | St-1048 | | | | | | | | | | | | | | | | | | | | 1 | | Left | Away from R-3 |
| 106 | | | St-1050 | | | | | | | | | | No | Yes | | | | | | | | | | | Right/Left | |
| 107 | | | St-1051 | | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1053 |
| 108 | | | St-1052 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | | |
| 109 | | St-1053 | | | | | | | | | | | | | | | | | | | | 1 | | Left | Towads St-593 | |
| 110 | | SEL09 P-2/15 | St-1059 | | | | | | | | | Yes | No | | | | | | | | | | | Right/Left | | |
| 111 | | | St-1061 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 112 | | | St-1062 | | | | | | | | | | Yes | Yes | | | | | | | | | | | Left | Towards St-1063 |
| 113 | | | St-1057 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | Right/Left | |
| 114 | | | St-1058 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | Right/Left | |
| 115 | | | St-1056 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 116 | | SEL09 P-2/17 | St-600 | | | | | | | | 2 | No | Yes | | | | | | | | | 2 | | Right/Left | | |
| 117 | | | St-1065 | | | | | | | | | 4 | No | Yes | | | | | | | | | | | Right/Left | |
| 118 | | | St-1064 | 1 | | | | | | | | 2 | | | | | | | | | | | | | Right | Away from St-599 |
| 119 | | SEL09 P-2/18 | St-1066 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-599 | |
| 120 | | | St-1067 | | | | | | | | | | No | Yes | | | | | | | | | | | Right | Towards St-1068 |
| 121 | | SEL09 P-2/19 | St-1069 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 122 | | | St-1070 | | | | | | | | | 5 | | | | | | | | | | | 1 | | Right/Left | |
| 123 | | | St-1071 | | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1071/A |
| 124 | | | St-1071/A | | | | | | | | | | | | | | | | | | | | | | Right | Away from St-1071 |
| 125 | | SEL09 P-2/20 | St-603 | | | | | | | | | | | | | | | | | | | | | Left | Away from R-3 | |
| 126 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 127 | | SEL09 P-2/21 | St-1072 | | | | | | | | | | | | | | | | | | | | | Right | Away from R-3 | |
| 128 | | | St-1074 | | | | | | | | | | | | | | | | | | | 1 | | | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STRE ET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | |
|-------------------|---------------------------------|---------------|---------------------------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|-----------------------------|-----------------------|--------------------------------------|-------------------|---------------------|-------------------|
| 129 | | SEL09 P-2/22 | St-1075 | | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-1073 | | |
| 130 | | | St-1073 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 131 | | SEL09 P-2/23 | St-1077 | | | | | | | | | | | | | | | | | | 1 | | | | | |
| 132 | | | St-1078 | | | | | | | | | | | | | | | | | | | 2 | | Right/Left | | |
| 133 | | | St-1079/A | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 134 | | SEL09 P-2/24 | St-609 | | | | | | | | 2 | | | | | | | | | | 2 | | Right/Left | | | |
| 135 | | | St-610 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 136 | | | St-612 | | | | | | | | | 1 | | | | | | | | | | 2 | | Right/Left | | |
| 137 | | SEL09 P-2/25 | St-1085 | | | | | | | | | Yes | Yes | | | | | | | | 1 | | | | | |
| 138 | | | St-1082 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 139 | | | St-1083 | | | | | | | | 3 | | | | | | | | | | | | | Right/Left | | |
| 140 | | | St-1084 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 141 | | SEL09 P-2/26 | St-1086 | | | | | | | | | | | | | | | | | | | | Right | Away from St-608 | | |
| 142 | | SEL09 P-2/27 | St-1089 | | | | | | | | | | | | | | | | | | 3 | | Right | Away from St-1088 | | |
| 143 | | | St-1090 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1089 | | |
| 144 | | | St-1091 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1091 | | |
| 145 | | | St-1088 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 146 | | | St-1088/A | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 147 | | | St-1092 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1088 | |
| 148 | | | St-1093 | | | | | 1 | | | | | | | | | | | | | | | 1 | | Right | Towards St-1094 |
| 149 | | | St-1094 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 150 | | | St-613/A | 1 | | | | | | | | | | | | | | | | | | | 4 | | Right/Left | |
| 151 | | SEL09 P-2/28 | R-23 | | | | | | | | | Yes | Yes | | | | | | | | | 2 | | Right/Left | | |
| 152 | | | St-1098 | 1 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1100/A | |
| 153 | | | St-1100 | | | | | | | | | | | | | | | | | | | | | | | |
| 154 | | | St-1100/A | | | | | | | | | | | | | | | | | | | | | Left | Towards R-3 | |
| 155 | | | St-1096 | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-3 | |
| 156 | | | St-1097 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 157 | | SEL09 P-2/29 | St-1101 | | | | | | | | 2 | | | | | | | | | | | | | Right | Toward St-1101/A | |
| 158 | | SEL09 P-2/30 | St-619 | | | | | | | | 2 | | | | | | | | | | | 1 | | Right/Left | | |
| 159 | | | St-618 | | | | | | | | | 2 | | | | | | | | | | | 1 | | Right/Left | |
| 160 | | | St-1103/A | | | | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1103/B |
| 161 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| New Town Feeder 2 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | Cuddalore Nellikuppam Rd. (R-1) | | | | | 2 | | | | No | Yes | 6 | | Bus Stop | | | | | 9 | | | Right/Left | Towards R-1/A | |
| 2 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-4 | | | | | | | | | No | No | | | | | | | | | 1 | | | | |
| 3 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/A | | | | | | | | | No | Yes | 5 | | | | | | | | | | Right | Towards R-1/B | |
| 4 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/B | | | | | | | | | No | No | | | | | | | | | | | Right | Towards R-1/C | |
| 5 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/C | 1 | | | | | | | | No | No | 3 | | Bus Stop | | | | | | | | Right | Towards R-1/D | |
| 6 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/D | | | | | | | | | No | No | | | | | | | | | | | Right | Towards R-1/E | |
| 7 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/E | 1 | | | 1 | | | | | No | No | | | 1 | | | | | | | | Right | Towards R-1/F | |
| 8 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/F | | | | | | | | | No | No | | | 1 | | | | | 1 | | | Right | Towards R-1/G | |
| 9 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-1/G | 1 | | | | | 7 | | | No | No | | | | | | | | 1 | | | Right | | |
| 10 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-1 | 1 | | | | | | | | No | No | | | | | | | | | 3 | | Right/Left | Towards DTR-02 | |
| 11 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-2 | | | | | | | | | No | No | | | | | | | | | 2 | | Left | Away from St-1 | |
| 12 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-3 | | | | | | | | | No | No | | | | | | | | | 1 | | | | |
| 13 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-4 | | | | | | | | | No | Yes | | | | | | | | | 1 | | Right | Away fom St-1 | |
| 14 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-5 | | | | | | | | 1 | No | No | | | | | | | | | 9 | | Right/Left | Towards DTR-06 | |
| 15 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-6 | | | | | | | | | No | No | | | | | | | | | 3 | | Right/Left | | |
| 16 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-7 | | | | | | | | | No | No | | | | | | | | | 1 | | Right/Left | | |
| 17 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-8 | | | | | | | | | No | No | | | | | | | | | 2 | | Left | Towards St-1135 | |
| 18 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-9 | | | | | | | | | No | No | | | | | | | | | 2 | | Right/Left | | |
| 19 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-10 | | | | | | | | | No | No | | | | | | | | | 3 | | Right/Left | Towards St-19 | |
| 20 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-11 | | | | | | | | | No | No | | | | | | | | | 1 | | | | |
| 21 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-13 | | | | | | | | | No | No | | | | | | | | | 1 | | | | |
| 22 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-15 | | | | | | | | | No | No | | | | | | | | | 1 | | | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|-------------------------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|--|
| 23 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-19 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards St-20 |
| 24 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-20 | | | | | | | | | No | No | | | | | | | | | | Left | Towards St-21, towards St-1157 |
| 25 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-21 | | | | | | | | 1 | No | No | | | | | | | | | | Left | Towards St-22, towards St-1156 |
| 26 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-23 | | | | | | | | | No | No | | 1 | | | | | | 1 | | Right/Left | Towards DTR-09 |
| 27 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-24 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | Towards DTR-11 |
| 28 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-26 | | | | | | | | | Yes | No | | | | | | | | 1 | | | |
| 29 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-27 | | | | | | | | | Yes | Yes | | | | | | | | 1 | | Right/Left | Towards St-36 |
| 30 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-36 | | | | | | | | 3 | No | Yes | | | | | | | | 2 | | Right/Left | Towards DTR-21 |
| 31 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-28 | | | | | | | | 3 | No | No | | | | | | | | 3 | | Right/Left | Towards St-33 |
| 32 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-33 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards St-34 |
| 33 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-34 | | | | | | | | | No | No | | | | | | | | | | Right/Left | Towards St-35 |
| 34 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-35 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | Towards DTR-25 |
| 35 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-29 | | | | | | | | 2 | No | No | | | | | | | | 5 | | Right/Left | Towards St-46 |
| 36 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-38 | | | | | | | | | No | No | | | | | | | | 1 | YES | Right/Left | Towards DTR-20, towards St-1220 |
| 37 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-46 | | | | | | | | | No | No | | | | | | | | | | Right | Towards St-45 |
| 38 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-45 | 1 | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards St-44 |
| 39 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-49 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | Towards DTR-23, towards St-1213 |
| 40 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-48 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards St-50 |
| 41 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-44 | | | | | | 6 | | | No | No | | 1 | 1 | | | | | 7 | YES | Right/Left | Right towards St-45, Left towards DTR-27 |
| 42 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-51 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 43 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-50 | | | | | | | | | No | No | | | | | | | | 2 | | | |
| 44 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-47 | | | | | | | | | No | No | | | | | | | | 1 | | | |
| 45 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-41 | | | | | | | | 1 | No | No | | | | | | | | 1 | | Right/Left | Towards St-40 |
| 46 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-40 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards St-39, towards St-41 |
| 47 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-52 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | Towards DTR-32, towards R-1 |
| 48 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-53 | | | | | | | | | No | Yes | | | | | | | | 1 | YES | Right | Towards St-56 |
| 49 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-56 | | | | | | | | | No | No | | | | | | | | 2 | YES | Right/Left | Towards St-58, towards St-1292 |
| 50 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-58 | | | | | | | | | No | No | | | | | | | | 1 | YES | Right | Towards St-59 |
| 51 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-59 | | | | | | | | | No | No | | | | | | | | | | Right/Left | Righttowards DTR-45, Left towards ST-60 |
| 52 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-60 | | | | | | | | | No | No | | | | | | | | 4 | | Left | Towards St-61 |
| 53 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-61 | | | | | | | | | No | No | | | | | | | | 4 | | Right/Left | Towards DTR-49 |
| 54 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-62 | | | | | | | | | No | No | | | | | | | | | | Right/Left | Towards St-63, towards St-1311 |
| 55 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-63 | | | | | | | | | No | No | | | | | | | | | | Right/Left | Towards R-21, towards St-62 |
| 56 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | R-21 | | | | | | | | | No | No | | | | | | | 1 | | | Right | Towards St-64 |
| 57 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-64 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards St-69 |
| 58 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-67 | | | | | | | | | No | No | | s | | | | | | | | Right | Towards St-68 |
| 59 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-71 | | | | | | | | | No | Yes | | | | | | | | 1 | YES | Right/Left | Towards DTR-62, towards St-71/A |
| 60 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-69 | | | | | | | | | No | No | | | | | | | | 1 | YES | Right/Left | Towards St-70 |
| 61 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-70 | | | | | | | | | No | No | | | | | | | | 1 | YES | Right/left | Towards St-71. |
| 62 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-84 | | | | | | | | | No | Yes | | | | | | | 3 | | | Right/Left | Towards St-88 |
| 63 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-88 | | | | | | | | | No | No | | | | | | | | 1 | | Left | Towards St-89 |
| 64 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-89 | | | | | | | | | Yes | Yes | | | | | | | | | | Right/Left | Towards St-90 |
| 65 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-90 | | | | | | | | | Yes | No | | | | | | | | | | Right/Left | Towards DTR-40 |
| 66 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-92 | | | | 1 | | | | | Yes | No | | | | | | | | 1 | | Right/Left | Towards St-84 |
| 67 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-93 | | | | | | | | | No | No | | | | | | | | 5 | | Right/Left | Towards St-94 |
| 68 | TANGEDCO/NARC/CUD/F2/NT/PKG2/HT | NT2 P-02/HT | St-94 | | | | | | | | | No | No | | | | | | | | 1 | | Right/Left | Towards DTR-56 |
| 69 | | | | | | | | | | | | | | | | | | | | | | | | |
| 70 | LT | | | | | | | | | | | | | | | | | | | | | | | |
| 71 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | R-27 | | | | | | | | | | | | | | | | | | | | Left | Away from R-1 |
| 72 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1109 | | | | | | | | | | | | | | | | | | 1 | | | |
| 73 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1110 | | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1111 |
| 74 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1111 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1110 |
| 75 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1112 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 76 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1113 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1 |
| 77 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1116 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1 |
| 78 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1117 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1 |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|-------------------------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|--|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|---------------------|
| 79 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | NT2 P-02/1 | St-1118 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 80 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1332 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-1 |
| 81 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1119 | | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-1120 |
| 82 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1122 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 83 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1123 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 84 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1124 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1123 |
| 85 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1121 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1 |
| 86 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1115 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 87 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT01 | | St-1115/A | | | | | | | | | | | | | | | | | | | | Left | Away from St-1115 |
| 88 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | NT2 P-02/2 | St-1128 | | | | | | | | | | | | | | | | | | 1 | Yes | Right/Left | |
| 89 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1129 | | | | | | | | | | | | | | | | | | 1 | Yes | Right/Left | |
| 90 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1126 | | | | | | | | | | | | | | | | | | 1 | Yes | Left | Towards R-1 |
| 91 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1127 | | | | | | | | | | | | | | | | | | 3 | Yes | Right/Left | |
| 92 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1130 | | | | | | | | | | | | | | | | | | 2 | Yes | Right/Left | |
| 93 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1131 | | | | | | | | | | | | | | | | | | | Yes | Right/Left | |
| 94 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1130/A | | | | | | | | | | | | | | | | | | | Yes | Left | Towards St-1133/A |
| 95 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT02 | | St-1133/A | | | | | | | | | | | | | | | | | | 1 | Yes | | |
| 96 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | NT2 P-02/3 | St-7/A | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 97 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-8/A | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 98 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-9/A | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 99 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-1134 | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-9 |
| 100 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-1137 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 101 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-1135 | | | | | | | | | | | | | | | | | | | | Left | Towards St-8 |
| 102 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT03 | | St-1135/A | | | | | | | | | | | | | | | | | | | | Right | Towards St-1136 |
| 103 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | NT2 P-02/4 | St-1147 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 104 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1146 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 105 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1148 | | | | | | | | | | | | | | | | | | 2 | | Right | Towards St-1149 |
| 106 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1149 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1148 |
| 107 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1145 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 108 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1144 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 109 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1150 | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 110 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1333 | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-5 |
| 111 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1139 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-5 |
| 112 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1140 | | | | | | | | | | | | | | | | | | | | Left | away from St-1140/A |
| 113 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1140/A | | | | | | | | | | | | | | | | | | 1 | | Right | away from St-1140/A |
| 114 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1141/A | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-1141 |
| 115 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1142 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 116 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1143 | | | | | | | | | | | | | | | | | | | | Left | Away from St-5 |
| 117 | TANGEDCO/NARC/CDL/PKG-2/F2/NT/LT04 | | St-1141 | | | | | | | | | | | | | | | | | | 1 | | | |
| 118 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | NT2 P-02/5 | St-12 | | | | | | | | | | | | | | | | | | | | Right | Away from St-10 |
| 119 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-14 | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-10 |
| 120 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-16 | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 121 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-17 | | | | | | | | | | | | | | | | | | | | Left | Away from St-10 |
| 122 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1168 | | | | | | | | | | | | | | | | | | | | Right | Towards St-1169 |
| 123 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1167 | | | | | | | | | | | | | | | | | | | | Right | Towards St-12/A |
| 124 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-12/A | | | | | | | | | | | | | | | | | | | | Right | Towards St-12 |
| 125 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1157 | | | | | | | | | | | | | | | | | | | | Left | Towards St-20 |
| 126 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-20/A | | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1163 |
| 127 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1159 | | | | | | | | | | | | | | | | | | 1 | | | |
| 128 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1158 | | | | | | | | | | | | | | | | | | | | Left | Towards St-1160 |
| 129 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1160 | | | | | | | | | | | | | | | | | | | | Left | Towards St-1162 |
| 130 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1161 | | | | | | | | | | | | | | | | | | 1 | | | |
| 131 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1164 | | | | | | | | | | | | | | | | | | | | Right | Towards St-1176 |
| 132 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1165 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1164 |
| 133 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1176 | | | | | | | | | | | | | | | | | | | | Right | Towards St-1177 |
| 134 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT07 | | St-1177 | | | | | | | | | | | | | | | | | | | | Right | Away from St-1176 |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|--------------------------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|---------------------|
| 135 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1170/A | | | | | | | | | | | | | | | | | 1 | Yes | Right/Left | |
| 136 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1173 | | | | | | | | | | | 1 | | | | | | 3 | Yes | Right/Left | |
| 137 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1212 | | | | | | | | | | | 1 | | | | | | | Yes | Right | Towards St-1176 |
| 138 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1171 | | | | | | | | | | | | | | | | | | | Right | Towards St-1170/A |
| 139 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1151 | | | | | | | | | | | 1 | | | | | | | Yes | | |
| 140 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1152 | | | | | | | | | | | 1 | | | | | | 2 | Yes | Right/Left | |
| 141 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1153 | | | | | | | | | | | 1 | | | | | | | Yes | Left | Away from St-25 |
| 142 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1154 | 1 | | | | | | | | | | 1 | | | | | | 1 | Yes | Right/Left | |
| 143 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-25 | | | | | | | | | | | 1 | | | | | | 1 | Yes | Right/Left | |
| 144 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1174 | | | | | | | | | | | 1 | | | | | | 2 | | Right/Left | |
| 145 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1175 | | | | | | | | | | | 1 | | | | | | | | Left | Towards St-1175/A |
| 146 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1175/A | | | | | | | | | | | 1 | | | | | | | | Left | Away from St-1175 |
| 147 | TANGEDCO/NARC/CDL/PKG-2/F-2/NT/LT/07 | | St-1155 | | | | | | | | | | | | | | | | | 1 | | | |
| 148 | | NT2 P-02/6 | St-1335/B | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 149 | | | St-1335/A | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1179 |
| 150 | | | St-1180 | | | | 1 | | | | | | | | | | | | | | | Right/Left | |
| 151 | | | St-1180/A | | | | | | | | | | | | | | | | | | | Right | Towards St-1182 |
| 152 | | | St-1187 | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 153 | | | St-1182 | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 154 | | | St-24/A | | | | | | | | | | | | | | | | | | | Left | Towards St-1186 |
| 155 | | | St-1183 | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 156 | | | St-1184 | | | | | | | | | | | | | | | | | | | Right | Away from St-1186 |
| 157 | | | St-1185 | | | | | | | | | | | | | | | | | | | Left | Away from St-1186 |
| 158 | | | St-1186 | | | | | | | | | | | | | | | | | | | Left | Towards St-1185 |
| 159 | | | St-1335 | | | | | | | | | | | | | | | | | 1 | | | |
| 160 | | NT2 P-02/7 | St-1188 | | | | | | | | | | | | | | | | | 1 | | Left | Away from R-1 |
| 161 | | | St-83 | | | | | | | | | | | | | | | | | 1 | | | |
| 162 | | NT2 P-02/8 | St-1204 | | | | | | | | | | | | | | | | | | | Right | Away from R-1 |
| 163 | | | St-1202 | | | | | | | | | | | | | | | | | | | Right | Towards St-1201 |
| 164 | | | St-1203 | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-1202 |
| 165 | | | St-1201 | | | | | | | | | | | | | | | | | 1 | | Right | Towards R-1 |
| 166 | | | St-1200 | | | | | | | | | | | | | | | | | 1 | | | |
| 167 | | | St-1199 | | | | | | | | | | | | | | | | | 1 | | | |
| 168 | | NT2 P-02/9 | St-45/A | | | | | | | | | | | | | | | | | | | Left | Towards St-45/A |
| 169 | | | St-1210 | | | | | | | | | | | | | | | | | | | Right | Towards St-1210/A |
| 170 | | | St-1211 | | | | | | | | | | | | | | | | | 1 | | | |
| 171 | | NT2 P-02/10 | St-1213 | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-49 |
| 172 | | | St-1214 | | | 1 | | | | | | | | | | | | | | 1 | | | |
| 173 | | NT2 P-02/12 | St-1217 | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-29 |
| 174 | | | St-1218 | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 175 | | | St-1219 | | | | | | | | | | | | | | | | | | | Right | Away from St-1218 |
| 176 | | | St-46/A | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-46 |
| 177 | | | St-1216 | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-1216/A |
| 178 | | | St-1216/A | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-1216 |
| 179 | | NT2 P-02/13 | St-1220 | | | | | | | | | | | | | | | | | 1 | | | |
| 180 | | | St-1221 | | | | | | | | | | | | | | | | | 1 | | | |
| 181 | | NT2 P-02/14 | St-1224 | | | | | | | | | | | | | | | | | 1 | | | |
| 182 | | | St-1223 | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-28 |
| 183 | | | St-1227 | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1228 |
| 184 | | | St-1228 | | | | | | | | | | | | | | | | | | | Left | Away from St-1227 |
| 185 | | | St-1229 | | | | | | | | | | | | | | | | | | | Right/left | |
| 186 | | | St-1230 | | | | | | | | | | | | | | | | | 1 | | Right/left | |
| 187 | | | St-1231 | | | | | | | | | | | | | | | | | 1 | | Right/left | |
| 188 | | | St-1232 | | | | | | | | | | | | | | | | | 1 | | Left | Towards St-1234 |
| 189 | | | St-1233 | | | | | | | | | | | | | | | | | 1 | | Right/left | |
| 190 | | | St-1240 | | | | | | | | | | | | | | | | | | | Right | Towards St-1242 |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | |
|------|-------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|---------------------|---------------------|-----------------|
| 191 | | | St-1236/A | | | | | | | | | | | | | | | | | | 1 | | Right/left | | | |
| 192 | | | St-1236 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1236/A | |
| 193 | | | St-1235 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-1236 | |
| 194 | | | St-1234 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 195 | | | St-1234/A | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1237/A | |
| 196 | | | St-1237/A | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1237 | |
| 197 | | | St-1242 | | | | | | | | | | | | | | | | | | | | 1 | Left | Towards St-38 | |
| 198 | | NT2 P-02/15 | St-1248 | | | | | | | | | | | | | | | | | | | | Right | Away from St-27 | | |
| 199 | | | St-1246 | | | | | | | | | | | | | | | | | | | | Right | Towards St-1246/A | | |
| 200 | | | St-1245 | | | | | | | | | | | | | | | | | | | | Left | Away from St-27 | | |
| 201 | | NT2 P-02/16 | St-1257 | | | | | | | | | | | | | | | | | | | | Right | Away from St-35 | | |
| 202 | | | St-1256 | | | | | | | | | | | | | | | | | | | 2 | Left | Away from St-35 | | |
| 203 | | | St-1250 | | | | | | | | | | | | | | | | | | | 1 | Right/Left | | | |
| 204 | | | St-1251 | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-1250 | | |
| 205 | | | St-1252 | | | | | | | | | | | | | | | | | | | 1 | Right | Away from St-1250 | | |
| 206 | | | St-1253 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 207 | | | St-1258 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1260 | |
| 208 | | | St-1260 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1261 | |
| 209 | | | St-1261 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-1260 | |
| 210 | | NT2 P-02/17 | St-1269 | | | | | | | | | | | | | | | | | | | 1 | Right | Away from St-44 | | |
| 211 | | | St-1268 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-44 | |
| 212 | | | St-57 | | | | | | | | | | | | | | | | | | | | 3 | Right | Away from St-44 | |
| 213 | | | St-42 | | | | | | | | | | | | | | | | | | | | 5 | Right/Left | | |
| 214 | | | St-1267 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-1267/A | |
| 215 | | | St-1267/A | | | | | | | | | | | | | | | | | | | | 1 | Right | Towards St-44 | |
| 216 | | | St-1336 | | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-44 | |
| 217 | | | St-1264 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1263 | |
| 218 | | | St-1264/A | | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-42 | |
| 219 | | | St-43 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1263 | |
| 220 | | | St-43/A | | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-43 | |
| 221 | | | St-1265 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-1265/A | |
| 222 | | | St-1265/A | | | | | | | | | | | | | | | | | | | | 1 | Right/Left | | |
| 223 | | | St-1266 | | | | | | | | | | | | | | | | | | | | 1 | Right | Away from St-1265/A | |
| 224 | | | St-1263/A | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1263/B | |
| 225 | | | St-39 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-43 | |
| 226 | | St-1262 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-40 | | |
| 227 | | NT2 P-02/18 | St-1270 | | | | | | | | | | | | | | | | | | | 1 | Right/Left | | | |
| 228 | | NT2 P-02/19 | St-1271 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1271/A | | |
| 229 | | | St-1272/A | | | | | | | | | | | | | | | | | | | | 1 | Right | Towards St-1272 | |
| 230 | | NT2 P-02/20 | St-1337 | | | | | | | | | | | | | | | | | | | | Left | Away from St-1337/A | | |
| 231 | | | St-1337/A | | | | | | | | | | | | | | | | | | | | 1 | Right | Away from St-1337 | |
| 232 | | NT2 P-02/22 | St-1280 | | | | | | | | | | | | | | | | | | | | Left | Towards St-1281 | | |
| 233 | | | St-1279 | | | | | | | | | | Yes | No | | | | | | | | | 1 | Right | Towards St-1281 | |
| 234 | | | St-1338 | | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-1279 | |
| 235 | | | St-1278 | | | | | | | | | | Yes | No | | | | | | | | | 1 | Right/Left | | |
| 236 | | | St-1277 | | | | | | | | | | No | Yes | | | | | | | | | 1 | Right | Away from St-92 | |
| 237 | | | St-1275 | | | | | | | | | | | | | | | | | | | | 1 | Right | Away from St-92 | |
| 238 | | | St-1276 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1276/A | |
| 239 | | | St-1276/A | | | | | | | | | | Yes | No | | | | | | | | | | Right | Away from St-1276 | |
| 240 | | | St-1274 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-92 | |
| 241 | | | St-1285 | | | | | | | | | | | | | | | | | | | | | 2 | | |
| 242 | | | St-1283 | | | | | | | | | | | | | | | | | | | | | 1 | Left | Away from St-92 |
| 243 | | | St-1284 | | | | | | | | | | No | Yes | | | | | | | | | | Right | Away from St-92 | |
| 244 | | | St-1282 | | | | | | | | | | Yes | Yes | | | | | | | | | | 1 | Right | Away from St-92 |
| 245 | | NT2 P-02/24 | St-54 | | | | | | | | | | | | | | | | | | | 1 | Yes | Right/Left | | |
| 246 | | | St-53 | | | | | | | | | Yes | No | | | | | | | | | | 5 | Right/Left | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | |
|-------------------|---------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|-----------------|---------------------|--|
| 247 | | NT2 P-02/25 | St-1287 | | | | | | | | | | | | | | | | | | 3 | | Left | Away from St-53 | | |
| 248 | | | St-1288 | | | | | | | | | | | | | | | | | | | 2 | | Right | Away from St-1287 | |
| 249 | | | St-1286 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-60 | |
| 250 | | NT2 P-02/26 | St-1290 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 251 | | | St-59/A | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 252 | | | St-1291 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 253 | | | St-1290/A | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1290/B | |
| 254 | | | St-1290/B | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1290/A | |
| 255 | | NT2 P-02/27 | St-1292 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-56 | |
| 256 | | NT2 P-02/28 | St-1339 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1294 | |
| 257 | | | St-1293 | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-1339 | |
| 258 | | NT2 P-02/29 | St-1295 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-61 | |
| 259 | | | St-1298 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-61 | |
| 260 | | | St-1297 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-61 | |
| 261 | | | St-1296 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 262 | | NT2 P-02/30 | St-1301 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1302 | |
| 263 | | | St-1302 | | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-1301 | |
| 264 | | | St-1300 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 265 | | NT2 P-02/31 | St-1303 | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-1 | |
| 266 | | NT2 P-02/32 | St-1305 | | | | | | | | | | | | | | | | | | | 1 | | Left | Away from St-1305/A | |
| 267 | | | St-1305/A | | | | | | | | | | | | | | | | | | | | | Right | Away from St-1305 | |
| 268 | | | St-1304 | | | | | | | | | | | | | | | | | | | 2 | | Left | Towards R-1 | |
| 269 | | NT2 P-02/33 | St-1310 | | | | | | | | | | | | | | | | | | 1 | | | | | |
| 270 | | | R-28 | | | | | | | | | | | | | | | | | | 1 | | | Right/Left | | |
| 271 | | | St-1306/A | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 272 | | | St-1306 | | | | | | | | | | | | | | | | | | | 1 | | Left | Away from R-1 | |
| 273 | | | St-1307 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 274 | | | St-1308 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 275 | | | St-1309 | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-1308 | |
| 276 | | NT2 P-02/35 | R-29 | | | | | | | | | | | | | | | | | | | | | Right | Towards St-1314 | |
| 277 | | | St-1314 | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from R-29 | |
| 278 | | | St-1313 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 279 | | NT2 P-02/36 | St-68 | | | | | | | | | | | | | | | | | | | 3 | | Right/Left | Towards St-1319 | |
| 280 | | | St-1319 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-1318 | |
| 281 | | NT2 P-02/38 | St-71/A | | | | | | | | | No | Yes | | | | | | | | | | | Right | Away from St-71 | |
| 282 | | NT2 P-02/39 | St-65 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 283 | | | St-66 | | | | | | | | | | | | | | | | | | | 2 | | Right/Left | | |
| 284 | | | St-1324 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 285 | | | St-1325 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-64 | |
| 286 | | | St-1326 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 287 | | | St-1327 | | | | | | | | | | No | Yes | | | | | | | | | 1 | | Right/Left | |
| 288 | | | St-1328 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 289 | | NT2 P-02/40 | St-1330 | | | | | | | | | No | Yes | | | | | | | | | 2 | | Left | Towards St-1329 | |
| 290 | | | St-1331 | | | | | | | | | | Yes | Yes | | | | | | | | | | | Right/Left | |
| New Town Feeder 6 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | R-4 | | | | | | | | | No | No | | | | | | | | 2 | | Right/Left | Towards R-2 | | |
| 2 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | R-2 | 1 | 1 | | | | | | | No | No | | | 1 | | | | 5 | | Yes | Right/Left | Towards St-136 | | |
| 3 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | R-2/A | | 1 | | | | 1 | | | No | No | | | 1 | | | | 3 | | | Right/Left | Towards St-195 | | |
| 4 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-151 | | | | 2 | 1 | | | | No | No | | | | | | | | 3 | | Right/Left | Towards DTR-07 | | |
| 5 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-95 | | | | | | | | | No | Yes | | | | | | | | 2 | | Right/Left | Towards St-129 | | |
| 6 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-129 | | | | | | | | | Yes | Yes | | | | | | | | 5 | | Right/Left | Towards R-3/A | | |
| 7 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | R-6 | 1 | | | | 1 | 1 | | | No | No | | | | | | | 4 | | | Right | Towards R-3/A | | |
| 8 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-95/A | | | | | | | | | No | Yes | | | | | | | | 1 | | Right | Towards St-96 | | |
| 9 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-125/A | | | | | | | | | No | No | | | | | | | | | | Right | Towards DTR-74 | | |
| 10 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-96 | | | | | | | | | Yes | No | | | | | | | | 1 | | Left | Towards St-97 | | |
| 11 | TNEB/NARC/CDL/NP/HT | NT2 F-6/HT | St-97 | | | | | | | | | No | No | | | | | | | | | | Left | Towards DTR-76 | | |

[illegible]

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE | | |
|------|---------------------------------|---------------|--------------------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|-------------------|------------------|
| 68 | | NT2 F-6/11 | St-818/A | | | | | | | | | Yes | No | | | | | | | | | | Left | Away from St-818 | | |
| 69 | | | St-827 | | | | | | | | | | Yes | No | | | | | | | | | | Left | Away from St-140 | |
| 70 | | | St-826 | | | | | | | | | | No | Yes | | | | | | | | 1 | | Right/Left | | |
| 71 | | | St-828 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 72 | | NT2 F-6/12 | St-142 | | | | | | | | | No | Yes | | | | | | | | | 2 | | Right/Left | | |
| 73 | | | St-832 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 74 | | | St-830 | | | | | | | | | | | | | | | | | | | | | Left | Aw ay from St-142 | |
| 75 | | NT2 F-6/13 | St-834 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 76 | | | St-835 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 77 | | | St-836 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 78 | | NT2 F-6/14 | St-140/A | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | | |
| 79 | | | St-839 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 80 | | | St-840 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | | |
| 81 | | | St-837 | | | | | | | | | | No | Yes | | | | | | | | | | Left | Away from St-838 | |
| 82 | | | St-838 | | | | | | | | | | No | Yes | | | | | | | | | | Right | Away from St-837 | |
| 83 | | | St-845 | | | | | | | | | | No | Yes | | | | | | | | | 1 | | Right/Left | |
| 84 | | NT2 F-6/15 | St-846 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 85 | | | St-848 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-845 | |
| 86 | | | St-150 | | | | | 1 | | | | | Yes | No | | | | | | | | | | | | |
| 87 | | | St-853 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 88 | | NT2 F-6/16 | St-854 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 89 | | | St-850 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 90 | | | St-851 | | | | | | | | | | | | | | | | | | | | | Right | Away from St-850 | |
| 91 | | | St-149 | | | | | 1 | | | | | | | | | | | | | | | | | Right/Left | |
| 92 | | NT2 F-6/17 | St-857 | | | | | | | | | | | | | | | | | | | | Left | Towards St-857/A | | |
| 93 | | | St-858 | | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-857 |
| 94 | | NT2 F-6/18 | St-137 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 95 | | NT2 F-6/19 | St-134 | | | | | | | | | | | | | | | | | | | 3 | | Right | Away from R-3 | |
| 96 | | | St-861 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 97 | | | St-863 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 98 | | | St-865 | | | | | 1 | | | | | | | | | | | | | | | | | | |
| 99 | | NT2 F-6/20 | St-866 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 100 | | | St-868 | | | | | | | | | | | | | | | | | | | | 1 | | Right | Away from St-136 |
| 101 | | | St-869 | | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 102 | | | St-867 | | | | | | | | | | Yes | No | | | | | | | | | 1 | | | |
| 103 | | NT2 F-6/21 | St-871 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 104 | | | St-873 | | | | | | | | | | | | | | | | | | | | | Right/Left | | |
| 105 | | | St-872 | 1 | | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 106 | | | St-889 | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 107 | | NT2 F-6/22 | St-132 | | | | | | | | | | | | | | | | | | | 1 | | | | |
| 108 | | | St-874 | | | | | | | | | | | | | | | | | | | | | Right | Away from R-3 | |
| 109 | | NT2 F-6/23 | St-875 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 110 | | | St-876 | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 111 | | NT2 F-6/24 | St-878 | | | | | | | | | | | | | | | | | | | | | Left | Towards St-879 | |
| 112 | | | St-879 | | | | | | | | | | | | | | | | | | | | | Left | Away from St-878 | |
| 113 | | | St-880 | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 114 | | NT2 F-6/25 | St-131 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 115 | | NT2 F-6/27 | St-884 | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | | |
| 116 | | | St-883 | | | | | | | | | | Yes | Yes | | | | | | | | | 1 | | Right/Left | |
| 117 | | | St-881 | | | | | | | | | | | | | | | | | | | | 1 | | | |
| 118 | | | St-882 | 1 | | | | | | | | | | | | | | | | | | | | | Right/Left | |
| 119 | | NT2 F-6/28 | St-885 | | | | | | | | | | | | | | | | | | | 1 | | Right/Left | | |
| 120 | | | St-888 | 1 | | | | | | | | | | | | | | | | | | | | Right | Away from St-95 | |
| | New Town Feeder 8 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | Anna Stadium Rd. (R-8) | | | | | | | | | | | | | | | | | | | | Left | Towardsa R-2 | | |
| 2 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | Judge Bungalow Rd. (R-7) | | | | 1 | | | | | | | | | | | | | | 1 | | Right | Towards DTR-91 | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|---------------------------------|---------------|------------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|
| 3 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | Beach Rd. R-2) | | 1 | | | | 1 | | | Yes | Yes | | | | | | | 2 | | | Left | Towards R-7 |
| 4 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | Beach Rd. R-2(B) | | | | | | | | | Yes | Yes | 3 | | | | | | 1 | | | Right | Towards St-191 |
| 5 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-187 | | | | | | | | | No | Yes | | | | | | | | 1 | YES | Left | Towards St-188 |
| 6 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-188 | | | | | | | | | | | | | | | | | | | YES | Right,Left | |
| 7 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-187/A | | | | | | | | | No | Yes | | | | | | | | | YES | Right | Towards St-189 |
| 8 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-189 | | | | | | | | | | | | | | | | | | | | Right | Towards DTR-99 |
| 9 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-186 | | | | | | | | | | | | | | | | | | 1 | | | |
| 10 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/C | 2 | | | | | | | | | | | | | | | | | | | Right | Towards R-2/D |
| 11 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/D | 1 | | | 1 | | | | | | | | | | | | | 1 | | | Left | Towards R-2/E |
| 12 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/E | | | | | | | | | | | | | | 1 | | | 2 | | | Right | Towards R-2/F |
| 13 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/F | | | | | | | | | | | | | | | | | 2 | | | Right,Left | |
| 14 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/G | | | | 2 | | | | | | | | | | | | | 2 | | | Left | Towards R-2/G |
| 15 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2/H | | | | | | | | | | | | | | | | | 1 | | | Left | Towards R-9 |
| 16 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-9 | | | | | | | | | | | | | | | | | | | | Right | Towards R-2/E |
| 17 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-257 | | | | | | | | | | | | | | | | | | 1 | | Left | Towards DTR-47 |
| 18 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-10 | | | | | | | | | No | Yes | | | | | | | | 2 | | Right/Left | Towards St-309 |
| 19 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-288 | | | | | | | | | Yes | Yes | | | | | | | | 1 | | Right/Left | Towards R-12 |
| 20 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-12 | | | | | | | | | Yes | No | | | | | | | | 2 | | Right/Left | Towards R-11 |
| 21 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-11 | 2 | | | | | | | | Yes | No | | | | | | | | 4 | | Right/Left | Towards R-12/A |
| 22 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-307 | | | | | | | | | | | | | | | | | | 1 | | | |
| 23 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-308 | | | | | | | | | | | | | | | | | | 2 | | Right/Left | |
| 24 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-12/A | | | | | | | | | Yes | No | | | | | | | | | | Right | Away from R-11 |
| 25 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-309 | | | | | | | | | No | Yes | | | | | | | | 2 | | Right | Towards St-309/A |
| 26 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-309/A | | | | | | | | | | | | | | | | | | | | Left | Towards DTR-23 |
| 27 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-301 | | | | | | | | | No | Yes | | | | | | | | | | Left | Towards St-302 |
| 28 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-298 | | | | | | | | | | | | | | | | | | 1 | YES | Right | Towards DTR-20 |
| 29 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-299 | | | | | | | | | | | | | | | | | | | YES | Left | Towards DTR-20 |
| 30 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-302 | | | | | | | | | Yes | No | | | | | | | | | | Right | Towards DTR-14 |
| 31 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-303 | | | | | | | | | Yes | No | | | | | | | | | | Right | Towards DTR-13 |
| 32 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-305 | | | | | | | | | | | | | | | | | | | | Left | Towards DTR-08 |
| 33 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-306 | | | | | | | | | | | | | | | | | | 1 | | | |
| 34 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-304 | | | | | | | | | | | | | | | | | | 1 | | | |
| 35 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6 | 2 | | | | | | | | | | | | | | | | | 2 | | Right,Left | |
| 36 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/A | | | | | | | | | | | | | | | | | | 1 | | Left | Towards R-6/B |
| 37 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/B | 1 | | | | | 1 | | | | | | | | | | | | 1 | | Right | Towards R-6/C |
| 38 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/C | 1 | | | | | | | 7 | Yes | No | | | | | | | | | | Left | Towards R-6/D |
| 39 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/D | | | | | | | | | | | | | | 1 | | | | | | Left | Towards R-6/E |
| 40 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/E | | | | 1 | | | | | | | | | | | | | | 1 | | Right | Towards R-6/F |
| 41 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-6/F | 1 | | | | | | | | | | | | | | | | | 1 | | Left | Towards DTR-68 |
| 42 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-182 | | | | | | | | | | | | | | | | | | 1 | | | |
| 43 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-195 | | | | | | | | | | | | | | | | | | 2 | | Left | Towards St-196 |
| 44 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-196 | | | | | | | | 5 | | | | | | | | | | | | Left | Towards St-197 |
| 45 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-197 | 1 | | | | | | | | | | | | | | | | | | | Left | Towards St-202 |
| 46 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-198 | | | | | | | | | | | | | | | | | | 1 | | | |
| 47 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-200 | | | | | | | | | | | | | | | | | | 1 | | | |
| 48 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-202 | | | | | | | | | | | | | | | | | | 1 | | | |
| 49 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-203 | | | | | | | | | | | | | | | | | | 1 | | | |
| 50 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-204 | | | | | | | | | | | | | | | | | | 1 | | | |
| 51 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-206 | | | | | | | | | | | | | | | | | | 1 | | | |
| 52 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-207 | | | | | | | | | | | | | | | | | | 1 | | | |
| 53 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-210 | | | | | | | | | | | | | | | | | | 1 | | | |
| 54 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-212 | | | | | | | | | | | | | | | | | | | | Right | Towards St-44 |
| 55 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-213 | | | | | | | | | | | | | | | | | | | | Right | Towards R-6/E |
| 56 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-215 | 1 | | | | | | | | | | | | | | | | | 1 | | | |
| 57 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-216 | | | | | | | | | | | | | | | | | | 1 | | | |
| 58 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-218 | | | | | | | | | | | | | | | | | | 1 | | | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|---------------------------------|---------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|---------------------|
| 59 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-219 | | | | | | | | | | | | | | | | | | 1 | | | |
| 60 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-220 | | | | | | 1 | | 2 | | | | | | | | | | | | Left | Towards St-64 |
| 61 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-222 | | | | | | | | | | | | | | | | | | 1 | | | |
| 62 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-225 | | | | | | | | | | | | | | | | | | 1 | | | |
| 63 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-229 | | | | | | | | | | | | | | | | | | 1 | | | |
| 64 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-230 | | | | | | | | | | | | | | | | | | 1 | YES | | |
| 65 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-231 | | | | | | | | | | | | 1 | | | | | | | YES | Right | Towards DTR-63 |
| 66 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-232 | | | | | | | | | | | | 1 | | | | | | | YES | Left | Towards DTR-73 |
| 67 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-232/A | | | | | | | | | | | | 1 | | | | | | | YES | Right | Towards DTR-72 |
| 68 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-233 | 1 | | | | | | | | | | | | | | | | | | | Right | Towards St-65 |
| 69 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-234 | | | | | | | | | | | | | | | | | | | | Right | Towards St-66 |
| 70 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-235 | | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-78 |
| 71 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-310 | | | | | | | | | | | | | | | | | | 1 | YES | Left | Towards DTR-84 |
| 72 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-237 | | | | | | | | | | | | | | | | | | 1 | | | |
| 73 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-239 | | | | | | | | | | | | | | | | | | 1 | | | |
| 74 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-241 | | | | | | | | | | | | | | | | | | 1 | | | |
| 75 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-243 | | | | | | | | | | | | | | | | | | 1 | | | |
| 76 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-245 | | | | | | | | | | | | | | | | | | 1 | | | |
| 77 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-247 | | | | | | | | | | | | | | | | | | 1 | | | |
| 78 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-248 | | | | | | | | | | | | | | | | | | 1 | | | |
| 79 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-250 | | | | | | | | | | | | | | | | | | | | Left | Towards DTR-87 |
| 80 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-251 | | | | | | | | | | | | | | | | | | | | Right | Towards DTR-85 |
| 81 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-235/A | | | | | | | | | | | | | | | | | | | | Left | Towards DTR-88 |
| 82 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-7 | | | | 1 | | | | | | | | | | | | | 3 | | | Right/Left | Towards DTR-91 |
| 83 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-7/A | | | | | | | | | No | Yes | | | | | | | | | YES | Right/Left | |
| 84 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-8 | | | | | | | | | No | Yes | | | | | | | | | | Left | Towards R-6 |
| 85 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-173 | | | | | | | | | | | | | | | | | | 1 | | | |
| 86 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-174 | | | | | | | | | | | | | | | | | | 1 | | | |
| 87 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | St-175 | | | | | | | | | | | | | | | | | | 1 | | | |
| 88 | TANGEDCO/NARC/CUD/F8/NT/PKG2/HT | NT2 F-8/HT | R-2 | | 1 | | | | | | | Yes | Yes | | | | | | | 2 | | | Right | Towards R-2/B |
| 89 | | | | | | | | | | | | | | | | | | | | | | | | |
| 90 | LT | | | | | | | | | | | | | | | | | | | | | | | |
| 91 | | NT2 F-8/1 | St-798 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 92 | | | St-289/A | | | | | | | | | | | | | | | | | | 1 | | | |
| 93 | | | St-289 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 94 | | | St-797 | | | | | | | | | | | | | | | | | | 1 | | | |
| 95 | | | St-287 | | | | | | | | | | | | | | | | | | 1 | | Right/Left | |
| 96 | | | St-293 | | | | | | | | | Yes | No | | | | | | | | | | | |
| 97 | | | St-294 | | | | | | | | | | | | | | | | | | | | Left | Away from R-11 |
| 98 | | | St-796 | | | | | | | | | Yes | Yes | | | | | | | | | | Right | Away from St-307 |
| 99 | | | St-802 | | | | | | | | | | | | | | | | | | 1 | | | |
| 100 | | | St-801 | | | | | | | | | | | | | | | | | | 1 | | Right/Lerft | |
| 101 | | | St-793 | | | | | | | | | | | | | | | | | | | | Left | Towards St-800 |
| 102 | | NT2 F-8/2 | St-120 | | | | | | | | | | | | | | | | | | | | Left | Away from St--119 |
| 103 | | | St-119 | | | | | | | | | | | | | | | | | | 1 | | Right/Lerft | |
| 104 | | | St-275 | 1 | | | | | | | | | | | | | | | | | 1 | | Right/Lerft | |
| 105 | | | St-806 | | | | | | | | | | | | | | | | | | | | Right/Lerft | |
| 106 | | | St-120/A | | | | | | | | | | | | | | | | | | | | Right/Lerft | |
| 107 | | | St-804 | | | | | | | | | | | | | | | | | | 1 | | Right/Lerft | |
| 108 | | | St-805 | | | | | | | | | | | | | | | | | | 2 | | Right/Lerft | |
| 109 | | | St-119/A | | | | | | | | | | | | | | | | | | | | Left | Away from St--119/B |
| 110 | | NT2 F-8/3 | St-810 | | | | | | | | | | | | | | | | | | | | Left | Towards St-811 |
| 111 | | | St-811 | | | | | | | | | | | | | | | | | | 1 | | Right | Towards St-812 |
| 112 | | | St-812 | | | | | | | | | | | | | | | | | | | | Right | Away from St-811 |
| 113 | | | St-808 | | | | | | | | | | | | | | | | | | | | Right | Towards St-809 |
| 114 | | | St-809 | | | | | | | | | | | | | | | | | | | | Right | Away from St-808 |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANA L CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|----------------------|---------------------------------------|--------------------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|--|-------|------------|--------------------|----------------------|-----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|
| 115 | | | R-2/A | | | | | | | | | | | | | | | | | | | | Left | Away from R-2 |
| Manjakuppam Feeder 7 | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | MKM5 P-01/HT,MKM7 P-01/HT,MKM7 P-01/I | MKM7 P-01/HT | ST-360 | | | | 1 | | 4 | | 6 | | | 7 | | | | | | | 6 | | RIGHT/LEFT | Towards ST-351 |
| 2 | | MKM7 P-01/HT | R-25 | | | | | | | | | | | | | | | | | 1 | | | RIGHT | Towards R-26 |
| 3 | | MKM7 P-01/HT | R-26 | | | | | | 2 | | | | | | | | | | | 2 | | | RIGHT/LEFT | Towards ST-360 |
| 4 | | MKM7 P-01/HT | R-29 | | | | | | 2 | | 6 | | | | | | | | | | 1 | | RIGHT/LEFT | Towards ST-390 |
| 5 | | MKM7 P-01/HT | ST-390 | | | | | | | | | | | | | | | | | | 1 | | LEFT | Towards ST-391 |
| 6 | | MKM7 P-01/HT | ST-391 | | | | | | | | | | | | | | | | | | | | LEFT | |
| 7 | | MKM7 P-01/HT | ST-392 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 8 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-394 | | | | | | | | | | | | | | | | | | 4 | | RIGHT/LEFT | Towards ST-395 |
| 9 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-395 | | | | | | | | 3 | YES | | | | | | | | | 1 | | RIGHT | |
| 10 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-397 | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | Towards ST-398 |
| 11 | | MKM7 P-01/HT | ST-398 | | | | | | | | | | | | | | | | | | | | RIGHT | Towards ST-399 |
| 12 | | MKM7 P-01/HT | ST-399 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-404 |
| 13 | | MKM7 P-01/HT | ST-404 | | | | | | | | | | | | | | | | | | 2 | | RIGHT/LEFT | Towards ST-403 |
| 14 | | MKM7 P-01/HT | ST-403 | | | | | | | | | | | | | | | | | | | | RIGHT | Towards ST-402 |
| 15 | | MKM7 P-01/HT | ST-402 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 16 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-396 | | | | | | | | | YES | | | | | | | | | 2 | | RIGHT/LEFT | Towards ST-407 |
| 17 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-407 | | | | | | | | | | | | | | | | | | 4 | | RIGHT/LEFT | Towards ST-409 |
| 18 | | MKM7 P-01/HT | ST-409 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-410 |
| 19 | | MKM7 P-01/HT | ST-410 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 20 | | MKM7 P-01/HT | ST-411 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-412 |
| 21 | | MKM7 P-01/HT | ST-412 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | |
| 22 | | MKM7 P-01/HT,MKM7 P-01/4 | R-29/A | | | | | | 1 | | 5 | YES | | | | | | | | 2 | 2 | | RIGHT | Towards ST-415 |
| 23 | | MKM7 P-01/HT,MKM7 P-01/4 | ST-415 | | | | | | | | | | | | | | | | | | 2 | | RIGHT | |
| 24 | | MKM7 P-01/HT | ST-389 | | | | 1 | | 1 | | | | | | | | | | | | 1 | | | Towards ST-387 |
| 25 | | MKM7 P-01/HT | R-28 | | | | | | 2 | | | | | | | | | | | 1 | | | RIGHT/LEFT | Towards ST-408 |
| 26 | | MKM7 P-01/HT | ST-408/A | | | | | | 4 | | | | | | | | | | | | 5 | | RIGHT/LEFT | Towards ST-442/A |
| 27 | | MKM7 P-01/HT | ST-442/A | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | Towards ST-437 |
| 28 | | MKM7 P-01/HT | ST-437 | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | |
| 29 | | MKM7 P-01/HT | ST-442 | | | | | | | | | | | | | | | | | | 1 | | LEFT | Towards ST-443 |
| 30 | | MKM7 P-01/HT | ST-410/A | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 31 | | MKM7 P-01/HT | ST-412/A | | | | | | | | | | | | | | | | | | 1 | | RIGHT | |
| 32 | | MKM7 P-01/HT | ST-416/A | | | | | | | | | | | | | | | | | | 3 | | RIGHT/LEFT | |
| 33 | | MKM7 P-01/HT | ST-418 | | | | | | | | | | | | | | | | | | | | LEFT | |
| 34 | | MKM7 P-01/HT | ST-422 | | | | | | | | | | | | | | | | | | 2 | | RIGHT/LEFT | |
| 35 | | MKM7 P-01/HT | ST-423 | | | | | | | | | | | | | | | | | | 1 | | | |
| 36 | | MKM7 P-01/HT | ST-426 | | | | | | | | | | | | | | | | | | 1 | | LEFT | Towards ST-429 |
| 37 | | MKM7 P-01/HT | ST-429 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-424 |
| 38 | | MKM7 P-01/HT | R-27 | | | | | | | | | | | | | | | | | 1 | | | RIGHT/LEFT | Towards ST-444 |
| 39 | | MKM7 P-01/HT | ST-444 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-445 |
| 40 | | MKM7 P-01/HT | ST-445 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-446 |
| 41 | | MKM7 P-01/HT | ST-446 | | | | | | | | | | | | | | | | | | 2 | | RIGHT | Towards ST-450 |
| 42 | | MKM7 P-01/HT | ST-450 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-452 |
| 43 | | MKM7 P-01/HT | ST-452 | | | | | | | | 3 | | | | | | | | | | | | RIGHT/LEFT | Towards ST-453 |
| 44 | | MKM7 P-01/HT | ST-453 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 45 | | MKM7 P-01/HT | ST-447 | | | | | | | | | | | | | | | | | | 2 | | RIGHT/LEFT | Towards ST-448 |
| 46 | | MKM7 P-01/HT | ST-448 | | | | 1 | | 1 | | | | | | | | | | | | 1 | | LEFT | Towards ST-449 |
| 47 | | MKM7 P-01/HT | ST-454/A | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-464 |
| 48 | | MKM7 P-01/HT | ST-464 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-465 |
| 49 | | MKM7 P-01/HT | ST-465 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-468 |
| 50 | | MKM7 P-01/HT | ST-468 | | | | | | 1 | | 2 | | | | | | | | | | | | LEFT | Towards ST-469 |
| 51 | | MKM7 P-01/HT | ST-469 | | | | | | | | | | | | | | | | | | | | RIGHT | Towards ST-470 |
| 52 | | MKM7 P-01/HT | ST-470 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-472 |
| 53 | | MKM7 P-01/HT | ST-472 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-475 |
| 54 | | MKM7 P-01/HT | ST-475 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | |

| S.NO | DRAWING NO. | MAP SHEET NO. | STREET NO.&Name | TEMPLE | CHURCH | MOSQUE | SCHOOL | HOSPITAL | VENDORS | VENDORS NAME | RAMPS | DRAINS | | TREES | DENSE AREA | HIGH ACTIVITY AREA | MAJOR RIVER CROSSING | RIVER/CANAL CROSSING | RAILWAY CROSSING | MAJOR ROAD CROSSING | MINOR ROAD/STREET CROSSING | ROAD CUTTING (YES/NO) | CABLE TRENCH (LEFT SIDE, RIGHT SIDE) | ROAD REFERENCE |
|------|-------------|--------------------------|-----------------|--------|--------|--------|--------|----------|---------|--------------|-------|--------|-----|-------|------------|--------------------|----------------------|----------------------|------------------|---------------------|----------------------------|-----------------------|--------------------------------------|------------------|
| 55 | | MKM7 P-01/HT | ST-476 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-480 |
| 56 | | MKM7 P-01/HT | ST-480 | | | | | | | | | | | | | | | | | | | | LEFT | Towards ST-481 |
| 57 | | MKM7 P-01/HT | ST-481 | | | | | | | | | | | | | | | | | | | | LEFT | |
| 58 | | MKM7 P-01/HT,MKM7 P-01/3 | ST-466 | | | | | | | | | | | | | | | | | | 2 | | RIGHT/LEFT | Towards ST-467 |
| 59 | | MKM7 P-01/HT,MKM7 P-01/3 | ST-467 | | | | | | | | | | | | | | | | | | 2 | | RIGHT/LEFT | |
| 60 | | MKM7 P-01/HT,MKM7 P-01/2 | ST-454 | | | | | | 1 | | 2 | | YES | | | | | | | | 6 | | RIGHT/LEFT | Towards ST-456 |
| 61 | | MKM7 P-01/HT,MKM7 P-01/2 | ST-456 | | | | | | | | 6 | | | | | | | | | | 4 | | RIGHT/LEFT | Towards ST-456/A |
| 62 | | MKM7 P-01/HT | ST-456/A | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | Towards ST-463 |
| 63 | | MKM7 P-01/HT | ST-462 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | |
| 64 | | MKM7 P-01/HT | ST-463 | | | | | | | | | | | | | | | | | | | | RIGHT | Towards ST-460 |
| 65 | | MKM7 P-01/HT | ST-460 | | | | | | | | | | | | | | | | | | 1 | | RIGHT | Towards ST-452 |
| 66 | | MKM7 P-01/HT | ST-452/A | | | | | | 2 | | | | | | | | | | | | 2 | | RIGHT | Towards ST-433 |
| 67 | | MKM7 P-01/HT | ST-433 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 68 | | MKM7 P-01/HT | ST-483 | | | | | | | | | | | | | | | | | | 2 | | LEFT | Towards ST-486 |
| 69 | | MKM7 P-01/HT | ST-486 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 70 | | MKM5 P-01/1 | ST-355 | | 1 | | | | | | | | YES | | | | | | | | 2 | | RIGHT/LEFT | |
| 71 | | MKM5 P-01/1 | ST-572 | | | | | | | | 3 | | YES | | | | | | | | 1 | | RIGHT/LEFT | |
| 72 | | MKM5 P-01/1 | ST-573 | | | | | | | | 2 | | YES | | | | | | | | 2 | | RIGHT/LEFT | |
| 73 | | MKM7 P-01/1 | ST-574 | | | | | | 1 | | | | YES | | | | | | | | | | LEFT | |
| 74 | | MKM7 P-01/1 | ST-575 | | | | 1 | | | | | | | | | | | | | | 1 | | | |
| 75 | | MKM7 P-01/1 | ST-388 | | | | 1 | | | | | | YES | | | | | | | | | | LEFT | Towards ST-576 |
| 76 | | MKM7 P-01/1 | ST-576 | | | | | | 1 | | | | | | | | | | | | | | RIGHT | |
| 77 | | MKM7 P-01/1 | ST-578 | | | | | | | | | | YES | | | YES | | | | | 2 | | RIGHT/LEFT | |
| 78 | | MKM7 P-01/2 | ST-580 | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | |
| 79 | | MKM7 P-01/2 | ST-581 | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | |
| 80 | | MKM7 P-01/4 | ST-583 | | | | | | | | | | YES | | | | | | | | | | | |
| 81 | | MKM7 P-01/4 | ST-408 | | | | | | | | 3 | | | | | | | | | | | | RIGHT/LEFT | Towards ST-417 |
| 82 | | MKM7 P-01/4 | ST-417 | | | | | | | | | | | | | | | | | | 1 | | RIGHT/LEFT | |
| 83 | | MKM7 P-01/4 | ST-586 | | | | | | | | | | | | | | | | | | | | LEFT | |
| 84 | | MKM7 P-01/4 | ST-588 | | | | | | | | | | | | | | | | | | | | RIGHT | |
| 85 | | MKM7 P-01/4 | ST-414 | | | | | | | | | | YES | | | | | | | | | | RIGHT/LEFT | |
| 86 | | MKM7 P-01/4 | ST-413 | | | | | | | | | | | | | | | | | | | | LEFT | |

Annexure 3 - Public Consultation Meeting at Cuddalore

Enclosure 1
Minutes of Meeting

Minutes of Public Hearing Meeting held on 30.09.2015 @ 10.30Hrs. in
“Vanniyar Thirumana Mandapam” Cuddalore regarding CDRRP.

The public hearing meeting was conducted by N-Arc, under the presidency of the District collector Thiru. S. Sureshkumar, IAS., on 30.09.2015.

The Superintending Engineer, Cuddalore Electricity Distribution Circle/Cuddalore welcomed all the participants. Superintending Engineer gave a brief speech about the CDRRP scheme.

A slide show was arranged to show the extent of damages occurred due to Thane Cyclone on 30.12.2011 & how it was restructured by mobilizing the TANGEDCO staff from all over the state.

Further, the benefits of conversion of the OH lines to UG cables were explained

- 1) How the damages can be avoided during natural disaster.
- 2) How accidents can be avoided.
- 3) How the narrow street will appear after laying UG cables.
- 4) Traffic hindrances will be avoided due to erection of UG cable.
- 5) Interruption of supply will be reduced considerably.
- 6) How environment is safeguarded, by chance of growing more trees, which has to be cleared if OH line exists.

Revenue District Officer

Gave a speech on how the CDRRP scheme is more important and by implementing the scheme, electrical accidents, interruption can be avoided and requested that the public should Co-operate for the implementation of the scheme.

Cuddalore, Municipal Chairman

He requested to implement the project area by area (i.e) to complete the work fully in one area and then to go for the other to avoid hindrance to public.

N-Arc consulting: Team leader Mr.Tikko expressed that the survey process was done for 7 months. By implementing the conversion of OH lines to UG cables, the supply would be more reliable and people would not be affected by the disaster if any in future.

Also the town would become more beautiful, secure and safe. The project is implemented by the financial support of World Bank, so as to reduce the risk during the disaster.

Further, explained the RMS ring main system, by which if supply interruption occurs in one DT it would be given by alternative routes.

By implementing the project OH line cut can be avoided, so that accident can be avoided.

Also, theft of energy will be avoided.

Line loss in OH line transmission will be avoided and also reduced.

Also, safety & reliable power supply is possible.

The proposed UG line will be designed after considering the existing TWAD, PWD, highways BSNL & other private communication networks.

By the implementation of the scheme indirect employment is also possible. He requested the public to Co-operate while implementation of project.

He requested the public organization to raise their doubts.

1) Thiru. M. Nizamudeen, General Secretary Tamil Nadu Consumer Federation (GSTFET)

- a) What is the impact of project on environment.
- b) What safety aspect is provided when water logs occurs during rainy season.
- c) How far it would create hindrance to the public while implementation.
- d) The project may be handed over to some NGO's, so that the fault in the scheme may be rectified.

2) Thiru. Balasubramaniyan, District Co-Ordinator Federation Consumer Organization, Nellikuppam

He emphasized that the red paint may be laid on the places where the UG cable runs so as to alert the public on safety aspect.

3) Thiru. Raj Mohan, FEDCOT

He raised the doubt about the area of implementation of project. Whether the project is implemented in whole district or in coastal area of Cuddalore or Cuddalore Town. The scheme should have been implemented earlier. Since, Thane has taken place nearly 4 years ago.

NGOS may be included in the scheme.

4) Thiru. Arulselvam, Tamil Nadu Consumer Education and Development Foundation (TAMCED-Foundation)

Raised a doubt whether the technical feasibility report has been given on social environment assessment.

5) Thiru. Manokaran, Manjakuppam

1) How the damages like road cuts, done during the implementation will be restored.

2) How other networks line, breakage water lines, communication lines damages will be avoided.

6) Thiru. Venkatramakrishnan, Fed cot- Joint Secretary

Whether the encroachment will be cleared and the cables will be laid or the cables will be laid in the middle of the road.

7) Thiru. Ganesan, Koothapakkam Angeragan Consumer Saftey Organisation

Whether the cables used for laying in underground would resist the natural calamities, disaster (or) it would create accidents.

8) Thiru. Harikrishnan

UG sewage system not yet completed in Cuddalore and public are facing hindrances. Hence the hindrance to public should be reduced.

9) Thiru. Globe: CPI

The detailed project should be given to the political parties, public organization etc.,. It should be clear.

10Thiru. Kumaran: CONFET

The cable used should be of all the international standards. So that it public will not be affected by electricity.

11) Thiru. Sadupalli:

The trenches may be dug manually and not using machineries and the work should be completed within 4 years.

12) Thiru. R.Elangovan: MSSRF

Standards of laying cables should be followed. Concrete structures should be used.

SPEECH GIVEN BY DISTRICT COLLECTOR

Cuddalore District is more affected by the natural disasters. Whenever the natural calamities occurs, in our state Cuddalore is more affected. So, as a precautionary measure in order to reduce the damages, the CDRRP project is implemented in Cuddalore.

Electricity has become a part of people if there is no electricity, people is affected immediately as water supply is affected. Cuddalore people have realized more during "Thane" how electricity is more important & how employees of TANGEDCO all over Tamilnadu came over to Cuddalore to restructure the network.

So, in order to avoid the above situation, with the help of World Bank Fund of Rs.218 crores, over head lines are converted to underground cables. This is done in Cuddalore Town and Cuddalore coastal areas.

The survey of network has been completed.

In this project, 7 feeders in Cuddalore town emanating from Semmankuppam SS, Capper Hills SS and Nathapattu SS are to be converted into UG cables.

This project will be implemented at time of less public movement and during night hours. Also, in the places of schools, colleges & worship places, safety measures would be considered. Environment will not be affected.

During the implementation of project the public will be informed through press news, about the project. Hence public may render their co-operation during the implementation of the project.

Explanation given by TANGEDCO Officials:

The CDRRP project is implemented in Cuddalore coastal areas and Cuddalore Town.

This project is implemented in 7Nos 22 KV feeders with 33Kms of HT line and 1300Km LT lines.

The project is implemented in 3 phases in the following feeders.

- | | | |
|-----------------------|----------------------|--------------------|
| 1) Pentesia 22KV | 2) Vandipalayam 22KV | 3) Suthukulam 22KV |
| 4) Cuddalore-NT 22 KV | 5) Manjakuppam 22KV | 6) Alpettai 22KV |
| 7) Suthukulam 22KV | | |

This project is implemented to avoid damages during natural disaster, to avoid interruption, to avoid electrical accidents and to avoid human loss.

While implementation the area where project work is done will be informed to public through newspapers.

Road cut, water line damages occurs if any the rectification works will be carried out by TANGEDCO or its contractor.

Other Department help are required during implementation of project. OH lines will be removed only after confirmation of successful project completion.

Explanation given by N-Arc about the project:

- 1) Survey work has been done completely and report to be submitted for review of TANGEDCO.
- 2) The proposed network has been framed after considering the existing networks of water works, communication sewage system and highways so as to avoid hindrances during implementation.
- 3) The UG cable will be laid 1.2 meters below the ground in trenches.
- 4) RMS Ring Main System would be provided so as to provide alternate supply in interruption period.
- 5) Barriers would be provided in the places of work.

- 6) Cleanliness would be maintained.
- 7) Safety precautions will be educated to people under work.
- 8) Environmental social management plan will be framed.
- 9) Damages like road cut, water line breakages will be rectified by contractor.
- 10) Insulation level will be more. UPC duct will be provided in road crossing.

List of participants:

1. Thiru. S.Sureshkumar I.A.S, District Collector, Cuddalore District, Cuddalore
2. Tmt. Umamageshwari, R.D.O., Cuddalore
3. Thiru. Kumar, Municipal Chairman, Cuddalore
4. Er. N.Sivanandam Superintending Engineer /CEDC/Cuddalore
5. Er.G.Kamaraj, Executive Engineer/O&M/Cuddalore

All AEEs/O&M of Cuddalore Division
All AEs, JEs/O&M of Cuddalore Division
Representatives of Consumer Organisation
Stake holders and Public.

Superintending Engineer
CEDC/Cuddalore

Public notice for public Awareness programme invitation by TANGECO Cuddalore



தமிழ்நாடு மின் உற்பத்தி மற்றும் பகிர்மான கழகம்
கடலூர்



Mis. N. Arc - New Delhi

விழிப்புணர்வு கூட்ட அழைப்பிதழ்

நாள்: **30-09-2015 புதன்கிழமை** காலை 10.30 மணியளவில்
இடம்: **வன்னியர் திருமண மண்டபம்**, போடிச்செட்டித் தெரு, திருப்பாதிரிப்புலியூர், கடலூர்-2.

அன்புடையீர்! வணக்கம்.

“தானே புயல் பாதிப்பினை கருத்தில் கொண்டு தமிழக அரசின் உத்தரவின் அடிப்படையில் தமிழ்நாடு மின் உற்பத்தி மற்றும் பகிர்மான கழகத்தால் கடலூர் நகர்ப்பகுதிகளுக்கு தற்போது மேல்நிலை மின்பாதைகள் மூலம் வழங்கப்படும் மின் விநியோகத்தை புதைவட மின்பாதைகளாக **(Under Ground Cable)** மாற்றி அமைத்து மின்விநியோகம் வழங்க அனுமதிக்கப் பட்டுள்ளது.

இது குறித்து சுற்றுச்சூழல் மற்றும் சமூக விழிப்புணர்வு கூட்டம் வரும் **30-09-2015** அன்று காலை 10.30 மணிக்கு கடலூர், திருப்பாதிரிப்புலியூர், போடிச்செட்டித் தெரு, **வன்னியர் திருமண மண்டபத்தில்** மதிப்பிற்குரிய திரு. **சீ.சுரேஷ்குமார்** கடலூர் மாவட்ட ஆட்சித்தலைவர் அவர்கள் தலைமையில் புதைவட அளவைப்பணி மேற்கொண்டு வரும் புதுவெல்லியை சேர்ந்த **"என் ஆர்க் நிறுவனம்"** மூலம் விழிப்புணர்வு கூட்டம் நடத்தப்பட உள்ளது.


இந்த விழிப்புணர்வு கூட்டத்தில் ஆர்வமுடன் கலந்து கொண்டு தங்களின் மேலான கருத்துக்களை தெரிவிக்குமாறு அன்புடன் கேட்டுக்கொள்கிறோம்.

இங்ஙனம்,
பொறிஞர். **ந.சிவானந்தம்**, M.E., MBA., M.I.E.,
மேற்பார்வை பொறியாளர்
கடலூர் மின் பகிர்மான வட்டம்,
கடலூர்.

Annex: 4

Enclosure: 3

Appreciation & Suggestion letter from Cuddalore district consumer & environment welfare protection sangam.

| மரம் நடுவோம் ! | | சுற்று சுழலை பாதுகாப்போம் ! | |
|---|---|-----------------------------|----------------|
|  | | | |
| கடலூர் மாவட்ட நுகர்வோர் மற்றும் சுற்றுச் சூழல் நல பாதுகாப்பு சங்கம் CUDDALORE DISTRICT CONSUMER & ENVIRONMENT WELFARE AND PROTECTION SANGAM பதிவு எண் : 30/2006/Cud. (அரசியல் சார்பற்றது) | | | |
| மாவட்ட அலுவலகம் : 15, T.N.C.S.C. நகர், கோண்டூர் அஞ்சல், கடலூர்-607 006. போன்: 04142-225564 | | | |
| மாவட்ட தலைவர் | மாவட்ட செயலாளர் | மாவட்ட பொருளாளர் | |
| திரு.கே.எஸ்.ஜக்கரியாஸ் | திரு.இரா.சாரங்கபாணி, பி.ஏ. | திரு.கோ.சாயிராம், பி.ஏ. | தேதி 30-9-2015 |
| மாவட்ட துணைத்தலைவர்கள் எம்.கே.பாண்டித்துரை வி.திருஞானசேகர் வி.சந்திரசேகரன் | பெறுநர் மாவட்ட ஆட்சித்தலைவர் அவர்கள், கடலூர் மாவட்டம், கடலூர் - 607001. | | |
| மாவட்ட இணைச்செயலாளர்கள் ஜி.ரவிச்சந்திரன் இரா.இராதாகிருஷ்ணன் கே.நாராயணன் | அன்புடையீர் வணக்கம் ! | | |
| சங்க ஆலோசகர் கோ.சேகர் | பொருள் : கடலூர் வட்டம் - மின்பகிர்மான கழகம் - மேல் நிலை மின்பாதை - புதைவடமாக மாற்றி அமைத்தல் சம்பந்தமாக. | | |
| நிகழ்ச்சி ஒருங்கிணைப்பாளர் இரா.சுந்தரமூர்த்தி | பார்வை : கடலூர் மின்பகிர்மானக்கழக கடித எண் ஆ.எண் 613 / 15 நாள் 23-9-2015. | | |
| செயற்குழு உறுப்பினர்கள் வா.சா.திலகம், எம்.பி.ஏ பி.எத்திராஜாஜு கே.இராதாகிருஷ்ணன் கே.இராஜேந்திரன் எஸ்.ஞானசேகரன் எஸ்.பாபு டி.தமிழ்ச்செல்வன், பி.ஏ கே.கோபாலகிருஷ்ணன் | கடலூர் நகர்ப்பகுதிகளுக்கு UNDER GROUND CABLE வழியாக மின்விநியோகம் செய்யப்படுவது வரவேற்க வேண்டிய நிகழ்வாகும். இதன்மூலம் ஏற்கெனவே விசிய தானே புயல், மற்றும் சுனாமி போன்று பிற்காலங்களில் பாதிப்பு ஏற்படுமாயின் அதன்மூலம் பாதிக்கப்படுவது தடுக்கப்பட்டு, பாதுகாக்கப்படுவார்கள், என்பது எல்லோரும் ஏற்கும் உண்மையாகும். மின்விநியோகத்தில் வழித்தட இழப்பு தற்பொழுது இந்தியாவில் 30 விழுக்காடாக உள்ளது, அது தவிர்க்கப்பட்டாலே, மின் அதிகரிப்பு விழுக்காட்டை சமாளித்து மின்தட்டுப்பாடு இல்லாத நாடாகமாறிவிடும். எனவே கடலூரில் மேற்படி மின்வழித்தடங்களில் ஏற்படும் இழப்புகள் இந்த முறை மூலம் நிவர்த்தி செய்யப்படுமானால் அதன் மூலம், மின் தடைகள் நேரம் குறைய வாய்ப்புகள் உள்ளது. | | |


Annex: 4
Enclosure: 3

-2-

மேலும் மேற்படி மின்விநியோக முறையில் பழுது ஏற்படுமாயின், தற்பொழுதுள்ள முறையில் உடனுக்குடன் மின்பகிர்மானக் கழகம் சரி செய்வது போல, தரைக்கு கீழ் செல்லும் மின் விநியோகத்தின் மூலமும் மின்சாரப் பழுதுகள் சரி செய்வதற்கு உரிய நவீனமுறைகளை கையாண்டு, நிர்வாகம் நடவடிக்கை மேற்கொண்டு பொதுமக்களிடையே தொடர்ந்து நன்மதிப்பை பெறவேண்டும், என எங்களது சங்கத்தின் சார்பாக அன்புடன் கேட்டுக்கொள்கிறேன்.

இடம் : கடலூர்,
நாள் : 30-9-2015.

இவண்,
மாவட்ட சங்க நிர்வாகிகள் சார்பாக,


30/9/15

கீரா.சாரங்கபாணி, கி.உ.
செயலாளர்
கடலூர் மாவட்ட நுகர்வோர் மற்றும்
சுற்றுச்சூழல் நலப் பாதுகாப்பு சங்கம்,
மீதநிதி : கடலூர் மாவட்ட நுகர்வோர் குழைந்த நீதிமன்றம்
Email : sarangapani@yahoo.com
No. 15, T.N.C.S.C. தகவ்.
கோண்டு அஞ்சல், கடலூர்-607 000, தமிழ்நாடு.

Annex 4 . A. Excerpts of the consultation meeting Cuddalore

PLACE - CUDDALORE

DATE: 01/10/2015

| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
|------|---------------------|---|--|
| 1 | Mr.Nizamudhien | Describe about the safety measures and enviromental effect while executing the project. Public having problem while executing the drainage work so take necessary action to avoid such impacts in this project. Explain about the cable route identification and safety measures. Only 30% of people called for this fuction, invite more people for awareness program. Already underground system available in chennai and take the survey of difficulties in this system and avoid the such items here. | We had collected information and safety measures in this first stage of scheme and ensuring the execcute the project without public disturbance. We had distribute the our Environmental and Social highlighted points for your ready reference, every 100mtr. cable mark identification shall be available and trench depth is maximum 1.2mtr. and underground cabling is safety and same system available in chennai. Environmental and Social experts are collected the details and this will incorporate in their report and also PMU consultant also ensure the same. |
| 2 | Mr.Bala Subramanian | Cuddlore is cyclone affected area and we are welcoming this project for our area. Execute the project without public disturbance and after installing the cable mark the identification marl in that route and explain about the | Thanks for your appreciation and support. We shall provide cabke route marker in complete cable route with 100mtr. Interval and we had considered the public saftey and minimize the disturbance. |

| Annex 4 . A. Excerpts of the consultation meeting Cuddalore | | | |
|---|------------------|--|--|
| | | | |
| PLACE - CUDDALORE | | | DATE: 01/10/2015 |
| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
| 3 | Mr.Maruthavaanan | There will be the chance to increase the sea level upto 2 feet and chance to sea water will reach upto 1/4kM fro the present level. Provide concrete / GI pipe while cable depth more than 3 1/2 feet. Consider all this in this scheme. | Thanks for your suggestion and we will incorporate the same in our report. We shall consider concrete / GI / DI pipe for road crossing and railway crossing with spare. Our cable trench is maximum 1.2 Mtr and buried cable trench. |

| Annex 4 . A. Excerpts of the consultation meeting Cuddalore | | | |
|---|-------------|---|---|
| PLACE - CUDDALORE | | | |
| | | | DATE: 01/10/2015 |
| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
| 4 | Mr.Ramkumar | <p>We are expecting this project from the Tamilnadu Honourable Chief Minister announced in assembly. As per your statement survey works completed in 6 months and work will be start on after 6 months. Cyclone may come any time so we request you to execute the scheme as much possible. In cuddlore, monsoon period will start this month and you consider all those thinks and execute the work. Explain the area covered in this scheme. In last SE meeting, TANGEDCO told survey works not completed but now you are telling work completed. Provide the correct information. Endowment committee cost to be added in your report.</p> | <p>Thanks for your suggestion. We initimated the field workshad completed and draft report submitted to TANGEDCO for comments. We shall speedup the work as much possible. This scheme covers cuddlore town and coastal area with seven areas electrical line. It covers 333KM HT line and 1300 LT line. Presently we designed the cable route without distrubting the other public services by the coordination with other departments and damages will be immediately recovered by TANGEDCO / Contractor.We had consider the Endowment committee cost also.</p> |

| Annex 4 . A. Excerpts of the consultation meeting Cuddalore | | | |
|---|--------------|---|--|
| PLACE - CUDDALORE | | DATE: 01/10/2015 | |
| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
| 5 | Mr.Kannan | Prepare environmental and social plan for analysing the public affects. In the time of execution, display the Engineer / Incharge contact number and details then public sahl be contact them if there is inconvenience. | Thanks for your suggestion. We had prepared the Enviromental & Social report by our experts and we shall submit the same. We shall incorportare your suggestion in our report and in the time of execution, contractor shall display the company and work incharge details in working place. |
| 6 | Mr.Manimaran | We are welcoming this project. We have to consider the reduce the he social cost and it is less than project cost. Provide the escape plan from the time of cyclone and describe action to be taken by the officers and public. | Thanks for your suggestion and support. Now only survey works are completed and necessary arrangement to be taken in the next stages. We shall incorporate your suggestion in our report. |

| Annex 4 . A. Excerpts of the consultation meeting Cuddalore | | | |
|---|-------------------|--|---|
| | | | |
| PLACE - CUDDALORE | | | DATE: 01/10/2015 |
| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
| 7 | Mr.Thirumalavanan | We have bad experience in the other public service trenches. Due to improper backfilling, public have disturbance while travelling and explain about the project execution by area wise or complete cuddlore in the same time. | Thanks for your suggestion. Contractor shall execute the project package wise also area wise and backfilling shall be done properly after cable laying with considering avoid public day to day activities. Already telephone, water and drainage lines are going underground and this is challenge to do our execution wiithout disturbing the other public service and we request your support while execute the project. |

| Annex 4 . A. Excerpts of the consultation meeting Cuddalore | | | |
|---|------------|--|--|
| | | | |
| PLACE - CUDDALORE | | | DATE: 01/10/2015 |
| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
| 8 | Mr.Ganesan | We are welcoming this project. we have doubt on the saftey of the underground cabling system while road crossing, bridge crossing and feasibility of the cable in cyclone. | Thanks for your suggestion and support. Underground cabling is more safer compared to Overhead, we had proposed pipes for road crossing ,railway crossing and bridge crossing. We had proposed our cable trench depth is 1.2Mtr and consider the safety measures in this system. |
| 9 | Mr.Baskar | Execute the work as much possible, consider the raining sesason and backfilling s to be done without delay. | Thanks for your suggestion and we shall consider the same. |
| 10 | Mr.Rajan | We are welcoming this project and circulate the plan details to welfare organization for execute project in proper manner and in time. | Thanks for your suggestion. In this first stage we had completed survey works and we shall execute the project with considering technical experts and welfare organization ideas and completing the project as much earlier. |

Annex 4 . A. Excerpts of the consultation meeting Cuddalore

PLACE - CUDDALORE

DATE: 01/10/2015

| S.No | Name | Suggestion / Question | TANGEDCO / NARC Reply |
|------|-----------------|---|---|
| 11 | Mr.Periyasamy | We are welcoming this project and execute the project with fully transparent and international standards. | Thanks for your suggestion. We had consider the international standards and client specification. |
| 12 | Mr.Ramanujam | Maximum consider the manual excavation and backfilling to be completed as much possible. | Thanks for your suggestion. We had consider the same. |
| 13 | Mr.Maruthamuthu | In chennai and pondichery, no electrical line in the raining season and town has neat look. In the same reason we are welcoming the project here. | Thanks for your suggestion and support. |

Enclosure 5

Lists of participants attended

| <p> <u>"പ്രദേശ മണ്ഡലങ്ങളിലെ"</u> <u>കുടുംബശ്രീ മുഖേന നടപ്പിലാക്കുന്ന</u> <u>Coastal Disaster Risk Reduction Project (CDRRP)</u> <u>മുഖേന: മുൻനിർത്തി പ്രദേശ പഞ്ചായത്ത്, തൃശ്ശൂർ</u> <u>തീയതി: 30.09.2015 മുൻനിർത്തി 21:00 മണി വരെ</u> <u>സ്ഥലം: പാലക്കാട് 10:30 മണി</u> </p> | | | |
|---|--|---|--|
| ക്രമം | പേര് | മുൻനിർത്തി പങ്കെടുത്ത | താല്പരത |
| 1. | <p> <u>Dr. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> <u>9843848467</u> </p> | <p> <u>Dr. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> </p> | <p> <u>Dr. S. S. S. S.</u> </p> |
| 2. | <p> <u>R. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> <u>9442274892</u> </p> | <p> <u>Dr. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> <u>Dr. S. S. S. S.</u> </p> | <p> <u>Dr. S. S. S. S.</u> </p> |
| 3. | <p> <u>T. Sambandam</u> <u>SRS, Cuddalore.</u> </p> | | <p> <u>T. Sambandam</u> </p> |
| 4. | <p> <u>S. RAMESH BABU</u> <u>M.A.M.Ed MPhil</u> <u>FEDCOT-Director</u> <u>Education.</u> </p> | <p> <u>Fedcot-Education</u> <u>Director.</u> </p> | <p> <u>S. Ramesh Babu</u> <u>2019/11</u> </p> |
| 5. | <p> <u>M. Varghese</u> <u>Secretary</u> </p> | <p> <u>Fedcot Joint</u> <u>Secretary</u> </p> | <p> <u>M. Varghese</u> </p> |
| 6. | <p> <u>M. Muthu Krishna</u> </p> | <p> <u>No. 70, Muthu Krishna</u> <u>Kodur</u> </p> | <p> <u>M. Muthu Krishna</u> </p> |
| 7. | <p> <u>S. S. S. S.</u> <u>MSSRF</u> <u>Cell: 94865 15790</u> </p> | <p> <u>Dr. S. S. S. S.</u> <u>Sabangal Street</u> <u>Parsipattai</u> <u>Cuddalore Dist-18</u> <u>PIN-608 502</u> </p> | <p> <u>S. S. S. S.</u> </p> |
| 8. | <p> <u>S. S. S. S.</u> <u>FEDCOT</u> <u>Cell: 94456 44057</u> </p> | <p> <u>FEDCOT</u> </p> | <p> <u>S. S. S. S.</u> </p> |

| Sl. No. | English | Tamil | Signature |
|---------|--|---|----------------|
| 9. | P. Hariprasad Managing Director Shree - 29 N.B. Road | பி. ஹரிபிரசாத் நிர்வாகி சுரே - 29 N.B. ரோட் | P. Hariprasad |
| 10. | P. Radhika Shree 2nd Floor 4 | பி. ராஜிகா சுரே 2வது மா 4 | P. Radhika |
| 11. | M. | ம. | M. M. M. M. M. |
| 12. | K. | க. | K. K. K. K. K. |
| 13. | C. Krishnan Asst. Manager Kamman Pharma SIPCOT, And. | சி. கிருஷ்ணன் அஸி. மேனேஜர் காமன் ஫ார்மா சிப்கொட், அன்ட. | C. Krishnan |
| 14. | M. N. N. N. N. General Secy Tamil Nadu Consumer Federation (Consumer) No. 12, Doraikottai Road | ம. ந. ந. ந. ந. ஜெனரல் செக்ரட்டரி தமிழ்நாடு கன்சுமர் ஫ேடரேஷன் (கன்சுமர்) நா. 12, டோரைகோட்டை ரோட் | M. N. N. N. N. |

| Sl. no. | Onam | English Name | Onam |
|---------|---|--|--------------------|
| 16. | T. ARUNSELVAN. 9443737134 | Tamil Nadu Consumer Education Development (TANCEDO-FOUNDER) | T. Arun |
| 17. | Dr. R. Kae Nil General Secretary 766 766 7600 | Tamil Nadu Consumer Protection & Human Rights Organization Cuddalore. | R. Kae Nil |
| 18. | T. Sathya Kumar 9786 452 111 HT. SC. NO. 65 | Loyal Super Mall, C-7/1 Sripot Complex Kumbakonam Cuddalore. | T. Sathya Kumar |
| 19. | R. Velayudhan 95 66 31 78 66 HT. SC. NO. 77 | Farmer's Guild Sivamangalam Cuddalore - 5. | R. Velayudhan |
| 20 | P. Ganesan 9345451137 | 107 Boddichan Cuddalore | P. Ganesan |
| 21 | P. Ganesan | Angeragan Nigam Vengaloor Cuddalore | P. Ganesan |
| 22. | A. Jeyaraj | " | A. Jeyaraj |
| 23 | R. Balasubramanian | District Co-operative Food Corp Congo Nagar, Nellikuppam 9952507471. | R. Balasubramanian |
| 24 | S. Thirumanthirani | Consumer Organisation Nellikuppam. 2639352842 | S. Thirumanthirani |

| No. | Name | Address | Signature |
|-----|--|----------------------------|------------------|
| 25. | R. SIVAKUMAR All Consumer And Environment Organisation Thiruvallur - 999 4049170 | ACAO | R. Sivakumar |
| 26. | N. CHANDHASHEKAR | ACAO | N. Chandhashekar |
| 27. | P. Jaisankar . 9989751433. | J. Jaisankar | P. Jaisankar |
| 28. | S.D. PONGUNNAM SUDHAN POWER TRAM 9842352095 | SUDHAN POWER TRAM | S. D. Pongunnam |
| 29. | M. MURUGAN DEE TIRUPATI | - | M. Murugan |
| 30. | S. RAMMOHAN | S. Rammoohan | S. Rammoohan |
| 31. | M. Arjunan Electrical Superintendent Cuddalore Municipality | - | M. Arjunan |
| 32. | V. @ Bmvi CPI 2nd Division | CPI 2nd Division (CPI.) | V. @ Bmvi |
| 33. | A. | - | A. |

| Sl. No. | Name | Qualification | Signature |
|---------|-------------------|-----------------|----------------|
| 34. | P. | ... | ... |
| 35 | P. J. ... | ... | ... |
| 36 | S. Chandrasekaran | ... | ... |
| 37 | V. S. Kumaran | CONFET | V. S. Kumaran |
| 38 | D. Arulprakash | Fire Service | ... |
| 39. | ... | ... | ... |
| 40 | ... | ... | ... |
| 41. | D. ... | ... | ... |
| 42 | ... | ... | ... |
| 43 | G. S. ... | DINAMALAR (CNS) | G. S. ... |
| 44 | ... | ... | ... |
| 45 | ... | ... | ... |
| 46. | B. Vijayakumar | AEE / TWAD Rd | B. Vijayakumar |
| 47 | S. ARUN | ... | ... |

